

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/265/CIVIL/Mtc-I/2022-TS dated 21.09.2022

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;
Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: रिकॉर्ड रूम और सन कंट्रोल को विनाइल फ्लोरिंग प्रदान करना एन एमपीए अस्पताल में कांच की खिड़की के शीशे पर फिल्में
Name of work	: Providing vinyl flooring to the record room and sun control films to the glass window panes at NMPA Hospital
अनुमानित लागत / Estimated Cost	: Rs.1,05,851.00
ईएमडी / EMD	: Rs.2,500.00
खुलने की तिथि / Date of opening	: 28.09.2022
समापन अवधि / Completion Period	: 60 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **28.09.2022** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorised representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.


कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
खरखाव प्रभाग-I / Maintenance Division-I,

नव मैंगलोर पत्तन प्राधिकरण / **NEW MANGALORE PORT AUTHORITY**
सिविल इंजिनीरिंग विभाग / **DEPARTMENT OF CIVIL ENGINEERING**
अनुरक्षण प्रभाग -I / **MAINTENANCE DIVISION-I**
कोटेशन/QUOTATION No.5/265/CIVIL/Mtc-I/2022-TS dated 21.09.2022

BILL OF QUANTITIES

कार्य का नाम: रिकॉर्ड रूम और सन कंट्रोल को विनाइल फ्लोरिंग प्रदान करना एन एमपीए अस्पताल में कांच की खिड़की के शीशे पर फिल्मों

Name of work: Providing vinyl flooring to the record room and sun control films to the glass window panes at NMPA Hospital.

SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Providing and laying linoleum plain flooring or coloured 3.2mm thick sheet / tiles laid with an approved adhesive on sub floor stretching, cutting and fixing complete , including cost of materials, labour, complete as per specifications.	22.00	M2	693.00	15,246.00
2	Providing and fixing sun control cooling films of reputed brand, medium with 50% transparency to the sliding window glass panes free of bubbles and scratches, including cost of transportation, fixing, cutting, Tools & plants and all other incidental charges etc. complete as directed by the Department	90.00	M2	495.50	44,505.00
3	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in- charge. (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts,bolts, fasteners etc.) including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	85.00	Kg	500.00	42,500.00

4	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge.	0.50	M3	1274.00	637.00
5	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates.	0.50	M3	5926.00	2,963.00
Amount put to quotation (excluding GST) Rs. :					1,05,851.00
ADD: % ()					
Above the estimate amount put to quotation.					Rs.
LESS: % ()					
Below the estimate amount put to quotation					Rs.
Total Amount Rs.					
Rupees					

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR