



नव मंगलूर पत्तन प्राधिकरण
NEW MANGALORE PORT AUTHORITY
यांत्रिक अभियंता विभाग
Mechanical Engineering Department
इलेक्ट्रिकल इंजिनियरिंग डिविजन, पणंबूर, मंगलूर
Electrical Engineering Division
Panambur, Mangalore - 575010

E-mail: ele-section@nmpt.gov.in
GSTIN: 29AAALN0057A2ZG

Phone: 0824 2887750/740/738
Fax: 0824 2408200/2408300

No.8/3/2023/Ele. Dvn/EQ/01/01

Date: 10.01.2023

To,

Sir,

Sub:- NMPA-EE (E) - "Providing Changeover Switch and allied works for High Mast Towers installed at Railway Marshalling Yard" - Quotation invited - Reg.

Quotation in sealed covers superscribed as "Providing Changeover Switch and allied works for High Mast Towers installed at Railway Marshalling Yard" invited in accordance with the instructions to the Tendered Terms & Conditions as detailed below, may please be submitted addressed to "**The Executive Engineer (Elec.), Electrical Division, Administration Building, New Mangalore Port Authority, Panambur, Mangalore- 575010**" not later than **3.00 PM on or before 17.01.2023**. Quotation will be opened on the same day at 3.30 PM in the presence of the tenderers who wish to be present.

Sl. No.	Description of Work	Qty	Rate (Rs.)	Rate in words	Amount (Rs.)
1	Labour charges for laying of 3.5 C X 185 sq.mm size 1.1KV class XLPE UG cable in existing trench GI pipe/on wall/on pole/ stoneware pipe as required etc., complete.	175 mtrs			
2	Digging of trench of 1.2 Meter deep x 0.5 Meter wide, refilling the trench to the required ground level and consolidating etc., complete in Hard soil	175 mtrs			


3	Supplying and laying of double walled corrugated HDPE Pipe including all necessary connecting Sockets/ couplings/tees/bends/end caps of same materials in existing trench as per IS 14930 part-II suitable for drawing underground cables.	140 mtrs			
4	Supplying and making straight through cable joint with epoxy resin including ferrules and other jointing materials for 3.5Cx185 sq.mm XLPE insulated LT UG cable.	1 No.			
5	Supply of on-load 400A, 4P, Changeover Switch, AC-23A Duty, 415V, 50Hz, AC supply with metal enclosure of 1200x600x600x2 mm thickness CRCA sheet with base channel, powder coated outdoor type with all accessories complete.	1 No.			
6	Providing RCC/Stone masonry foundation for Changeover Switch having enclosure of 1200x600x600mm dimension. The foundation starts 300mm below the ground after making 100mm stone soling and height of the foundation 500mm above the foundation level and curing etc. and the panel should be stand on the four Stainless steel bolts (12mm x 6") and each bolt with four nuts & washers complete.	1 No.			
7	Installation and Commissioning of 400A, 4P Changeover Switch enclosure by terminating the required I/C cable & O/G cable	1 No.			
	Total				
	Applicable GST				
	Grand Total				

TERMS & CONDITIONS:

1. The rate quoted for the items shall be firm and F.O.R destination basis. Please note that NMPA is not issuing any concessional C or D forms.
2. The Tenderer shall submit Valid Electrical Contractor License and GST Registration Certificate along with their offer, without which the offer will be rejected.
3. Applicable GST will be paid as extra as per actual.

4. The time allowed for Providing Changeover Switch and allied works for High Mast Towers installed at Railway Marshalling Yard is **30 days** from the date of issue of work order.
5. Please note that no advance payment will be made. But payment will be made within 15 days after satisfactory completion of Work.
6. The Tenderers should quote their rates in figures as well as in words the amount tendered by them. The amount per each item should be worked out and requisite total should be given. All rates shall be quoted in proper form in the tender schedule enclosed. The rates quoted should be valid for **90 days**.
7. The Changeover Switch Panel, HDPE pipe & Straight through cable joint to be supplied should conform to the Technical Specifications and standards of IS.
8. The complete work of Providing Changeover Switch and allied works for High Mast Towers installed at Railway Marshalling Yard shall have guarantee period of **one year** after successful completion of work.
9. The Tenderer shall be responsible for making good of all the damages done during the work and has to employ skilled & competent workers for carrying out the work.
10. The Tenderer shall be responsible for taking precautionary measures for the safety of the workman working under them and the responsibility arising due to any mishap during the execution of work, the payment of any compensation etc., lies entirely on the part of the Contractor.
11. No tools, plant, Labour, equipment, transport, etc., required for the work will be supplied departmentally and contractor has to make his own arrangements.
12. The evaluation shall be done on the basis of total lowest value (L1) quoted. The GST element if any will not be considered for evaluation.
13. The acceptance of the tender will rest with competent authority of NMPA who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all of the tenders received without assigning any reason.
14. LIQUIDATED DAMAGES:
 - i. In case of delay in completion of the contract, liquidated damages (L.D) may be levied at the rate of 0.5% of the contract price plus applicable GST per week of delay, or part thereof subject to a maximum of 10 per cent of the contract price.
15. Department standard operating procedure will be shared with the successful bidder before commencing the work and an undertaking will be obtained for complying with the same. In case if the Contractor does have a defined SOP for carrying out the work, the same shall be scrutinized and approved by the Executive Engineer (E)-I for its applicability.

16. If the Tenderer after award of work/contract fail to execute the work in the specified allotted period, then the Tenderer shall be debarred for a period of three (3) years from participating for tenders at New Mangalore Port Authority.


Executive Engineer (E)
Electrical Division, NMPA

Seal and sign of Tenderer