

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजीनरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.3/232/CIVIL/Mtc-I/2022-TS dated 11.01.2023

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: एनएमपीए में घाट क्षेत्र के अंदर खाली कंटेनर यार्ड के प्रवेश द्वार पर जलापूर्ति पाइप की तत्काल मरम्मत
Name of work	: Urgent repairs to water supply pipe at the entrance of empty container yard inside the wharf area at NMPA
अनुमानित लागत / Estimated Cost	: Rs.76,000.00
ईएमडी / EMD	: Rs.1800.00
खुलने की तिथि / Date of opening	: 13.01.2023
समापन अवधि / Completion Period	: 7 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **13.01.2023** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorised representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

- 1.Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
- 2.Bank A/C No. 10205649448
- 3.IFSC Code: SBIN0002249
- 4.MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.


कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
खरखाव प्रभाग-I / Maintenance Division-I,

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I
कोटेशन/QUOTATION No.3/232/CIVIL/Mtc-I/2022-TS dated 11.01.2023

BILL OF QUANTITIES

कार्य का नाम: एनएमपीए में घाट क्षेत्र के अंदर खाली कंटेनर यार्ड के प्रवेश द्वार पर जलापूर्ति पाइप की तत्काल मरम्मत					
Name of work: Urgent repairs to water supply pipe at the entrance of empty container yard inside the wharf area at NMPA					
SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Cutting Concrete road surface using machine cutter with groove cutting to demarcate leakage pit of area up to 10 Sqm including earth work excavation in all classifications of soil / base /sub base etc., bailing out water with pumps including barricading, danger lighting etc., as per requirement, attending the leak in 4" CI pipe or any other dia using MS detachable joint/s (4" CI pipe or any other dia , if required for replacement pipe will be supplied by the Department) refilling the trench for 30 cm depth quarry dust above and around pipelines and balance with available earth in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming including watering and consolidation by mechanical means, reinstatement of road after attending the leakage by providing and laying GSB Gr.V 300 mm thick, WMM 300 mm thick, 1:3:6 PCC 200 mm thick, laying available paver blocks with bedding sand etc., complete as approved by Engineer in-charge. (Work to be carried out as per leak repair manual and the rate includes hire charges of dewatering Pump, tractor, Jeep with all kinds of Labour in a Complete manner).	1.00	Job	76,000.00	76,000.00
Amount put to quotation (excluding GST) Rs. :					76,000.00
ADD: % () Above the estimate amount put to quotation.					Rs.
LESS: % () Below the estimate amount put to quotation					Rs.
Total Amount Rs.					
Rupees					

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR