

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/283/CIVIL/Mtc-I/2022-TS dated 03.01.2023

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

| | |
|---------------------------------|---|
| कार्य का नाम; | : केन्द्रीय विद्यालय संख्या 1 की पश्चिमी ओर चारदीवारी का निर्माण |
| Name of work | : Construction of western side Compound wall of Kendriya Vidyalaya no.1 |
| अनुमानित लागत / Estimated Cost | : Rs.1,12,102.85 |
| ईएमडी / EMD | : Rs.2,650.00 |
| खुलने की तिथि / Date of opening | : 10.01.2023 |
| समापन अवधि / Completion Period | : 60 days |

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **10.01.2023** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorised representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.

The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan .The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.



कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
खरखाव प्रभाग-I / Maintenance Division-I,

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजीनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I
कोटेशन/QUOTATION No.5/283 /CIVIL/Mtc-I/2022-TS dated 03.01.2023

BILL OF QUANTITIES

| कार्य का नाम: केन्द्रीय विद्यालय संख्या 1 की पश्चिमी ओर चारदीवारी का निर्माण | | | | | |
|--|--|------------|-------------|------------------------|-----------------------|
| Name of work: Construction of western side Compound wall of Kendriya Vidyalaya no.1 | | | | | |
| SI No | Description of items | Qty | Unit | Rate in Figures | Amount Rs. Ps. |
| 1 | Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work. In all kinds of soils Depth upto 1.5 m. | 10.00 | CuM | 186.00 | 1,860.00 |
| 2 | Extra lead charges for earthwork from 50m to 2kms | 8.00 | CuM | 77.73 | 621.85 |
| 3 | Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately). Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates | 1.00 | CuM | 5926.00 | 5,926.00 |
| 4 | Providing and constructing laterite | 13.00 | CuM | 5945.00 | 77,285.00 |

| | | | | | |
|---|---|--------|-----|--------|--------------------|
| | size stone masonry including cost and conveyance of all materials curing etc complete as per specification I.S. 3620/1979 having compressive strength not less than 3.5 N/mm ² for saturated dry samples - For Super structure in CM 1:6 | | | | |
| 5 | Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. | 50.00 | Sqm | 307.00 | 15,350.00 |
| 6 | Finishing walls with Premium Acrylic Smooth exterior paint of required shade : (Two coats applied @ 1.43 ltr/ 10 m ²) over existing cement paint surface including preparing the surface after thoroughly cleaning the surface to remove all dirt, dust and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. | 140.00 | Sqm | 79.00 | 11,060.00 |
| Amount put to quotation (excluding GST) Rs. : | | | | | 1,12,102.85 |
| ADD: | % () | | | | |
| Above the estimate amount put to quotation. | | | | | Rs. |
| LESS: | % () | | | | |
| Below the estimate amount put to quotation | | | | | Rs. |
| Total Amount Rs. | | | | | |
| Rupees | | | | | |

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR