



NEW MANGALORE PORT AUTHORITY

Mechanical Engineering Department

Panambur, Mangalore – 575 010.

Phone: 0824- 2887730/701.

No. 20/114/2023-24/EE(M)III-TS(OTM)

Date:25/04/2023

To,

The Prospective Bidders,

Sir,

Sub: Mech. Div. - "Painting of Handrails of Tower Monitors & Ground Monitors of Fire Fighting Facilities of Berth No. 10, 11 & 13 including supply of paint"-Quotation Requested - Reg.

Quotations are invited for the work of "Painting of Handrails of Tower Monitors & Ground Monitors of Fire Fighting Facilities of Berth No. 10, 11 & 13 including supply of paint" as per BOQ and Terms & Conditions detailed below.

Sl. No.	Description of item	Unit	Qty.	Rate in Rs	Amount in Rs.
A	Painting of Handrails of 02 Nos. Tower Monitors of Berth No.10 including supply of paint.				
1.	Charges for Scraping, cleaning & painting of ISA 75mmx75mmx8mm thick, 1 mtr. length with base plate of size 150mm x 150 mm x 8 mm thick with one coat of epoxy primer paint, one coat of epoxy intermediate paint and two coats of epoxy finish paint of Yellow colour.	Nos.	86		
2.	Charges for Scraping, cleaning & Painting of 40 NB dia GI pipe with one coat of epoxy primer paint, one coat of epoxy intermediate paint and two coats of epoxy finish paint of Yellow colour.	Mtrs.	248		


B	Painting of Handrails of 02 Nos. Tower Monitors of Berth No.11 including supply of paint.				
1.	Charges for Scraping, cleaning & painting of ISA 75mmx75mmx8mm thick, 1 mtr. length with base plate of size 160mm x 160 mm x 8 mm thick with one coat of epoxy primer paint, one coat of epoxy intermediate paint and two coats of epoxy finish paint of Yellow colour.	Nos.	88		
2.	Charges for Scraping, cleaning & Painting of 40 NB dia GI pipe with one coat of epoxy primer paint, one coat of epoxy intermediate paint and two coats of epoxy finish paint of Yellow colour.	Mtrs	274		
C	Painting of Handrails of 02 Nos. Tower Monitors & 2 Nos. of Ground Monitors of Berth No.13 including supply of paint.				
1.	Charges for Scraping, cleaning & painting of 40 mm width x 5 mm thickness SS flat with one coat of epoxy primer paint, one coat of epoxy intermediate paint and two coats of epoxy finish paint of Yellow colour.	Mtrs	163		
2.	Charges for Scraping, cleaning & painting of 25 sq.mm size SS hollow pipe of 0.9 mtrs Height with one coat of epoxy primer paint, one coat of epoxy intermediate paint and two coats of epoxy finish paint of Yellow colour.	Nos.	574		
Sub Total (A+B+C)					
GST @.....%					
Grand Total					

Terms & Conditions:

- 1) The rates quoted by the Tenderer shall be inclusive of cost of labour charges, transportation charges, tools & tackles, wire brush, scrappers, cotton waste, painting brush/roller, paint & thinner etc. complete required for carrying out the painting work.
- 2) The rate quoted shall be firm and final and inclusive of all taxes & duties excluding GST. GST as applicable shall be paid extra. GST shall be quoted separately.
- 3) Income Tax at the applicable rates will be recovered from the gross amount of the firm's bill as per the relevant provisions of the Acts.
- 4) The quotation shall be valid for a period of 60 days from the date of opening of the quotation.
- 5) The Tenderers may visit the work site (Oil Jetty Area), NMPA and access the details of work to be carried out and get acquainted with the work involved before submitting the quotations by contacting the AEE(M), OTM Sub Division or the undersigned. Any assistance in this regard will be provided by the Department.
- 6) The contractor shall be responsible for taking precautionary measures for the safety of the work men working under him and the responsibility arising due to any mishap during the execution of work, the payment of any compensation, if any, etc. lies entirely on the part of the contractor. The contractor has to employ skilled and competent workers for carrying out the work.
- 7) The work shall be completed within 8 working days each for Berth No. 10, 11 and 13 from the date of issue of work order.
- 8) (i) The work shall be commenced within 10th day from the date of issue of work order. The time allowed for completion of work is 8 working days each for Berth No. 10, 11 and 13.
(ii) During Berthing of Oil Tankers at Oil Jetty, the permission for carrying out the Chipping/Hot Work will not be allowed. Number of days for the completion of the work will be counted the days of non-occupancy of tankers in the respective Berths.
- 9) The contractor is required to be equipped with manpower and materials, equipment, tools & tackles, consumables etc. required for carrying out the work at all time and commence the work within 24 Hrs. after the information is passed on to him regarding the free availability of Jetty.
- 10) The contractor shall obtain hot work permission from the competent authority of NMPA for carrying out the hot works. The copy of the same shall be given to AEE(M), OTM Sub Div. before commencing the works.
- 11) Free electricity and water supply will be given for the said works.

- 12) Power supply shall be given to the Contractor on free of cost. Tapping of power from the source point of NMPT to the required location will have to be arranged by the Contractor at his cost conforming to IE Rules / Standard.
- 13) The paint to be used for the work should conform to the IS standards. All materials to be used should be got approved by the Engineer-in-Charge in the first instance and the work shall be carried out.
- 14) The paint coats shall be smooth and even and shall not show any trace of marks.
- 15) Any damages to the departmental properties during the execution of works will be on contractors account.
- 16) No tools, plant, labour, equipment, consumable, transport etc. required for the work will be supplied by the Department and the Contractor has to make his own arrangements.
- 17) The work will be carried out to the entire satisfaction of Engineer in charge of the Department.
- 18) The free wharf entry passes to the personnel and their vehicle (Red Pass) shall be provided by the Department as per the Rules. The request letter along with required documents for the same shall be provided by the Contractor well in advance indicating the details of vehicle and driver.
- 19) The work carried out shall be guaranteed for a period of 6 months from the date of completion of work.
- 20) Liquidated Damages for delay in completion:
In the event of failure by the contractor to complete the works within stipulated time or on the expiry of any period of extension granted by the Port, the liquidated damages @ 0.5% per week subject to a maximum of 10% of contract value will be levied.
- 21) No advance payment will be made. But, 90% payment will be made through E-payment after satisfactory completion of work to the entire satisfaction of the Engineer-in-Charge and within 15 days from the date of submission of bills. The balance 10% payment will be withheld towards the security deposit. The security deposit will be released without interest after completion of six month guarantee period reckoning from the date of overall completion of the work.
- 22) The contractor shall submit the bill to the Executive Engineer (M)III after completion of work.
- 23) The competent authority of NMPA reserves the right to reject any or all the quotations without assigning any reasons.

- 24) The offer enclosed in a sealed cover super scribed as "Painting of Handrails of Tower Monitors & Ground Monitors of Fire Fighting Facilities of Berth No. 10, 11 & 13 including supply of paint" should reach to the under signed on or before 08/05/2023 at 15:00 Hrs. to the below mentioned address. Quotation will be opened on the same day at 16.00 Hrs. in the presence of the bidders who wish to be present.



(Krishnamurthy D S)

कार्यपालक अभियंता, (एम) III
Executive Engineer, (M) III
नव मंगलूर पत्तन प्राधिकरण
New Mangalore Port Authority
पणंबूर, मंगलूर - ५७५०१०
Panambur, Mangalore - 575 010

Address for Communication:

Executive Engineer (M)III,
Administrative Building, 2nd Floor,
Room No.234,
New Mangalore Port Authority,
Panambur, Mangalore – 575010.
Mob: 9449700435, Ph: 0824-2887730
Email: krishnamurthy.ds@nmpt.gov.in