

TENDER DOCUMENT

NEW MANGALORE PORT AUTHORITY

CIVIL ENGINEERING DEPARTMENT

NIT No. CIVIL/CE(C)/EE(C)/46/2023-24

E-Tender Event No.2023_NMPT_768308_1

Tender for

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS,
BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE
SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25
(TWO YEARS) - RE TENDER"

THROUGH E-TENDERING MODE

Tender Amount : Rs.53,15,597/-

E.M.D. : Rs.1,25,500/-

Tender Fee : Rs.1,120/-(Including GST @ 12%)



TENDER DOCUMENT

NEW MANGALORE PORT AUTHORITY

CIVIL ENGINEERING DEPARTMENT

Tender for

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS,
BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE
SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25
(TWO YEARS) - RE TENDER"

Volume - 1

Table of Contents

i) ii)	NOTICE INVITING TENDER9 INSTRUCTIONS TO TENDERERS			
A.		structions for E-Tendering12		
В.	Ins	structions to Tenderers (General)16		
	1.	Introduction:		
	2.	Applicants:		
	3.	Invitation for Bids:		
	4.	Purchase of Tender Documents:		
	5.	One Bid per Bidder:		
	6.	Cost of Bidding:		
	7.	Site visit:		
	8.	Content of Bidding Documents:		
	9.	Clarification of the Bidding Documents:		
	10.	Amendment of Bidding Documents:		
	11.	Preparation of bids:		
	12.	Minimum Eligibility Criteria:		
	13.	Bid Prices: 20		
	14.	Currencies of Bid and Payment:		
	15.	Bid Validity:		
	16.	Bid Security / EMD:		
	17.	No Alternative Proposals by Bidders:		
	18.	Format and Signing of Bid:		
	19.	Bid Submission:		
	20.	Deadline for Submission of the Bids:		
	21.	Late Bids: 24		
	22.	Modification and Withdrawal of Bids:		
	23.	Bid Opening - Technical Bid:		
	24.	Bid Opening – Financial Bid:		
	25.	Clarification of Bids:		
	26.	Examination of Bids and Determination of Responsiveness:		

	27.	Correction of Errors: (Not Applicable)	<u>'</u> 6
	28.	Evaluation and Comparison of Bids:	<u>'</u> 6
	29.	Alteration of tender documents:	<u>'</u> 6
	30.	Alternative conditions and Proposal:	<u>'</u> 6
	31.	Award of Contract:	27
	32.	Notification of Award:	27
	33.	Release of Bid Security / EMD:	27
	34.	Performance Security:	27
	35.	Fraud and Corrupt Practices:	18
	36.	Rejection of Tender:	19
	37.	Additional Information:2	19
	38.	Compliance of Local Content as per Make in India Policy:	19
	Anne	exure – 1	6O
	Anne	exure – 3 3	13
	Anne	exure – 4	34
	Anne	exure – 5	55
	Anne	exure – 6	6
	Anne	exure – 6A (Not applicable)3	37
	Anne	exure – 7 3	8
	Anne	exure – 8 3	9
	Anne	exure-94	.1
	Anne	exure-104	3
	Anne	exure-114	.4
	Anne	exure-134	.7
SECTI	ON - I	I 4	.8
		M OF AGREEMENT4	
		5	
Α.		eneral	
	1.	Definitions 5	0
	2.	Interpretation5	52
	3.	Language and Law5	52

	4.	Engineer or his nominee's Decisions
	5.	Delegation
	6.	Communications
	7.	Contract Agreement
	8.	Subcontracting53
	9.	Personnel
	10.	Employer's and Contractor's Risks
	11.	Employer's Risks
	12.	Contractor's Risks
	13.	Insurance55
	14.	Site Investigation Reports
	15.	Queries about the Contract Data56
	16.	Contractor to Construct the Works
	17.	The Works to Be Completed by the Intended Completion Date 56
	18.	Approval by the Engineer or his nominee
	19.	Safety
	20.	Discoveries
	21.	Possession of the Site
	22.	Access to the Site
	23.	Instructions
	24.	Disputes
	25.	Settlement of Disputes
	26.	Replacement of conciliator (deleted)
В.	TII	ME CONTROL60
	27.	Program60
	28.	Revised Program60
	29.	Extension of the Intended Completion Date60
	30.	Delays Ordered by the Engineer or his nominee61
	31.	Management Meetings
	32.	Early Warning61
C.	Ql	JALITY CONTROL62

	33.	Identify Defects	2
	34.	Tests62	2
	35.	Defect Liability62	2
	36.	Uncorrected Defects. 63	3
D.	C	OST CONTROL	64
	37.	Bill of Quantities	4
	38.	Changes in the Quantities64	4
	39.	Variations64	4
	40.	Payments for Variations6!	5
	41.	Cash flow forecasts60	6
	42.	Payment Certificates	6
	43.	Payments6	7
	44.	Compensation Events	8
	45.	Tax69	9
	46.	Currencies60	9
	47.	Price Adjustment. (Not Applicable)69	9
	48.	Retention69	9
	49.	Liquidated Damages69	9
	50.	Nominated Subcontractors	0
	51.	Advance payment (Not Applicable)7	1
	52.	Securities7	1
	53.	Removal Of Craft Or Plant Which Has Sunk (NA)	2
	54.	Cost of Repairs	2
E.	FI	NISHING THE CONTRACT	72
	55.	Completion72	2
	56.	Taking Over73	3
	57.	Final Account74	4
	58.	Submission of 'As built Drawings (NA)	4
	59.	Termination	4
	60.	Payment upon Termination	6
	61	Property 76	6

	62.	Release from Performance	. 76
F.	SPE	CIAL CONDITIONS OF CONTRACT	77
	63.	Labour	. 77
	64.	Compliance with labour regulations	. 77
	65.	Safety, Security and Protection of the Environment	. 78
	66.	Insurance of Works and Contractor's Equipment	. 78
	67.	War Risks Insurance	. 80
	68.	Royalty(NA)	. 80
	69.	Transport of Contractor's Equipment or Temporary Works	. 80
	70.	Transport of Materials or Plant	. 81
	71.	Labor Laws & Regulations	. 81
	72.	Life Saving Appliances and First Aid	. 85
	73.	Diving Operations	. 85
	74.	Bribes	. 85
	75.	Details to be Confidential	. 85
	76.	Contractor's Temporary works, office, etc.	. 86
	77.	Water Supply	. 86
	78.	Power Supply	. 86
	79.	Taxes and Duties	. 87
	80.	Price Adjustment (not applicable to this contract)	. 88
	81.	Noise and Disturbance	. 88
	82.	Safety Code	. 88
	83.	Port Authority Rules	. 89
	84.	Execution of work	. 89
	85.	Customs Duty	. 90
	86.	Drawings & Designs	. 92
	87.	Monsoon Period	. 93
	88.	Progress Report	. 93
	89.	Completion Documents (not applicable)	. 94
	90.	Submission of statutory documents	. 94

	G.	SALIENT	FEATURES	OF	SOME	MAJOR	LAWS	APPLICABLE	TO
	ESTA	ABLISHME	NTS ENGAGE	DIN	CONST	RUCTION	WORK		. 95
v)	CON	TRACT DA	TA						.97
vi)	FOR	M OF SEC	URITIES						101
	ANNE	EXURE - A							102
	Anne	xure B (NA	λ)						104
	Anne	xure – C (N	۱A)						106
	ΔPPF	NDIX 1TO	GENERAL C	OND	ITIONS (OF CONTR	RACT (N	Δ)	109

NEW MANGALORE PORT AUTHORITY PANAMBUR, MANGALORE -575010 CIVIL ENGINEERING DEPARTMENT

NIT No: CIVIL/CE(C)/EE(C)/46/2023-24 Date: 24-08-2023

TENDER ID: 2023_NMPT_768308_1

i) NOTICE INVITING TENDER

(Through E-Procurement only)

E-Tenders are invited by New Mangalore Port Authority, Panambur, Mangalore-575010 through https://www.eprocure.gov.in/eprocure/app of CPP portal from the Contractor fulfilling the Minimum Eligibility Criteria stipulated in this notice in two cover bidding procedure for the work of "Annual maintenance of fenders, mooring ladders, bollards, roofing sheet and rolling shutters inside security compound wall for the year 2023-24 and 2024-25 (Two Years)-Re Tender"

a) The tenderers must have experience of having successfully completed *similar works during last 7 (seven) years ending last day of month previous to the one in which applications are invited shall be either of the following:-

At least Three similar completed works costing not less than the amount equal to Rs.10.64 lakhs each

or

At least Two similar completed works costing not less than the amount equal to Rs.13.29 lakhs each

or

At least One similar completed work costing not less than the amount equal to Rs.21.27 lakhs

Note1:*Similar work(s) means "Civil works comprising fabrication and erection of steel structures".

Note2: Documentary evidence for successful completion of the work shall be furnished along with work order and work completion certificate.

- b) Average Financial turnover of the tenderer over the last three financial years 2019-20, 2020-21 and 2021-22 shall be at least Rs.7.98 lakhs.
- c) The financial capacity of bidders would be evaluated considering the works in hand at NMPA. The port would award the work not exceeding the remaining financial capacity of the bidder. The financial capacity to be 3.33times of the average financial turnover of last three years of the bidder minus works in hand at NMPA. The bidder must fill the Annexure-6.

In case the average turnover is Rs.3.00 crores, the financial capacity of the contractor will considered as (3x3.333) Rs.10.00 crores.

The turnover means sales/ contract receipts excluding taxes other income shall not be considered for calculation of turnover.

Pertinent information is given in the following table:

i)	Estimated Amount put to Tender	Rs53,15,597/-	
ii)	Earnest Money Deposit (EMD)	Rs.1,25,500/- (Rupees One Lakh	
		TwentyFive Thousand Five Hundred	
		Only.)	
		The EMD shall be in the form of	
		Insurance Surety Bonds, Account Payee	
		Demand draft, Fixed Deposit Receipt,	
		Bankers Cheque or shall be paid by	
		RTGS in favour of F.A. & C.A.O., NMPA.	
		Scanned copy should be uploaded along	
		with bid. The benefit of Exemption of	
		EMD to all Micro and small enterprises	
		(MSE) will allowed. Shall upload with	
		their offer, the proof of their being MSE registered with district industries center	
		(DIC) or Khadhi and village industries	
		commission or Khadhi and Industries	
		board (KVIV) or Coir board or National	
		Small Industries Corporation (NSIC) or	
		Directorate of handicrafts and	
		handlooms or Udyam Registration	
		Certificate or any other body specified by	
		Ministry of MSME.	
iii)	Cost of Tender (Tender fee)	Rs. 1120/- (Rupees One Thousand One	
		Hundred Twenty Only) Payment of	
		Tender fee by NEFT in favour of F.A. &	
		C.A.O., NMPA. Scanned copy should be	
		uploaded along with bid. The benefit of	
		Exemption of Tender fee to Micro and	
		small enterprises (MSE) will allowed.	

		Shall upload with their offer, the proof of
		their being MSE registered with district
		industries center (DIC) or Khadhi and
		village industries commission or Khadhi
		and Industries board (KVIV) or Coir
		board or National Small Industries
		Corporation (NSIC) or Directorate of
		handicrafts and handlooms or Udyam
		Registration Certificate or any other body
		specified by Ministry of MSME.
iv)	Document download start date	24-08-2023 at 15.00 HRS
	and time	
v)	Seek clarification start date	NA
	and time	
vi)	Seek clarification end date and	NA
	time	
vii)	Bid submission start date and time	07-09-2023 at 10.00 HRS
vii)	Bid submission closing date	14-09-2023 at 15.00 HRS
V11)	and time	14-07-2023 at 13.00 files
ix)	Date & time of opening of	
_	Cover -I : Technical	15-09-2023 at 15.30 HRS
	Part - II : Financial	Shall be communicated separately.
x)	Completion period	24 (Twenty Four) Months (including
		monsoon)
xi)	Validity of Tender	120 days from the date of closing of
		online submission of e-tender.

Tenderer shall have to pay the prescribed cost of tender i.e., Rs.1,120/-(Rupees One Thousand One Hundred Twenty Only) by NEFT in favour of F.A. & C.A.O., NMPA. NMPA Bank Details.

- 1. Name of the Bank: State Bank of India, Panambur, Mangalore 575 010.
- 2. Bank A/C No. 10205649448 3. IFSC Code: SBIN0002249

4. MICR Code: 575002011

Contact Nos. 0824-2887306 and 0824-2407149

Email id: yogindra.s@nmpt.gov.in /chiefengineer@nmpt.gov.in

Amendments / further information etc. pertaining to the tender, if any shall be uploaded only on websites https://www.eprocure.gov.in/eprocure/app of CPP portal, may have to be referred by the prospective Tenderer from time to time.

NEW MANGALORE PORTAUTHORITY PANAMBUR, MANGALORE -575010 NIT No: CIVIL/CE(C)/EE(C)/46/2023-24

E-Tender event No. 2023_NMPT_768308_1

- ii) INSTRUCTIONS TO TENDERERS
- A. Instructions for E-Tendering INSTRUCTION TO E-TENDERING
- 1. SPECIAL INSTRUCTIONS TO THE BIDDERS FOR THE E-SUBMISSION OF THE BIDS ONLINE THROUGH THIS E-PROCUREMENT PORTAL

This is an e-procurement event of NMPA. The e-procurement service provider is https://www.eprocure.gov.in/eprocure/app of CPP portal. You are requested to read the terms & conditions of this tender before submitting your online tender. Tenderers who do not comply with the conditions with documentary proof (wherever required) will not qualify in the Tender.

- 1. Bidder should do Online Enrolment in the Portal using the option Click Here to Enroll available in the Home Page. Then the Digital Signature enrollment has to be done with the e-token, after logging into the portal.
- 2. Bidder then logs into the portal giving user id / password chosen during enrollment.
- 3. The e-token that is registered should be used by the bidder and should not be misused by others.
- 4. DSC once mapped to an account cannot be remapped to any other account. It can only be inactivated.
- 5. The Bidders can update well in advance, the documents such as certificates, purchase order details etc., under My Documents option and these can be selected as per tender requirements and then attached along with bid documents during bid submission. This will ensure lesser upload of bid documents.
- 6. After downloading / getting the tender schedules, the Bidder should go through them carefully and then submit the documents as per the tender document; otherwise, the bid will be rejected.
- 7. The BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for that tender. Bidders are allowed to enter the Bidder Name and Values only.
- 8. If there are any clarifications, this may be obtained online through the e-Procurement Portal, or through the contact details given in the tender document. Bidder should take into account of the corrigendum published before submitting the

- 9. bids online on the portal or on www.newmangaloreport.gov.in
 Bidder, in advance, should prepare the bid documents to be submitted as indicated in the tender schedule and they should be in PDF formats.
- 10. Bidder should arrange for the EMD and tender fee as specified in the tender. The benefit of Exemption of EMD to all Micro and small enterprises (MSE) will allowed. Bidder Shall upload with their offer, the proof of their being MSE registered with district industries center (DIC) or Khadhi and village industries commission or Khadhi and Industries board (KVIV) or Coir board or National Small Industries Corporation (NSIC) or Directorate of handicrafts and handlooms or Udyam Registration Certificate or any other body specified by Ministry of MSME will be considered. The bidder should read the terms and conditions and accepts the same to proceed further to submit the bids.
- 11. The bidder has to submit the tender document(s) online well in advance before the prescribed time to avoid any delay or problem during the bid submission process.
- 12. There is no limit on the size of the file uploaded at the server end. However, the upload is decided on the Memory available at the Client System as well as the Network bandwidth available at the client side at that point of time. In order to reduce the file size, bidders are suggested to scan the documents in 75-100 DPI so that the clarity is maintained and the size of file gets reduced. This will help in quick uploading even at very low bandwidth speeds.
- 13. It is important to note that, the bidder has to click on the Freeze Bid Button, to ensure that, he/she completes the Bid Submission Process. Bids, which are not frozen, are considered as Incomplete/Invalid bids and are not considered for evaluation purposes.
- 14. The Tender Inviting Authority (TIA) will not be held responsible for any sort of delay or the difficulties faced during the submission of bids online by the bidders due to local issues.
- 15. The bidder may submit the bid documents online mode only, through this portal.

 Offline documents will not be handled through this system.
- 16. At the time of freezing the bid, the e-Procurement system will give a successful bid updating message after uploading all the bid documents submitted and then a bid summary will be shown with the bid no., date & time of submission of the bid with all other relevant details. The documents submitted by the bidders will be digitally signed using the e-token of the bidder and then submitted.
- 17. After the bid submission, the bid summary has to be printed and kept as an acknowledgement as a token of the submission of the bid. The bid

- summary will act as a proof of bid submission for a tender floated and will also act as an entry point to participate in the bid opening event.
- 18. Successful bid submission from the system means, the bids as uploaded by the bidder is received and stored in the system. System does not certify for its correctness.
- 19. The bidder should see that the bid documents submitted should be free from virus and if the documents could not be opened, due to virus, during tender opening, the bid is liable to be rejected.
- 20. The time that is displayed from the server clock at the top of the tender Portal, will be valid for all actions of requesting bid submission, bid opening etc., in the e-Procurement portal. The Time followed in this portal is as per Indian Standard Time (IST) which is GMT+5:30. The bidders should adhere to this time during bid submission.
- 21. The bidders are requested to submit the bids through online e-Procurement system to the Tender Inviting Authority (TIA) well before the bid submission end date and time (as per Server System Clock).
- 22. Tender form Fee and EMD shall be submitted with the Part I- Technical BID. BID submitted without fees, as mentioned above will not be considered for evaluation and shall be rejected summarily the benefit of Exemption of EMD and tender fee to all Micro and small enterprises (MSE) registered with district industries center (DIC) or Khadhi and village industries commission or Khadhi and Industries board (KVIV) or Coir board or National Small Industries Corporation (NSIC) or Directorate of handicrafts and handlooms or any other body specified by Ministry of MSME, will be considered. The bidder shall upload with their offer, the proof of their being MSE.
- 23. The bidder/tenderer/contractor shall file the applicable returns with Tax departments in time and submit the same as documentary proof. The GST applicable shall be shown as a separate line items in the Tax invoices to avail in put credit to Port.

2. Cover - I Details (Technical)

The following documents shall be uploaded online only.

- 1. Scanned copy of NEFT Payment details for cost of tender / documentary evidence for exemption of tender fee.
- 2. Scanned copy of RTGS/NEFT Payment details for EMD/ documentary evidence for exemption of EMD.
- 3. Scanned copy of documents as per Annexure 1 to 13 of section I(iii) of volume-I (Original power of attorney i.e. Annexure 2 to be submitted by post or by hand

immediately after the closing date for submission of online e-tender).

- 4. Scanned copy of valid PAN card, ESI, PF and GST Registration certificate.
- 5. List of Ongoing works in hand at NMPA should be indicated in the prescribed form.
- 6. Scanned copy of Form of Tender as per Section VI(iii) of volume -III
- 7. Technical bid document Cover I (Volume I to Volume III) along with amendments and clarifications.

3. Cover - II Detail (Finance)

PRICE BID (Bill of Quantities)

Price should be quoted in the BOQ template available in the portal. The BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for that tender. Bidders are allowed to enter the Bidder Name and Values only.

Any indication of 'Quoted price' in the online technical bid documents shall lead to rejection of the bid outright.

The price bid submitted through e-portal mode only will be taken up for the purpose for evaluation.

4. Opening of bids

- A. Part I Techno-Commercial bid will be opened electronically on specified date and time as given in the NIT. Bidder(s) can witness electronic opening of bid.
- B. Part II Price bid will be opened electronically of only those bidder(s) whose Part I Techno-Commercial Bid is found to be Techno-Commercially acceptable by NMPA. Such bidder(s) will be intimated, the date of opening of Part II Price bid, through valid email confirmed by them.

Note: The tenderers are advised to offer their best possible rates. There would generally be no negotiations hence most competitive prices may be quoted while submitting the price bid. However in case the lowest rate appears to be reasonable taking into account the prevailing market conditions, the work may be awarded to the lowest bidder and if the rate is still considered high, action as per prevailing instructions / guidelines shall be taken. All entries in the tender should be entered in online Technical & Commercial Formats without any ambiguity.

5. Evaluation process:

A proposal shall be considered responsive if –

- a. It is received by the proposed Due Date and Time.
- b. It is Digitally Signed.
- c. It contains the information and documents as required in the Tender Document.
- d. It contains information in formats specified in the Tender Document.

- e. It mentions the validity period as set out in the document.
- f. It provides the information in reasonable detail. The Port Authority reserves the right to determine whether the information has been provided in reasonable detail.
- g. There are no significant inconsistencies between the proposal and the supporting documents.
- h. The Technical qualification conforms to as specified in the qualification criteria.
- i. A Tender that is substantially responsive is one that conforms to the preceding requirements without material deviation or reservation. A material deviation or reservation is one (1) which affects in any substantial way, the scope, quality, or performance of the Tenderer or (2) which limits in any substantial way, inconsistent with the Tender document, or (3) whose rectification would affect unfairly the competitive position of other Qualified Applicant presenting substantially responsive bids.
- j. The Port Authority reserves the right to reject any tender which in its opinion is non-responsive and no request for alteration, modification, substitution or withdrawal shall be entertained by the Port Authority in respect of such Tenders.
- k. The Port Authority would have the right to review the Technical Qualification and seek clarifications wherever necessary.
- I. Since the tender involves selection based on pre-qualification criteria and technical specification, the Chief Engineer will examine and seek clarification if any and list out the firms, which are found technically suitable and Cover-II Price Bid of such tenderers only will be opened and EMD will be returned to the unsuccessful tenderers
- m. The date and time will be intimated to tenderers whose offers are found suitable and Cover II of such tenderers will be opened on the specified date and time
- n. The cost of stamping Agreement must be borne by the successful Tenderer
- o. The Fax/E-Mail offers will be treated as defective, invalid and rejected. Only detailed complete offers received through online prior to closing time and date of the tenders will be taken as valid.

B. Instructions to Tenderers (General)

1. Introduction:

This work essentially comprises of "Annual maintenance of fenders, mooring ladders, bollards, roofing sheet and rolling shutters inside security compound wall for the year 2023-24 and 2024-25 (Two Years)-Re Tender"

2. Applicants:

Contractors who wish to bid for the tender for the contract work should apply for the

tender document. The successful bidder will be expected to complete the works by the intended completion date specified in the Contract document.

3. Invitation for Bids:

The online Invitation for Bids is open to all eligible bidders meeting the eligibility criteria. The bidders may submit bids for the works detailed in the NIT through etender mode only.

4. Purchase of Tender Documents:

Tender document can be downloaded from NMPA website www.newmangaloreport.gov.in, www.tender.gov.in&https://www.eprocure.gov.in/eprocure/app of CPP portal

5. One Bid per Bidder:

Each bidder shall submit only one bid for one package. Bidder who submits or participates in more than one Bid will cause all the proposals with the Bidder's participation to be disqualified.

6. Cost of Bidding:

The bidder shall bear all costs associated with the preparation and submission of his Bid, and the Employer will in no case be responsible and liable for those costs.

7. Site visit:

The Bidder, at the Bidder's own responsibility and risk is encouraged to visit and examine the work site and its surroundings and obtain all information that may be necessary for preparing the Bid and entering into a contract for construction of the Works. The costs of visiting the site shall be at the Bidders' own expense.

8. Content of Bidding Documents:

Tender Document will consist of:

Volume I	Section I	Notice Inviting Tenders
		Instructions to Tenderers
		Annexure (1 to 13)
	Section II	Form of Agreement
	Section III	Conditions of Contract: Part A - E: General
		Conditions
		Conditions of Contract : Part F: Special
		Conditions
		Contract Data
		Form of Securities (A & B)
		Appendix - I and Appendix - II

Volume II	Section IV	Technical Specifications
	Section V	Drawings
Volume III	Section VI	Preamble
		Bill of Quantities
		For of tender
	Section VII	Schedules (A & B)

Any indication of "Quoted price" in the technical bid, shall lead to rejection of the bid outright. For evaluation purpose the uploaded offer documents will be treated as authentic and final. No hard copy shall be submitted, upload the entire document on the CPP portal only.

9. Clarification of the Bidding Documents:

The Tenderers are advised to examine the Tender Document carefully and if there be or appear to be any ambiguity or discrepancy in the documents, or any clarifications needed on the Tender Documents; these shall be referred to the Chief Engineer (Civil) in writing, so as to reach at least three days before start date of submission of bid. It is to be noted that queries asked after due date will not be answered. Employer's clarifications shall be furnished in the CPP e-portal or shall be issued a corrigendum in the web site after closing date of online pre-bid meeting without identifying the source.

A provision is made in the CPP e-portal for online pre-bid meeting during the date mentioned in the NIT. The bidders can ask queries if any during the period of pre-bid meeting through online. The queries of the bidders shall be answered online or a separate consolidated list of queries and clarifications shall be uploaded in web sites after closing date of online pre-bid meeting.

10. Amendment of Bidding Documents:

Any modification of the tender documents as a result of any ambiguity shall be shall be made exclusively through the issue of an Addendum. Any addendum thus issued shall be part of the tender documents and will be uploaded in CPP e-portal and Port website to all the bidders. Prospective

Bidders shall acknowledge receipt of each addendum to the Employer. Such addenda will be numbered and it shall be submitted by the Tenderers as part of Part I of their bid. The Addendum can also be downloaded from NMPA official website from 'Ongoing Project link'. The responsibility of downloading such addendum / amendment from NMPA website and CPP e-portal fully lies with the bidder.

11. Preparation of bids:

All documents relating to the bid shall be in the English language.

12. Minimum Eligibility Criteria:

a) The tenderers must have experience of having successfully completed *similar works during last 7 (seven) years ending last day of month previous to the one in which applications are invited shall be either of the following:-

At least Three similar completed works costing not less than the amount equal to Rs.10.64 lakhs each

or

At least Two similar completed works costing not less than the amount equal to Rs.13.29 lakhs each

or

At least One similar completed works costing not less than the amount equal to Rs.21.27 lakhs

Note1:*Similar work(s) means "Civil works comprising fabrication and erection of steel structures".

Note2: Documentary evidence for successful completion of the work shall be furnished along with work order and work completion certificate

b) Average Financial turnover of the tenderer over the last three financial years 2019-20, 2020-21 and 2021-22 shall be at least Rs.7.98 lakhs.

The financial capacity of bidders would be evaluated considering the works in hand at NMPA. The port would award the work not exceeding the remaining financial capacity of the bidder. The financial capacity to be 3.33times of the average financial turnover of last three years of the bidder minus works in hand at NMPA. The bidder must fill the Annexure-6.

In case the average turnover is Rs.3.00 crores, the financial capacity of the contractor will considered as (3x3.333) Rs.10.00 crores.

The turnover means sales / contract receipts excluding taxes other income shall not be considered for calculation of turnover.

Copy of the work order, Client's satisfactory work completion Certificate, along with any other documentary proof certifying the year of completion, brief description of the project and project completion cost shall be submitted in support of the assignments performed and claimed by the tenderer to fulfill the eligibility criteria for qualification. Experience of the tenderer / contractor for completed works, executed in private organization shall be considered only if the Tax Deducted at Source Certificate with respect to referred work, issued by Competent Authority is enclosed

by the tenderer along with the tender

A statement duly certified by the Chartered accountant showing the average annual Financial Turnover over the last 3 financial years shall be submitted.

Even though the bidders meet the above qualifying criteria, they are subject to be disqualified if they have:

- i) made misleading or false representations in the forms, statements and attachments submitted in proof of the qualification requirements; and/or
- ii) record of poor performance such as abandoning the works, not properly completing the contract, inordinate delays in completion, litigation history, or financial failures etc.,

13. Bid Prices:

The contract shall be for the whole works as described in based on the priced Bill of Quantities submitted through CPP e-portal by the Bidder .The Bidder shall fill in the percentage of Excess or Less in the Bill of Quantities through CPP e-portal. Items for which no rate or price is entered will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities.

14. Currencies of Bid and Payment:

The Unit rates and the prices shall be quoted by the bidder entirely in Indian Rupees

15. Bid Validity:

Bids shall remain valid for a period not less than one hundred twenty days (120 days) after the last date for online bid submission. A bid valid for a shorter period shall be rejected by the Employer as non-responsive.

In exceptional circumstances, prior to expiry of the original bid validity period, the Employer may request that the bidders may extend the period of validity for a specified additional period. The request and the bidders' responses shall be made in writing or by cable. A bidder agreeing to the request will not be permitted to modify his bid and also shall submit an extension for EMD, if it is in the form of Bank Guarantee

16. Bid Security / EMD:

- i. The EMD shall be in the form of Insurance Surety Bonds, Account Payee Demand draft, Fixed Deposit Receipt, Bankers Cheque or shall be paid by RTGS/NEFT in favour of Financial Adviser & Chief Accounts Officer, New Mangalore Port Authority, Mangalore
 - 1. Name of the Bank: State Bank of India, Panambur, Mangalore 10.
 - 2. Bank A/C No. 10205649448
 - 3. IFSC Code: SBIN0002249

4. MICR Code: 575002011

- ii. The Techno Commercial Bid shall be accompanied by the RTGS/NEFT deposit details towards Earnest Money Deposit of Rs.125500/- (Rupees One Lakh TwentyFive Thousand Five Hundred Only) as stipulated in the tender. The tender without EMD shall be treated invalid. The benefit of Exemption of EMD and tender fee to all Micro and small enterprises (MSE) registered with district industries center (DIC) or Khadhi and village industries commission or Khadhi and Industries board (KVIV) or Coir board or National Small Industries Corporation (NSIC) or Directorate of handicrafts and handlooms or any other body specified by Ministry of MSME, will be considered. The bidder shall upload with their offer, the proof of their being MSE.
- iii. In the event of Bidder withdrawing his Bid before the expiry of tender validity period of 120 days from the last date for online bid submission, the tender shall be cancelled and EMD shall be forfeited.
- iv. The Earnest Money Deposit of unsuccessful bidder shall be returned without interest as early as possible by RTGS/NEFT on conclusion of contract. The Earnest Money Deposit of the successful bidder shall be refunded (without interest) after he has signed the agreement and furnished required performance security.
- v. The Bid Security of a successful bidder will be forfeited in the following cases:
- a) If the bidder withdraws his Tender during the period of bid validity.
- b) In case of a successful tenderer fails
- i) to commence the work, apart forfeiture of other claims
- ii) within the specified time limit to sign the Agreement or furnish the required Performance Security. In the event of forfeiting the EMD / SD / LD and while imposing penalty GST as applicable will be collected.

17. No Alternative Proposals by Bidders:

Bidders shall submit offers that comply with the requirements of the bidding documents, including the basic technical design as indicated in the drawing and specifications. Alternatives will not be considered.

18. Format and Signing of Bid:

The Bid shall be in online mode. The Bid shall contain no alterations or additions, except those comply with instructions issued by the Employer

19. Bid Submission:

Tender document including quoted bid price have to be submitted online only through CPP Portal before deadline for online submission of bid.

For evaluation purpose the uploaded offer documents will be treated as authentic and final. Any documents submitted in the form of hard copy except Power of

attorney.

The Tender shall be submitted in Two Bids.

- I. Technical Bid: Shall contain the following.
- i) Techno Commercial Bid: Shall contain all the documents. Techno Commercial Bid should not contain Price Bid. "Disclosure/indication of Price in the Techno Commercial Bid shall render the tender disgualified and rejected.
- ii) The details of payment of EARNEST MONEY DEPOSIT for Rs.125500/- (Rupees One Lakh TwentyFive Thousand Five Hundred Only) by RTGS/NEFT to NMPA Bank Account, failing which the Techno commercial Bid shall not be considered).
- iii) Transaction details of payment towards the COST OF TENDER Fee: Rs. 1120/(Rupees One Thousand One Hundred Twenty Only) (To be paid by RTGS/NEFT to NMPA Bank Account).
- II. FINANCIAL BID: shall contain only the Price.
- III. LAST DATE FOR SUBMISSION OF ONLINE TENDER: is as per the date mentioned in the NIT

NMPA may at its sole discretion reserves the right to extend the date for receipt of Bid. Bid after the aforesaid time and date or the extended time and date, if any, shall not be accepted by the portal.

The following details pertaining to Techno Commercial Bid shall be uploaded online.

- a) Letter of Submission- Covering letter (vide Annexure 1)
- b) Power of Attorney in favour of signatory/s to the Tender, (vide Annexure -2) (Original power of attorney i.e. Annexur-2 to be submitted by post or by hand so as to reach the Executive Engineer (Civil) immediately after the closing date for submission of online e-tender).
- c) Organization Details (vide Annexure-3)
- d) Details of "Minimum eligibility criteria" as per Clause 12 of instruction to Tenderers and certificates (Client Certificates / work completion certificates or any other documentary evidences with respect to the eligibility work) (vide Annexure-4) of condition of contract. The following specific instruction may be noted;
- i) Bidders are expected to provide information in respect of Eligible Assignments in this Section. The assignments cited must comply with the criteria specified in Clause No. 12 (a) for "Minimum eligibility".
- ii) A separate sheet should be filled for each of the eligible assignments the details are to be supplemented by documentary proof from the respective client for having carried out such assignment duly certified by client's completion certificates and work orders etc.

- iii) The works indicated in Annexure- 4 will only be considered for evaluation.

 Mere submission of work completion certificate will not be considered as Eligible Assignments
- e) A statement duly certified by Chartered Accountant showing Average Financial turnover of the tenderer over the last three financial years (vide Annexure-5) with balance sheet.
- f) List of Ongoing works in hand at NMPA should be indicated in the prescribed form (Annexure-6)
- g) A list of Plant and equipment proposed to be engaged for work. (vide Annexure-7) The equipment indicated in the Annexure -7 will form part of contract agreement and as such the bidders are requested to indicate the availability of the equipment at site at what stage of the construction period the equipment would made available.
- h) Tenderer should submit copy of Permanent Account Number. (PAN), ESI, PF and GST Registration (GSTIN) Number along with certificates issued by the authority as applicable
- i) A declaration to the effect that (vide Annexure -8):-
- a. All details regarding construction plant and machinery, temporary work and personnel for site organization considered necessary and sufficient for the work have been furnished in the Annexure to Conditions of Contract in Volume I and that such plant, temporary works and personnel for site organization will be available at appropriate time of relevant works for which the equipment have been proposed at site till the completion of the respective work.
- b. No conditions are incorporated in the financial bid. In case any conditions are specified in the financial bid, the tender will be rejected summarily without making any further reference to the bidder.
- c. We have not made any payment or illegal gratification to any persons/ authority connected with the bid process so as to influence the bid process and have not committed any offence under PC Act in connection with the bid.
- d. We disclose with that we have made / not made payments or propose to be made to any intermediaries (agents) etc in connection with the bid.
- j) NEFT Payment details towards cost of tender / documentary evidence for exemption of tender cost.
- k) RTGS/NEFT Payment details towards EMD / documentary evidence for exemption of EMD

20. Deadline for Submission of the Bids:

i. The completed bid shall be submitted in the electronic form by the date and

time mentioned in NIT only through CPP e-portal.

- ii. The Employer may extend the deadline for submission of bids by issuing an amendment in accordance with Clause 10, in which case all rights and obligations of the Employer and the bidders previously subject to the original deadline will thereafter be subject to the deadline as extended.
- iii. Price should be quoted in CPP e-portal. Any indication of 'Quoted price' in the online technical bid documents shall lead to rejection of the bid outright. For evaluation purpose the uploaded offer documents will be treated as authentic and final. No hard copy shall be submitted for reference purpose. The bid submitted through e-tendering mode only will be taken up for the purpose for evaluation.
- iv. The uploaded Port Tender Document will be treated as authentic tender and if any discrepancy is noticed at any stage between the Port's tender document and the one submitted/uploaded by the tenderer, the conditions mentioned in the Port's uploaded document shall prevail. Besides, the tenderer shall be liable for legal action for the lapses.

21. Late Bids:

The time that is displayed from the server clock at the top of the CPP e-portal, will be valid for all actions of requesting bid submission, bid opening etc., The bidders should adhere to this time during bid submission.

22. Modification and Withdrawal of Bids:

- i. Bidders may modify the offers by deleting their already freezed bids in online only through CPP e-portal (after submission of bid) and resubmit/upload the revised offer before the deadline prescribed in Clause 20.
- ii. No bid shall be withdrawn and resubmitted through CPP e-portal by the bidder after the deadline for submission of bids.
- iii. Withdrawal of a Bid between the deadline for submission of bids and the expiration of the original period of bid validity specified in Clause 15 may result in the forfeiture of the Bid Security or the bidder shall be disqualified from bidding for any contract with New Mangalore Port Authority for a period of 2 (two) years in pursuant to Clause 16.
- iv. Bidders may only modify the prices and other required details of their Bids by Resubmitting Bid only in accordance with this clause through CPP e-portal.

23. Bid Opening - Technical Bid:

a. On the due date and time as specified in Clause 20, the Employer will first open Techno Commercial bids of all bids received online in presence of the Bidders or

their representatives who choose to attend. In the event of specified date for bid opening is declared as holiday by the Employer, the bid will be opened at the appointed time and location on the next working day.

- b. In the first instance the Techno Commercial Bid containing the RTGS/NEFT payment details of EMD & Cost of tender document will be verified. If EMD and Tender Fee is in line with the Tender Condition there after the Techno Commercial Bid will be considered for evaluation.
- c. If all Bidders have submitted unconditional Bids together with requisite Bid security, then all Bidders will be so informed then and there. If any Bid contains any deviation from the Bids documents and / or if the same does not contains Bid security in the manner prescribed in the Bid documents, then that Bid will be rejected and the Bidder informed accordingly.

24. Bid Opening - Financial Bid:

The date and time of opening of price bid (cover-II) shall be intimated to the qualified bidders based on the evaluation of the technical bid. The price bid (cover-II) of such eligible bidders shall be opened on the specified date and time.

If bidder withdraws his tender after opening of price bid the bidder will be disqualified for participating in NMPA tender for a period of two years.

25. Clarification of Bids:

To assist in the examination and comparison of Bids, the Employer may, at his discretion, ask any Bidder for clarification of his Bid, including breakdown of unit rates. The request for clarification and the response shall be in writing, but no change in the price or substance of the Bid shall be sought, offered, or permitted. No Bidder shall contact the Employer on any matter relating to his bid from the time of the bid opening to the time the contract is awarded. If the Bidder wishes to bring additional information to the notice of the Employer, he should do so in writing.

Any effort by the Bidder to influence the Employer's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid.

Employer reserves the right to reject any Bid, if the Bidder does not provide the clarification sought for by the Employer, within the time specified by the Employer, for proper evaluation of the Bid.

26. Examination of Bids and Determination of Responsiveness:

Prior to detailed evaluation of Bids. NMPA will determine whether each Bid

- a) meets the eligibility criteria as defined in Clause 12.
- b) has been properly signed by an authorised signatory (accredited representative)

holding Power of Attorney in his favour. The Power of Attorney shall interalia include a provision to bind the Bidder to settlement of disputes clause;

- c) is accompanied by the requisite Bid security and;
- d) is responsive to the requirements of the Bidding documents.

A responsive Bid is one which conforms to all the terms, conditions and specification of the Bidding documents, without material deviation or reservation. A material deviation or reservation is one

- a) which affects in any substantial way the scope, quality or performance of the Works;
- b) which limits in any substantial way, the Employer's rights or the Bidder's obligations under the Contract; or
- c) whose rectification would affect unfairly the competitive position of other Bidders presenting responsive Bids.

The tenderer shall submit a certificate in the tender schedule in the Technical Bid that he has not incorporated any conditions in the Financial Bid and in case any conditions are specified in the financial bid his tender will be rejected without making any further reference to him.

If a Bid is not substantially responsive, it shall be rejected by the Employer, and may not subsequently be made responsive by correction or withdrawal of the nonconforming deviation or reservation.

27. Correction of Errors: (Not Applicable)

28. Evaluation and Comparison of Bids:

The Employer will evaluate and compare only the Bids determined to be responsive in accordance with Clause 26. In evaluating the Bids, the Employer will determine for each Bid the evaluated Bid Price by adjusting the Bid Price as follows:

a) making appropriate adjustments to reflect discounts or other price modifications offered in accordance with Clause 22.

29. Alteration of tender documents:

No alteration shall be made in any of the tender documents or in the Bill of Quantities and the tender shall comply strictly with the terms and conditions of the tender document. The Employer may however ask any tenderer for clarifications of his tender if required. Nevertheless, no tenderer will be permitted to alter his tender price after opening of the tender.

30. Alternative conditions and Proposal:

The Tenderer shall note that alternative or qualifying tender conditions, or alternative design proposal for whole or part of the work will not be acceptable. Tenders containing any qualifying conditions or even Bidder's clarifications in any

form will be treated as non-responsive and will run the risk of rejection. Part II: Price Bid of such Bidder's will not be opened.

31. Award of Contract:

The Employer will award the Contract to the bidder whose bid has been determined to be responsive to the bidding documents and who has offered the lowest evaluated bid price, provided that such bidder has been determined to be

- a) Eligible in accordance with the provisions of Clause 12, and
- b) Qualified in accordance with the provisions of Clause 12.

32. Notification of Award:

- i) The Bidder whose Bid has been accepted will be notified about the award by the Employer prior to expiration of the Bid validity period by, fax or e-mail and confirmed by registered letter. This letter (hereinafter and in the Conditions of Contract called the "Letter of Acceptance") will state the sum that the Employer will pay the Contractor in consideration of the execution, completion and maintenance of the works by the Contractor as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price").
- ii) The notification of award will constitute the formation of the Contract subject only to the furnishing of a performance security in accordance with the provisions of Clause 34.
- iii) The Agreement will also incorporate all correspondence exchanged between the employer and the successful bidder. Within 21 days of receipt of Letter of Acceptance, the successful bidder shall furnish the performance security and sign the Agreement with the Employer. The contractor shall make 12 copies of the Agreement and submit to the employer within 7 days following the date of signing of Agreement.

33. Release of Bid Security / EMD:

The Earnest Money Deposit of unsuccessful bidder, shall be returned without interest by RTGS/NEFT on conclusion of Contract. The Earnest Money Deposit of the successful bidder if deposited in cash, shall be refunded (without interest) after he has signed the agreement and furnished required performance security.

34. Performance Security:

i) Within 21 days of receipt of the Letter of Acceptance, the successful Bidder shall deliver to the Employer a Performance Security in the form in the form of Insurance Surety Bonds, Account Payee Demand draft, Fixed Deposit Receipt from a commercial bank, remittance by RTGS for an amount equivalent to 5% of the Contract price including GST, as applicable rounded off to the nearest

1000.

ii) If the performance security is provided by the successful Bidder in the form of a Bank Guarantee, it shall be issued by a Nationalized /Scheduled Indian bank having its branch at Mangalore acceptable by NMPA. The BG shall be issued in favor of New Mangalore Port Authority in the Format enclosed in Volume I as Annexure-A.

35. Fraud and Corrupt Practices:

The bidder and their respective officers, employees, agents and advisers shall observe the highest standard of ethics during the Selection Process. Notwithstanding anything to the contrary contained in this document, the Port shall reject the tender without being liable in any manner whatsoever to the bidder, if it determines that the bidder has, directly or indirectly or through an agent, engaged in corrupt practice, fraudulent practice, coercive practice, undesirable practice or restrictive practice (collectively the "Prohibited Practices") in the Selection Process. In such an event, the Port shall, without prejudice to its any other rights or remedies, forfeit and appropriate the Bid Security or Performance Security, as the case may be, as mutually agreed genuine pre-estimated compensation and damages payable to the Port for, inter alia, time, cost and effort of the Authority, in regard to the Tender, including consideration and evaluation of such Bidder's Proposal. Such Bidder shall not be eligible to participate in any tender or RFP issued by the Authority during a period of 2 (two) years from the date such Bidder is found by the Authority to have directly or through an agent, engaged or indulged in any corrupt practice, fraudulent practice, coercive practice, undesirable practice or restrictive practice, as the case may be.

For the purposes of this Clause, the following terms shall have the meaning hereinafter respectively assigned to them:

- (a) "corrupt practice" means
- i) the offering, giving, receiving, or soliciting, directly or indirectly, of anything of value to influence the action of any person connected with the Selection Process (for avoidance of doubt, offering of employment to or employing or engaging in any manner whatsoever, directly or indirectly, any official of the Authority who is or has been associated in any manner, directly or indirectly with the Selection Process or the LOA or has dealt with matters concerning the Agreement or arising there from, before or after the execution thereof, at any time prior to the expiry of one year from the date such official resigns or retires from or otherwise ceases to be in the service of the Authority, shall be deemed to constitute influencing the actions of a person

or

connected with the Selection Process;

- ii) engaging in any manner whatsoever, whether during the Selection Process or after the issue of the LOA or after the execution of the Agreement, as the case may be, any person in respect of any matter relating to the Project or the LOA or the Agreement, who at any time has been or is a legal, financial or technical consultant/ adviser of the Authority in relation to any matter concerning the Project;
- (b) "fraudulent practice" means a misrepresentation or omission of facts or disclosure of incomplete facts, in order to influence the Selection Process;
- (c) "coercive practice" means impairing or harming or threatening to impair or harm, directly or indirectly, any persons or property to influence any person's participation or action in the Selection Process;
- (d) "undesirable practice" means
- i) establishing contact with any person connected with or employed or engaged by the Authority with the objective of canvassing, lobbying or in any manner influencing or attempting to influence the Selection Process; or
- ii) having a Conflict of Interest; and
- (e) "Restrictive practice" means forming a cartel or arriving at any understanding or arrangement among Applicants with the objective of restricting or manipulating a full and fair competition in the Selection Process.

36. Rejection of Tender:

Any Tender not conforming to the foregoing instructions will not be considered. The Employer does not bind himself to accept the lowest or any tender and has the right to reject any tender without assigning any reason thereof. No representation whatsoever will be entertained on this account.

37. Additional Information:

The "Instructions to Tenderers" shall not form part of the Contract. They are intended only to aid the Tenderers in the preparation of their tender.

38. Compliance of Local Content as per Make in India Policy:

Bidder shall comply with DPIIT Order No. P-45021/2/2017-PP(B-II) dtd. 16-09-2020 in respect of Local Content and furnish an undertaking in the prescribed format as per Annexure 13, to that effect, failing which, the bid may be liable for cancellation.

LETTER OF SUBMISSION - COVERING LETTER

(ON THE LETTER HEAD OF THE BIDDER)

Date:

To,
The Executive Engineer (Civil),
New Mangalore Port Authority,
Administration Building,
Panambur, Mangalore – 575 010

Sir,

Sub: The work of "Annual maintenance of fenders, mooring ladders, bollards, roofing sheet and rolling shutters inside security compound wall for the year 2023-24 and 2024-25 (Two Years)-Re Tender"

We are submitting our Bid enclosing the following, with the details as per the requirements of the Bid Document, for your evaluation.

- i. Tender Document along with Addendum No ----,
- ii. Power of Attorney (Annexure 2)
- iii. Organization Details (Annexure 3)
- iv. Details to fulfill the "Minimum Eligibility Criteria" and certificates –(Annexure 4)
- v. Average Financial turnover over the last three financial year (Annexure 5)
- vi. list of ongoing works In hand at NMPA-(Annexure-6)
- vii. List of plant and equipment (Annexure 7)
- viii. Declaration (Annexure 8)
- ix. EMD Paid by RTGS/NEFT vide UTR No......dtd. of (name and address of the branch).
- x. Banker's Details Annexure 10 & 11
- xi. Tender fee paid by NEFT vide vide UTR No......dtd. of (name and address of the branch).
- xii. Copy of valid PAN Card ESI, PF and GST Registration certificate.

Signature (Authorised Signatory)

ON STAMP PAPER of Rs 100/-

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER"

FORMAT OF POWER OF ATTORNEY (in original)

In favour of signatory/s to the Tender, duly authenticated by Notary Public.

POWER OF ATTORNEY IN FAVOUR OF ----- (Name, Designation, Company name)

TO ALL TO WHOM THESE PRESENTS shall come, I, (Name & address of the authorized person to sub-delegate/delegate powers, delegated on him by the Board of Directors) do hereby sub-delegate/delegate, in terms of the powers delegated to me by the Board of Directors, ------ (name of the Co.) to Shri ----- (name, designation & address of the Attorney) the following:

NOW KNOW YE AND THOSE PRESENTS that I, (Name & address of the authorized person to sub-delegate/delegate powers, delegated on him by the Board of Directors), do hereby authorize and empower Shri ----- (name, designation & address of the Attorney) to do severally amongst others, for the purpose of carrying on our business, the following:

- a) To represent lawfully the (name of the Co.) for obtaining bid/tender documents, prepare, sign, execute and submit tenders for execution of (Name of work) or any other works incidental to such construction works.
- b) To discuss the technical and financial matters, negotiate and accept prices and take decisions regarding terms and conditions and sign agreements and contracts and also to bind the (name of the Co.) to the arbitration clause included in the contract.
- c) For all or any of the purposes here of to sign and deliver or otherwise execute such deed or deeds, transfer or transfers, endorsement or endorsements and to perform such other acts, matters, things as the Attorney shall consider requisite or advisable as full and effectively as the Company could do, if present and acting there.
 - I, (Name & address of the authorized person to sub-delegate/delegate powers, delegated on him by the Board of Directors) in terms of the powers delegated to me

the Co.), do hereby agree that all acts,
virtue of this power of attorney, shall
the Company.
rson to sub-delegate/delegate powers,
ırther undertake to ratify and confirm
to be done for the Company, the said
ers hereby given.
delivered to Shri (name &
day of, 20, (Two
ation is signed on this day of
), will have effect from the date he
dress of the authorized person to sub-
by the Board of Directors) has, this
nd) set my hands and

(Name & designation of Attorney)

Annexure - 3

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER"

-

ORGANIZATION DETAILS

CONTACT	No.:	
NAME OF	APPI	ICANT

- 1. Name of the Owner:
- 2. Address:

Telephone No.:

Fax No.

- Description of Applicant
 (for e.g. General, Civil Engineering etc.,)
- 4. Registration and Classification of Contractors:
- 5. Name and address of bankers:
- 6. Number of years of experience as a general contractor:-

In own Country:

Internationally:

- 7. Number of years of experience as a sub-contractor:
 - Name and Address of partners or associated companies to be involved in the project and whether Parent/Subsidiary/other:
- 8. Name and address of any associates knowledgeable in the procedures of customs, immigration and local experience in various aspect of the project etc.
- 9. Name and address of the companies / Sub-contractors who will be involved in the execution of works, namely:

Signature (Authorised Signatory)

NEW MANGALORE PORT AUTHORITY

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER" Tenderer shall furnish Details of "eligibility works experience" as per Clause 12(a) of Minimum Eligible Criteria (MEC) of Instruction to Tenderer and certificates in the following format (Client Certificates/work completion certificates or any other documentary evidences with respect to the eligibility work)

ELIGIBLE ASSIGNMENT DETAILS FOR MEC

Assignment Number:

Description	Bidder to fill up the details here
Name and Address of the Client	
Title of the Eligible Assignment	
Date of completion of the Eligible	
Assignment	
Project Cost	
Reference No of the enclosed work order	
Reference No of the enclosed Client work	
Completion Certificate	
Reference No of any other documentary	
evidence; if enclosed.	
Name, telephone no, telefax no and email	
address of the client's representative	
Description and Scope of Work	

Signature (Authorised Signatory)

Certificate from the Statutory Auditor

This is to certify that the information contained in Column 4 above is correct as per the accounts of the Applicant and/ or the clients.

(Signature, name and designation of the authorised signatory)

Date: Name and seal of the audit firm:

In case the Applicant does not have a statutory auditor, it shall provide the certificate from its chartered accountant that ordinarily audits the annual accounts of the Applicant.

Instructions:

- i. Bidders are expected to provide information in respect of Eligible Assignments in this Section. The assignments cited must comply with the criteria specified Clause No. 12.0(a) Minimum eligibility of the "Instructions to Tenderers".
- ii. A separate sheet should be filled for each of the eligible assignments.
- iii. The details are to be supplemented by documentary proof (Work order and work completion certificate) from the respective client for having carried out such assignment duly certified by clients.

NEW MANGALORE PORT AUTHORITY

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER"

FINANCIAL CAPABLITY

(A) Net worth & Average Annual Turnover of the Bidder

Net Worth	Turnover			
Year 1	Year 1	Year 2	Year 3	Average

Instructions:

Net Worth = (Subscribed and Paid-up Equity + Reserves) - (Revaluation reserves + Miscellaneous expenditure not written off + depreciation not provided for). Year 1 will be the Financial Year 2020-21. Year 2 shall be the year immediately preceding Year 1 and Year 3 shall be the year immediately preceding Year 2. The Bidder shall provide audited Annual Reports as required under this Bid Document.

Net worth & Annual turnover of the bidder shall be submitted duly verified by Charted Accountant or Competent Authority.

(B) (Here specify proposed sources of credit line to meet the Cash flow demand for the work)

Source of Credit line	Amount

There should be a letter from the Bank mentioning that line of credit offered is specifically for this work/contract.

NOTE: If the Tenderer intends to meet the "Cash Flow Demand" for the project through their internal resources without availing the loan of credit, a specific mention to be made to this effect and proof for such resources shall be enclosed.

Certified by C.A Signature (Authorised Signatory)

NEW MANGALORE PORT AUTHORITY

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER"

LIST OF ONGOING WORKS IN HAND AT NMPA

The Tenderer shall furnish in the format given below details of works being carried out by him at the time of bidding in NMPA.

SI.	Name of work	Work order No.	Value Of	Average annual
No.		and Date	Work Order	financial turnover
			In Rs.	as per MEC for the
				work

Contractor

Annexure - 6A (Not applicable)

NEW MANGALORE PORT AUTHORITY

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER"

DETAILS OF PROPOSED APPROACH & METHODOLOGY

Bidder shall furnish a detailed method statement (Technical Note) for carrying out of the works, along with a construction programme showing sequence of operation and the time frame for various segments of temporary and permanent works.

Signature (Authorised Signatory)

NEW MANGALORE PORT AUTHORITY

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER"

PLANT AND EQUIPMENT PROPOSED FOR THE WORK

Please indicate the main plant and equipment considered to be necessary for undertaking the work and whether this plant is ready in ownership or will be purchased or hired.

Descript	Require	Owned /	Nos /	Age /	Remarks	At what stage of
ion of	ment	leased /	capac	conditi	(from	contract period
equipme	no. /	to be	ity	on	whom to	the equipment
nt	capacity	procure			be	will be available
		d			purchased)	

Note: The equipment indicated in the above statement will form part of contract agreement and as such the bidders are requested to indicate the availability of the equipment at site and at what stage of the construction period in a separate column.

Signature (Authorised Signatory)

NEW MANGALORE PORT AUTHORITY

"ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER"

DECLARATION

We M/s. (Name & address of the bidder) hereby declare that:-

- I have read the tender document Vol. I (Section I to III) Vol. II (Section IV and V) and Vol. III (Section V and VII) and agreed to the terms and conditions mentioned therein.
- ii. All details regarding construction plant, temporary work and personnel for site organization considered necessary and sufficient for the work have been furnished in the Annexures to Conditions of Contract in Volume I and that such plant, temporary works and personnel for site organization will be available at the site till the completion of the respective work.
- iii. No conditions are incorporated in the financial bid. In case any conditions are specified in the financial bid, the tender will be rejected summarily without making any further reference to the bidder.
- iv. We have not made any payment or illegal gratification to any persons/ authority connected with the bid process so as to influence the bid process and have not committed any offence under PC Act in connection with the bid.
- v. We shall undertake that, the Employer i.e. NMPA is indemnified against all damages or compensation payable at Law in respect of or in consequence of any accident or injury to any workman or other person in the employment of the Contractor or Sub-Contractor against all claims, demands, proceedings, costs, charges and expenses whatsoever in respect thereof or in relation thereto and the Employer shall be at liberty to deduct or adjust from the Contactor's bills an amount that Employer may be called upon to pay towards claims, demands, proceedings, costs, charges and expenses Whatsoever in respect of or in relation to any accident or injury referred to above without any reference to the Contractor. The contractor shall execute indemnity bond in the prescribed format as per **Annexure 12**

vi. We shall comply with all the Central State and Municipal Laws and Rules and we shall be solely responsible for complying with the provisions of the Contract Labour

(Regulations & Abolition) Act, 1970 & the contract labour (Regulation & Abolition)

Karnataka Rules 1974 and rules there under and the enactments that may be

applicable including ESI Act, the payment of wages act, Provident Fund Act, the

Minimum Wages Act, the Factory's Act. The Workmen Compensation Act or any

other applicable legislation and the Municipal by-laws or other statutory Rules and

Regulations whatsoever in force if these are applicable. Any obligations finding or

otherwise missed under any statutory enactments, rules & regulations there under

shall be the responsibility of the Contractor and the NMPA will take no responsibility

for the same. The Contractor should take Workmen's Compensation Policy for his

Workers, who are not covered under ESI and submit the same to the EIC

immediately after commencement of the work

vii. We undertake that, we are liable to pay all Statutory Compensation to the

Labourers/persons engaged by him for the satisfactory execution of the works. If any claim is made against New Mangalore Port Authority on this work, the Port Authority

shall have the right to deduct the same from the bill amount payable to the

contractor after verification of the validity and if admissible as per rules

viii. *We disclose with that we have made / not made payments or propose to be made to

any intermediaries (agents) etc. in connection with the bid.

* Note: Delete whichever is not applicable.

Signature

(Authorised Signatory)

BID SECURITY (BANK GUARANTEE)(NA)

	WHEREAS, [Name of Bidder] (he	ereinafter called "the Bidder")
	has submitted his bid dated	[date] for the Annual
	maintenance of fenders, mooring ladders, bollards, roof	ing sheet and rolling shutters
	inside security compound wall for the year 2023-24	and 2024-25 (Two Years)-Re
	Tender(hereinafter called "the Bid").	
	KNOW ALL PEOPLE by these presents that We	
	[name of bank] of (name of co	untry) having our registered
	office at (hereinafter called	d "the Bank") are bound unto
	[name of Employ	yer] (hereinafter called "the
	Employer") in the sum of 1	for which payment well and
	truly to be made to the said Employer the Bank bin	ds itself, his successors and
	assigns by these presents.	
	SEALED with the Common Seal of the said Bank this _	day of 20
	THE CONDITIONS of these obligations are:	
(1)	(1) If after Bid opening the Bidder withdraws his Bid dur	ing the period of bid validity
	specified in the Form of Bid;	
	or	
(2)	(2) If the Bidder having been notified of the acceptance	of his Bid by the Employer
	during the period of bid validity:	
(a)	(a) fails or refuses to execute the Form of Agreeme	nt in accordance with the
	Instructions to Bidders, if required; or	
(b)	(b) fails or refuses to furnish the Performance Securi	ty, in accordance with the
	Instructions to Bidders, or	
(c)	(c) does not accept the correction of the Bid Price pursuant	to Clause 27;
	We undertake to pay to the Employer up to the above	e amount upon receipt of his
	first written demand, without the Employer having	to substantiate his demand,
	provided that in his demand the Employer will note that	it the amount claimed by him
	is due to him owing to the occurrence of one or a	any of the three conditions,
	specifying the occurred condition or conditions.	
	This Guarantee will remain in force up to and includi	· ·
	after the deadline for submission of Bids as such	
	Instructions to Bidders or as it may be extended by the	. 3
	extension(s) to the Bank is hereby waived. Any demand	I in respect of this Guarantee

42

should reach the	Bank not later than	the above date.	
Notwithstanding a	anything mentioned abov	/e,	
Our liability agai	nst this guarantee is re	estricted to Rs	(Rupees
	only) and u	nless a claim in writing	g is lodged with us
within 3 months of	of the date of expiry or th	ne extended date of expi	ry of this guarantee
all our liabilities u	ınder this guarantee sha	II stand discharges.	
IN WITNESS WHE	EREOF this guarantee ha	as been duly executed o	n this day of
20			
DATE	SIGNATURE OF THE	BANK	
WITNESS	SI	EAL	
[Signature, name	and address]		

The Bidder should insert the amount of the guarantee in words and figures denominated in Indian Rupees. This figure should be the same as shown in Clause 16 of the Instructions to Bidders.

30 days after the end of the validity period of the Bid. Date should be inserted by the Employer before the Bidding documents are issued.

DETAILS OF THE PARTY OPTING FOR REFUND OF EMD THROUGH E-PAYMENT SYSTEM FROM NEW MANGALORE PORT AUTHORITY

Name of the Party	:
Bank A/c No	:
Account type	: (Savings / Current / Overdraft)
Bank Name	:
Branch	:
IFSC Code Number	: (11 digit code)
Centre (Location)	:
FAX No.	:
E-Mail ID	: (For forwarding information of remittance)
Mobile No	:

Signature of the Party

FORMAT FOR FURNISHING BANK INFORMATION FOR e-PAYMENT

1	Name and full address of the	
	beneficiary	
2	Credit Account No.	
	(Should be full 14 digit)	
3	Account Type	
	(SB or CA or OD)	
4	Name of the Bank	
5	Branch	
	(Full address with telephone No.)	
6	IFSC Code Number (11 digit)	
7	MICR code	
	(Should be 9 digit)	
8	Telephone/Mobile/Fax No. of the	Telephone:
	beneficiary	Mobile :
		Fax :
9	Photostat copy of a Cheque	

Signature of the party with seal

Verified the details furnished by the party and it is ascertained that the information furnished are in full shape as required. Xerox copy of a Cheque is also enclosed.

Signature of the HOD/HOO with seal

INDEMNITY BOND

(To be furnished in Stamp paper not less than Rs.100 e-Stamp paper)
This deed of indemnity is executed by herein after referred to as 'Indemnifier' which expression shall unless repugnant to the context or meaning thereof, include its successors, Administrator, representatives and assignees in favour of New Mangalore Port Authority, Panambur, Mangalore 575010, herein after referred to as 'Indemnified' which expression shall unless repugnant to the context or meaning thereof include its representatives and assignees witnesses as to.

Whereas the indemnified herein as awarded to the indemnifier herein a Tender/Contract or for supply of / Construction of on terms and conditions set out interalia in the work order No........ valued at Rs.......

AND Whereas, the clauses No...... of the above mentioned work order provides for indemnifying the indemnified by the indemnifier for any accident, damage or compensation payable to any workmen or other person in the employment of the contractor or any sub-contractor during the period of tender/contract.

AND Whereas, the Indemnifier hereby irrevocably agrees to indemnify the indemnified against all damages or compensation payable at law in respect of or in consequence of any accident or injury to any workmen or other person in the employment of the contractor or sub-contractor against all claims, demands, proceedings, costs, charges and expenses whatsoever in respect thereof or in relation thereto and the indemnified shall be at liberty to deduct or adjust from the bills payable to the indemnifier by the indemnified for an amount that the indemnified may be called upon to pay towards claims, demands, proceedings, costs, charges and expenses whatsoever in respect of or in relation to any accident or injury referred to above without any reference to the indemnifier.

The Indemnifier shall comply with all the Central State and Municipal Laws and Rules and shall be solely responsible for complying with the provisions of the Contract Labour (Regulations & Abolition) Act, 1970 & the contract labour (Regulation & Abolition) Karnataka Rules 1974 and rules there under and the enactments that may be applicable including ESI Act, the payment of wages act, Provident Fund Act, the Minimum Wages Act, the Factory's Act, the Workmen Compensation Act or any other applicable legislation and the Municipal by-laws or other statutory Rules and Regulations whatsoever in force if these are applicable. Any obligations finding or otherwise missed under any statutory enactments rules &

46

regulations there under shall be the responsibility of the Indemnifier and the Indemnified will have no responsibility for the same. The Indemnifier shall obtain Workmen's Compensation Policy for his workers, who are not covered under ESI and submit the same to the ESIC immediately after commencement of the work.

The Indemnifier is liable to pay all Statutory Compensation to the Labourers / persons engaged by him for the satisfactory execution of the works. If any claim is made against Indemnified arising out of this work, the Port shall have the right to deduct the same from the bill amount payable to the Indemnifier after verification of the validity and if admissible as per rules.

The Indemnifier shall ensure the use of PPE such as helmets, safety shoes, nose masks, hand gloves, safety harness or any other equipment as required depending on nature of work by his staff at site.

In addition to complying of the above, the Indemnifier hereby undertakes to indemnify the indemnified against any unforeseen incidents / accidents, which may lead to fatality including death, permanent/ partial disablement, injury, financial loss, legal issues or any other etc., of the labourers / workmen's/ staffs of the contractor / sub-contractor for which the indemnified and its officers / representation are in no way responsible.

1 01
INDEMINIFIER
(Signature with Name and Designation)
Company Seal
Station:
Date:
Witness:
1
Signature with Name, Designation & Address
2
Signature with Name, Designation & Address

For

Annexure-13

Format for Self Certification under Preference to "MAKE IN INDIA" Policy (Refer Clause No. 38 of ITT)

CERTIFICATE

In line with God dtd:16-09-2020,								, ,
submission		tender,					that	we
M/s				3		3		
meeting the requ								
for the material				•				
							_	
Details of location	n at whi	ch local va	lue add	ition will be	mad	e is as fo	llows:	
We also unders								0 3
under Rule 175(
its successors ca			•				•	
Financial Rules	along wi	th such oth	ner acti	ons as may	be pe	ermissibl	e under l	aw. Seal
and Signature of	Author	ized Signat	ory					
				_	- 1		5	
				S	signa [.]	ture of th	ne Bidder	
Date:								
Place:								

iii) FORM OF AGREEMENT

THIS AGREEMENT made the day of
20 BETWEEN New Mangalore Port Authority (hereinafter called "the Employer") o
the one part and
(hereinafter called "the Contractor") of the other part WHEREAS the Employer is
desirous that certain works should be executed by the Contractor
Viz and has accepted a Tender by the Contractor for
the execution and Completion of such works and the remedying of any defects
therein at a contract price of Rs
NOW THIS AGREEMENT WITNESSETH as follows:
In this Agreement words and expressions shall have the same meanings as are

- 1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the General Conditions hereinafter referred to.
- 2. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz.
 - a) The Letter of Acceptance;
 - b) The Said Tender (Technical Bid);
 - c) The Conditions of Contract (Parts I and II)
 - d) The Specifications;
 - e) The Drawings;
 - f) The Bill of Quantities and
 - g) The Addenda
 - h) Letters exchanged between the Employer and the Tenderer up to the issue of Letter of Acceptance as separately listed and annexed here to.
- 3. In consideration of the payments to be made by the Employer to the contractor as hereinafter mentioned the Contractor hereby covenants with the Employer to execute and complete the works and remedy any defects therein in conformity in all respect with the provisions of the Contract.

4. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the works and the remedying of defects therein the Contract Price or and such other sum as may become payable under the Provisions of the Contract at the times and in the manner prescribed by the Contract.

IN WITNESS whereof the parties hereto have caused this Agreement to be executed the day and year first above written in accordance with their respective laws.

This document contains pages in all. This agreement is assigned No. CEA /20XX-XX.

The Common Seal of						

was hereunto affixed in the presence of :

iv) CONDITIONS OF CONTRACT

A. General

1. Definitions

Terms which are defined in the Contract Data are not also defined in the Conditions of Contract but keep their defined meanings. Capital initials are used to identify defined terms.

Bill of Quantities means the priced and completed Bill of Quantities forming part of the Bid.

Compensation Events are those defined in Clause 44.

The Completion Date is the date of completion of the Works as certified by the Engineer or his nominee in accordance with Sub Clause 54

The Contract is the contract between the Employer and the Contractor to execute, complete and maintain the Works. It consists of the documents listed in Clause 2.3 below.

The Contract Data defines the documents and other information which comprise the Contract.

The Contractor is a person or corporate body whose Bid to carry out the Works has been accepted by the Employer.

The Contractor's Bid is the completed Bidding documents submitted by the Contractor to the Employer.

The Contract Price is the price stated in the letter of acceptance and thereafter as adjusted in accordance with the provisions of the Contract.

Days are calendar days, months are calendar months.

A Defect is any part of the Works not completed in accordance with the Contract.

The Defects Liability Period is the period named in the Contract Data and calculated from the Completion Date.

The Employer is the party who will employ the Contractor to carry out the Works.

Equipment is the Contractor's machinery and vehicles brought temporarily to the

Site to construct the Works.

The Initial Contract Price is the Contract Price listed in the Employer's Letter of Acceptance.

The Intended Completion Date is the date on which it is intended that the Contractor shall complete the works. The Intended Completion Date is specified in the Contract Data. The Intended Completion Date may be revised only by the Engineer or his nominee by issuing an extension of time.

Materials are all supplies, including consumables, used by the contractor for incorporation in the Works.

The Engineer or his nominee is the person named in the Contract Data (or any other competent person appointed and notified to the contractor to act in replacement of the Engineer or his nominee) who is responsible for supervising the Contractor, administering the Contract, certifying payments due to the Contractor, issuing and valuing Variations to the Contract, awarding extensions of time and valuing the Compensation Events.

Plant is any integral part of the Works which is to have mechanical, electrical, electronic or chemical or biological function.

The Site is the area defined as such in the Contract Data.

Site Investigation Reports are those which are included in the Bidding documents and are factual interpretative reports about the surface and sub-surface conditions at the site.

Specification means the Specification of the Works included in the Contract and any modification or addition made or approved by the Engineer or his nominee.

The Start Date is given in the Contract Data. It is the date when the Contractor shall commence execution of the works. It does not necessarily coincide with any of the Site Possession Date.

A Subcontractor is a person or corporate body who has a Contract with the Contractor to carry out a part of the work in the Contract which includes work on the Site.

Temporary Works are works designed, constructed, installed and removed by the Contractor which are needed for construction or installation of the Works.

A Variation is an instruction given by the Engineer or his nominee which varies the Works.

The Works are what the Contract requires the Contractor to construct, install and turn over to the Employer as defined in the Contract Data.

The Trained Work Person are those employed / proposed to be employed by the Contractor at the Project Site, who have participated and are in possession of a valid Competency Certificate through a programme run under the auspices of a University, State Technical Board, Ministry of Government of India.

2. Interpretation

- 2.1 In interpreting these Conditions of Contract, singular also means plural, male also means female or neuter and the other way around. Headings have no significance. Words have their normal meaning under the language of the Contract unless specifically defined. The Engineer or his nominee will provide instructions clarifying queries about the Conditions of Contract.
- 2.2 If sectional completion is specified in the Contract Data, references in the Conditions of Contract to the Works, the Completion Date, and the Intended Completion Date apply to any Section of the Works (other than references to the Completion Date and Intended Completion date for the whole of the Works).
- 2.3 The documents forming the Contract shall be interpreted in the following order of priority:
 - (1) Agreement
 - (2) Letter of Acceptance and notice to proceed with works
 - (3) Contractor's Bid
 - (4) Contract Data
 - (5) Conditions of Contract including Special Conditions of Contract
 - (6) Specifications
 - (7) Drawings
 - (8) Bill of quantities and
 - (9) Any other documents listed in the Contract Data as forming part of the Contract.

3. Language and Law

3.1 The language of the Contract and the law governing the Contract are stated in the Contract Data.

4. Engineer or his nominee's Decisions

4.1 Except where otherwise specifically stated, the Engineer or his nominee will decide contractual matters between the Employer and the Contractor in the role representing the Employer.

5. Delegation

5.1 The Engineer or his nominee may delegate any of the duties and

responsibilities to other people after notifying the Contractor and may cancel any delegation after notifying the Contractor.

6. Communications

Communications between parties which are referred to in the conditions are effective only when in writing. A notice shall be effective only when it is delivered (in terms of Indian Contract Act 1872).

7. Contract Agreement

A suitable form is annexed as "FORM OF AGREEMENT" to the Contract Document. Upon signing the Contract Agreement, the Contractor shall make 12 copies of Contract Documents in hardbound cover which shall cover documents used in Contract/Agreement and provide the same to the Employer at no extra cost.

Data made available by the Employer in accordance with provisions of the Condition of Contract shall be deemed to include data listed elsewhere in the Contract and open for inspection at the office of the Deputy Chief Engineer (Civil) of the New Mangalore Port Authority (by prior appointment with the Engineer). Within 21 days of receipt of Letter of Acceptance, the successful bidder shall furnish the performance security and sign the Agreement with the Employer. However No work shall be commenced before signing of contract Agreement.

8. Subcontracting

8.1 The Contractor may subcontract with the approval of the Engineer or his nominee but may not assign the Contract without the approval of the Employer in writing. Subcontracting does not alter the Contractor's obligations.

Other Contractors

8.2 The Contractor shall co-operate and share the site with other contractors, public authorities, utilities, and the Employer between the dates given in the Schedule of other contractors. The Contractor shall as referred to in the Contract Data, also provide facilities and services for them as described in the Schedule. The employer may modify the schedule of other contractors and shall notify the contractor of any such modification.

9. Personnel

9.1 The Contractor shall employ the key personnel named in the Schedule of Key Personnel as referred to in the Contract Data to carry out the functions stated in the Schedule or other personnel approved by the Engineer or his nominee. The Engineer or his nominee will approve any proposed replacement of key personnel only if their qualifications, abilities, and relevant experience are

- substantially equal to or better than those of the personnel listed in the schedule.
- 9.2 If the Engineer or his nominee asks the contractor to remove a person who is a member of the contractor's staff of his work force stating the reasons, the contractor shall ensure that the person leaves the site within seven days and has no further connections with the work in the contract.

10. Employer's and Contractor's Risks

10.1 The Employer carries the risks which this Contract states are Employer's risks and the contractor carries the risks which this Contract states are contractor's risks.

11. Employer's Risks

- 11.1 The Employers risks are
 - (a) In so far as they directly affect the execution of the Works in the country where the Permanent Works are to be executed:
- i) war and hostilities (whether war be declared or not), invasion, act of foreign enemies;
- ii) rebellion, revolution, insurrection, or military or usurped power, or civil war;
- iii) ionizing radiations, or contamination by radioactivity from any nuclear fuel, or from any nuclear waste, from the combustion of nuclear fuel, radioactive toxic explosive or other hazardous properties of any explosive nuclear assembly or nuclear component thereof;
- iv) pressure waves caused by aircraft or other aerial devices travelling at sonic or Supersonic speeds; and
- v) riot, commotion or disorder, unless solely restricted to the employees of the Contractor or of his Subcontractors and arising from the conduct of the Works;
- vi) Unforeseen Rains (Rains if any; during the period other than the Monsoon period as stated in the Tender), floods, tornadoes, earthquakes and landslides.
- b) loss or damage due to the use or occupation by the Employer of any Section or part of the Permanent Works, except as may be provided for in the Contract;
- c) loss or damage to the extent that it is due to the design of the Works, other than any part of the design provided by the Contractor or for which the Contractor is responsible; and
- d) any operation of the forces of nature (in so far as it occurs on the Site) which an experienced contractor:

- i) could not have reasonably foreseen, or
- ii) could reasonably have foreseen, but against which he could not reasonably have taken at least one of the following measures:
- iii)prevent loss or damage to physical property from occurring by taking appropriate measures, or
- iv) insure against.

12. Contractor's Risks

12.1 All risks of loss of or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract other than the excepted risks are the responsibility of the Contractor.

13. Insurance

- 13.1The Contractor shall provide in the joint names of the Employer and the Contractor, insurance cover from the Start Date to the end of the Defects Liability Period, in the amounts and deductibles stated in the Contract Data for the following events which are due to the Contractors risks.
- a) loss of or damage to the Works, Plant and Materials
- b) loss of or damage to Equipment;
- c) loss of or damage of property (except the Works, Plant, Materials and Equipment) in connection with the Contract; and
- d) personal injury or death.
 - 13.2 Policies and certificates for insurance shall be delivered by the contractor to the Engineer or his nominee for the Engineer or his nominee's approval before the start date. All such insurances shall provide for compensation to be payable in the types and proportions of currencies required to rectify the loss or damage incurred.
- 13.3 If the contractor does not provide any of the policies and certificates required, the Employer may affect the insurance which the contractor should have provided and recover the premiums the Employer has paid from payments otherwise due to the contractor or, if no payment is due, the payment of the premiums shall be a debt due.
- 13.4 Alterations to the terms of insurance shall not be made without the approval of the Engineer or his nominee.
- 13.5 Both parties shall comply with all conditions of the insurance policies.

14. Site Investigation Reports

The Contractor, in preparing the Bid, shall rely on the Site Investigation

Report referred to in the Contract Data, supplemented by any information available to the Bidder.

15. Queries about the Contract Data

The Engineer or his nominee will clarify queries on the Contract Data.

16. Contractor to Construct the Works

The Contractor shall construct and install the works in accordance with the Specification and Drawings.

17. The Works to Be Completed by the Intended Completion Date

The Contractor may commence execution of the works on the Start Date and shall carry out the works in accordance with the program submitted by the contractor as updated with the approval of the Engineer or his nominee, and complete them by the Intended Completion Date.

18. Approval by the Engineer or his nominee

- 18.1 The Contractor shall submit Specifications and Drawings showing the proposed Temporary Works to the Engineer or his nominee, who is to approve them if they comply with the specifications and Drawings.
- 18.2 The Contractor shall be responsible for design of Temporary Works.
- 18.3 The Engineer or his nominee's Approval shall not alter the contractor's Responsibility for design of the Temporary Works.
- 18.4 All Drawings prepared by the contractor for the execution of the temporary or permanent Works, are subject to prior approval by the Engineer or his nominee before their use.

19. Safety

The contractor shall be responsible for the safety of all activities on the Site.

20. Discoveries

Anything of historical or other interest or of significant value unexpectedly discovered on the Site is the property of the Employer. The Contractor is to notify the Engineer or his nominee of such discoveries and carry out the Engineer or his nominee's instructions for dealing with them.

21. Possession of the Site

The Employer shall give possession of all parts of the Site to the Contractor, free from encumbrances. If possession of a part is not given by the start date stated in the Contract Data the Employer is deemed to have delayed the start of the relevant activities and this will be a Compensation Event.

22. Access to the Site

The Contractor shall allow the Engineer or his nominee and any person

authorized by the Engineer or his nominee access to the Site to any place where work in connection with the Contract is being carried out or is intended to be carried out and to any place where materials or plant are being manufactured, fabricated and/or assembled for the works.

23. Instructions

The Contractor shall carry out all instructions of the Engineer or his nominee which comply with the applicable laws where the Site is located.

24. Disputes

If the Contractor believes that a decision taken by the Engineer or his nominee was either outside the authority given to the Engineer or his nominee by the Contract or that the decision was wrongly taken, the decision shall be referred to the Dispute Review Board (DRB) within 28 days of the notification of the Engineer or his nominee's decision.

25. Settlement of Disputes

25.1 If a dispute of any kind whatsoever arises between the Employer and the Contractor in connection with, or arising out of the Contract or the execution of the Works, whether during the execution of the Works or after their completion and whether before or after repudiation or after termination of the Contract, including any disagreement by either party with any action, inaction, opinion, instruction, determination, certificate or valuation of the Engineer or his nominee, the matter in dispute shall, in the first place be referred to the Disputes Review Board [DRB] established pursuant to Appendix 1 hereto. (Not applicable to this contract) Unless the Contract has already been repudiated or terminated or frustrated the Contractor shall in every case, continue to proceed with the Works with all due diligence and the Contractor and the Employer shall give effect forthwith to every decision of the Engineer or his nominee unless and until the same shall be revised, as hereinafter provided, in a Dispute Review Board Recommendation / Arbitral Award.

25.2. Arbitration

Any dispute in respect of in respect of contracts where party is dissatisfied by the Dispute Review Board's (DRB) decision shall be decided by arbitration as set forth below:

i) A dispute with contractor shall be finally settled by arbitration in accordance with the Indian Arbitration and Conciliation Act, 1996, or any statutory amendment thereof. The arbitral tribunal shall consist of 3 arbitrators, one each to

- be appointed by the Employer and the contractor, and the third to be appointed by the mutual consent of both the arbitrators, failing which by making a reference to CIDC-SIAC Arbitration Center from their panel.
- ii) Neither party shall be limited in the proceedings before such arbitrators to the evidence or arguments already put before the Engineer or his nominee or the Board, as the case may be, for the purpose of obtaining said recommendations/decision. No such recommendations/decision shall disqualify the Engineer or his nominee or any of the members of the Board, as the case may be, from being called as a witness and giving evidence before the arbitrators or any matter whatsoever relevant to the dispute.
- iii) The reference to arbitration shall proceed notwithstanding that the works shall not then be or be alleged to be complete, provided always that the obligations of the Employer, the Engineer or his nominee and the Contractor shall not be altered by reason of the arbitration being conducted during the progress of the works. Neither party shall be entitled to suspend the works to which the dispute relates, and payment to the Contractor shall be continued to be made as provided by the contract.
- iv) If one of the parties fails to appoint its arbitrators in pursuance of sub-clause [i], within 14 days after receipt of the notice of the appointment of its arbitrator by the other party, then President/Chairman of the nominated Institution shall appoint arbitrator within 14 days of the receipt of the request by the nominated institution. A certified copy of the President's/ Chairman's order, making such an appointment shall be furnished to both the parties.
- v) Arbitration proceedings shall be held at Mangalore, and the language of the arbitration proceedings and that of all documents and communications between the parties shall be 'English
- vi) The Arbitration shall be conducted by the experts from the panel of CIDCSIAC Arbitration Center.
- vii) The decision of the majority of arbitrators shall be final and binding upon both parties. The expenses of the arbitrators as determined by the arbitrators shall be shared equally by the Employer and the Contractor. However, the expenses incurred by each party in connection with the preparation, presentation, etc. of its case prior to, during and after the arbitration proceedings shall be borne by each party itself.
- viii) All arbitration awards shall be in writing and shall state the reasons for the award.
- ix) Performance under the contract shall continue during the arbitration proceedings and payments due to the contractor by the Employer shall not be withheld, unless

they are subject matter of the

26. Replacement of conciliator (deleted)

arbitration proceedings.

B. TIME CONTROL

27. Program

- 27.1 Within the time stated in the Contract Data the Contractor shall submit to the Engineer or his nominee for approval a Program showing the general methods, arrangements, order, and timing for all the activities in the works along with monthly cash flow forecast.
- 27.2 An update of the Program shall be a program showing the actual progress achieved on each activity and the effect of the progress achieved on the timing of the remaining work including any changes to the sequence of the activities.
- 27.3 The Contractor shall submit to the Engineer on the first day of each week or such longer period as the Engineer may from time to time direct, a progress report in an approved form showing up-to-date total progress, progress achieved against planned progress, during the previous week and progress forecast for the following week for all important items in each section or portion of the Works, in relation with the approved Program.
- 27.4 The Contractor shall submit to the Engineer or his nominee, for approval an updated Program at intervals no longer than the period stated in the Contract Data. If the Contractor does not submit an updated Program within this period, the Engineer or his nominee may withhold the amount stated in the Contract Data from the next payment certificate and continue to withhold this amount until the next payment after the date on which the overdue Program has been submitted.

28. Revised Program

The Engineer or his nominee's approval of the Program shall not alter the Contractor's obligations. The Contractor may revise the Program and submit it to the Engineer or his nominee again at any time. A revised Program is to show the effect of Variations and Compensation Events.

29. Extension of the Intended Completion Date

- 29.1 The Engineer or his nominee shall extend the Intended Completion Date if a Compensation Event occurs or a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date without the Contractor taking steps to accelerate the remaining work and which would cause the Contractor to incur additional cost.
- 29.2 The Engineer or his nominee shall decide whether and by how much to extend the Intended Completion Date within 21 days of the Contractor

asking the Engineer or his nominee for a decision upon the effect of a Compensation Event or Variation and submitting full supporting information. If the Contractor has failed to give early warning of a delay or has failed to cooperate in dealing with a delay, the delay by this failure shall not be considered in assessing the new Intended Completion Date.

30. Delays Ordered by the Engineer or his nominee

The Engineer or his nominee may instruct the Contractor to delay the start or progress of any activity within the Works.

31. Management Meetings

- 31.1 Either the Engineer or his nominee or the Contractor may require the other to attend a management meeting. The business of a management meeting shall be to review the plans for remaining work and to deal with matters raised in accordance with the early warning procedure.
- 31.2 The Engineer or his nominee shall record the business of management meetings and is to provide copies of his record to those attending the meeting and to the Employer. The responsibility of the parties for actions to be taken is to be decided by the Engineer or his nominee either at the management meeting or after the management meeting and stated in writing to all who attended the meeting.

32. Early Warning

- 32.1 The Contractor is to warn the Engineer or his nominee at the earliest opportunity of specific likely future events or circumstances that may adversely affect the quality of the work, increase the Contract Price or delay the execution of works. The Engineer or his nominee may require the Contractor to provide an estimate of the expected effect of the event or circumstance on the Contract Price and Completion Date. The estimate is to be provided by the Contractor as soon as reasonably possible.
- 32.2 The Contractor shall cooperate with the Engineer or his nominee in making and considering proposals for how the effect of such an event or circumstance can be avoided or reduced by anyone involved in the work and in carrying out any resulting instruction of the Engineer or his nominee.

C. QUALITY CONTROL

33. Identify Defects

The Engineer or his nominee shall check the Contractor's work and notify the Contractor of any Defects that are found. Such checking shall not affect the Contractor's responsibilities. The Engineer or his nominee may instruct the Contractor to search for a Defect and to uncover and test any work that the Engineer or his nominee considers may have a Defect.

34. Tests

If the Engineer or his nominee instructs the Contractor to carry out a test not specified in the Specification to check whether any work has a Defect and the test shows that it does the Contractor shall pay for the test and any samples. If there is no Defect the test shall be a Compensation Event.

35. Defect Liability

- 35.1 The Engineer or his nominee shall give notice to the Contractor of any Defects before the end of the Defects Liability Period, which begins at Completion and is defined in the Contract Data. The Defects Liability Period shall be extended for as long as Defects remain to be corrected.
- 35.2 Every time notice of a Defect is given, the Contractor shall correct the notified defect within the length of time specified by the Engineer or his nominee's notice. To the intent that the works shall, at or as soon as practicable after the expiration of the Defects Liability Period, be delivered to the Employer in the condition required by the Contract, fair wear and tear excepted, to the satisfaction of the Engineer, the Contractor shall:
- (a) Complete the work, if any, outstanding on the date stated in the Taking-Over Certificate within the date to be intimated by the engineer and
- (b) execute all such work of amendment, reconstruction, and remedying defects, shrinkages or other faults as the Engineer may, during the Defects Liability Period or within 14 days after its expiration, as a result of an inspection made by or on behalf of the Engineer prior to its expiration, instruct the Contractor to execute.

35.3 Cost of Remedying Defects

All work referred to in Sub-Clause 35.2 shall be executed by the contractor at his own cost if the necessity thereof is, in the opinion of the Engineer, due to:

- a) The use of materials, Plant or workmanship not in accordance with the Contract, or
- b) Where the Contractor is responsible for the design of part of the Permanent Works,

any fault in such design, or the neglect or failure on the part of the Contractor to comply with any obligation, expressed or implied, on the Contractor's part under the Contract.

35.4 Defects Liability Certificate

The Contract shall not be considered as completed until a Defects Liability Certificate shall have been signed by the Engineer and delivered to the Employer, with a copy to the Contractor, stating the date on which the Contractor shall have completed his obligations to execute and complete the Works and remedy any defects therein to the Engineer's satisfaction. The Defects Liability Certificate shall be given by the Engineer within 28 days after the expiration of the Defects Liability Period, or, if different defects liability periods shall become applicable to different Sections or parts of the Permanent Works, the expiration of the latest such period, or as soon thereafter as any works instructed, pursuant to Clauses 35, have been completed to the satisfaction of the Engineer.

35.5 Unfulfilled Obligations

Notwithstanding the issue of the Defects Liability Certificate the Contractor and the Employer shall remain liable for the fulfillment of any obligation incurred under the provisions of the Contract prior to the issue of the Defects Liability Certificate which remains unperformed at the time such Defects Liability Certificate is issued and, for the purposes of determining the nature and extent of any such obligation, the Contract shall be deemed to remain in force between the parties to the Contract.

36. Uncorrected Defects.

If the Contractor has not corrected a Defect within the time specified in the Engineer or his nominee's notice the Engineer or his nominee will assess the cost of having the Defect corrected, and the Contractor will pay this amount.

D. COST CONTROL

37. Bill of Quantities

- 37.1 The Bill of Quantities shall contain items for the construction, supply, installation, testing and commissioning work to be done by the Contractor.
- 37.2 The Bill of Quantities is used to calculate the Contract Price. The Contractor is paid for the quantity of the work done at the rate in the Bill of Quantities for each item.

38. Changes in the Quantities

- 38.1 If the final quantity of the work done differs from the quantity in the Bill of Quantities for the particular item by more than +25 % provided the change exceeds +10% of initial Contract Price, the Engineer or his nominee shall adjust the rate(s), to allow for the change.
- 38.2 The Engineer or his nominee shall not adjust rates from changes in quantities if thereby the Initial Contract Price is exceeded by more than 15 percent except with the Prior approval of the Employer.
- 38.3 If requested by the Engineer or his nominee where the quoted rate(s) of any item(s) is abnormally high, the Contractor shall provide the Engineer or his nominee with a detailed cost breakdown of such rate in the Bill of Quantities.

39. Variations

- 39.1 The Engineer shall make any variation of the form, quality or quantity of the Works or any part thereof that may, in his opinion, be necessary and for that purpose, or if for any other reason it shall, in his opinion, be appropriate, he shall have the authority to instruct the Contractor to do and the Contractor shall do any of the following:
- a) increase or decrease the quantity of any work included in the Contract,
- b) omit any such work,
- c) change the character or quality or kind of any such work,
- d) change the levels, lines, position and dimension of any part of the Works,
- e) execute additional work of any kind necessary for the completion of the Works,
- f) change any specified sequence or timing of construction of any part of the Works. No such variation shall in any way vitiate or invalidate the Contract, by the effect, if any, of all such variations shall be valued in accordance with Clause 40. Provided that where the issue of an instruction to vary the works is necessitated by some default of or breach of contract by the contractor or for which he is responsible, any additional cost attributable to such default shall be borne by the contractor. All

Variations shall be included in updated Programs produced by the contractor.

39.2 Instructions for Variations

The Contractor shall not make any such variation without an instruction of the Engineer. Provided that no instruction shall be required for increase or decrease in the quantity of any work where such increase or decrease is not the result of an instruction given under this clause, but is the result of the quantities exceeding or being less than those stated in the Bill of Quantities.

40. Payments for Variations

- 40.1 Variation permitted shall not exceed +25% in quantity of each individual item, and +10% of the total contract price. Within 14 days of the date of instruction for executing varied work, extra work or substitution, and before the commencement of such work, notice shall be given either (a) by the contractor to the Employer of his intention to claim extra payment or a varied rate or price, or (b) by the Employer to the contractor of his intention to vary rate or price.
- 40.2 For items not existing in the Bill of Quantities or substitution to items in the Bill of Quantities, rate payable should be determined by methods given below and in the order given below:
- i) Rates and prices in Contract, if applicable plus escalation as per contract.
- ii) Rates and prices in the Schedule of Rates applicable to the Contract plus ruling percentage.
- iii) Market rates of materials and labor, hire charges of plant and machinery used, plus 10% for overheads and profits of contractor.
- 40.3 For items in the Bill of Quantities but where quantities have increased beyond the variation limits, the rate payable for quantity in excess of the quantity in the Bill of Quantity plus the permissible variation should be:
- i) Rates and prices in contract, if reasonable plus escalation, failing which (ii) and (iii) below will apply
- ii) Rates and prices in the schedule of Rates applicable to the contract plus ruling percentage.
- iii) Market rates of material and labor, hire charges of plant and machinery used plus 10% for overheads and profits of contractor.
- 40.4 If there is delay in the Employer and the Contractor coming to an agreement on the rate of an extra item, rates as proposed by the Employer shall be payable provisionally till such time as the rates are

- finally determined or till date mutually agreed.
- 40.5 If the Engineer or his nominee decides that the urgency of varying the work prevent a quotation being given and considers not delaying the work, no quotation shall be given and the Variation shall be treated as a Compensation Event.

41. Cash flow forecasts

41.1 When the Program is updated, the contractor is to provide the Engineer or his nominee with an updated cash flow forecast.

42. Payment Certificates

- 42.1 The Contractor shall submit to the Engineer or his nominee monthly statements of the estimated value of the work completed less the cumulative amount certified previously.
- 42.2 The Engineer or his nominee shall check the Contractors' monthly statement within 14 days and certify the amount to be paid to the Contractor after taking into account any credit or debit for the month in question in respect of materials for the works in the relevant amounts and under conditions set forth in sub-clause 51.6 of the Contract Data (Secured Advance).
- 42.3 The value of work executed shall be determined by the Engineer or his nominee.
- 42.4 The value of work executed shall comprise the value of the quantities of the items in the Bill of quantities completed.
- 42.5 The value of work executed shall include the valuation of variations and Compensation Events.
- 42.6 The Engineer or his nominee may exclude any item certified in a previous certificate or reduce the proportion of any item previously certified in any certificate in the light of later information.

43. Payments

- 43.1 The bills for other Construction/Renovation/Miscellaneous works which are not paid on monthly basis the Contractor has to submit the bill within 7 days of joint measurement taken along with the concerned Engineer. The Engineer has to ensure that joint measurement to be completed within 7 days of completing of part work / running work. The concerned Engineer i/c shall check and make entries into bill/M.B within 10 days of submission of the interim bill and submit to Executive Engineer/ Superintending Engineer (Civil). The Executive Engineer/ Superintending Engineer (Civil) shall check the bills and after certification of the quantities as per manual shall forward to the Finance Department within 3 working days. Contractor and Assistant Engineer both jointly complete the measurements, if Contractor due to any reason does not attend/avoid joint survey/measurements the Executive Engineer shall give notice to the contractor to be present at the site for joint measurement within 7 days notice. If the contractor fails to attend the joint measurement second notice shall be issued to the contractor to attend the joint measurement within 3 days failure to attend the site for joint measurement the Assistant Engineer and AEE or EE would record the reason and complete the measurements in a transparent manner departmentally and submit the bill. Bills / Tax invoice shall be prepared and submitted by the Contractor. Joint
 - measurements shall be taken continuously and need not be connected with billing stage. System of 4 copies of measurements, one each for Contractor, Employer and Engineer or his nominee, and signed by both Contractor and Employer shall be followed.
- 43.2 Interim of bill amount will be paid within 14 days of submission of the bill.
- 43.3 Contractor shall submit final Bill within 60 days from the date of completion of work and the same will be paid by the Port within 30 days from the date of submission
- 43.4 The payment will be made to the contractor after deducting any dues payable to the Port statutory authorities etc
- 43.5 If an amount certified is increased in a later certificate as a result of an award by the DRB or an Arbitrator, the Contractor shall be paid interest upon the delayed payment as set out in this clause. Interest shall be calculated from the date upon which the increased amount would have been certified in the absence of dispute.

43.6 Items of the Works for which no rate or price has been entered in will not be paid for by the Employer and shall be deemed covered by other rates and prices in the Contract.

44. Compensation Events

- 44.1 The following mutually agreed Compensation Events unless they are caused by the Contractor would be applicable:
- (a) The Employer does not give access to a part of the Site by the Site Possession Date stated in the Contract Data.
- (b) The Employer modifies the schedule of other contractors in a way which affects the work of the contractor under the contract.
- (c) The Engineer or his nominee orders a delay or does not issue drawings, specifications or instructions required for execution of works on time.
- (d) The Engineer or his nominee instructs the Contractor to uncover or to carry out additional tests upon work which is then found to have no Defects.
- (e) The Engineer or his nominee unreasonably does not approve for a subcontract to be let.
- (f) Ground conditions are substantially more adverse than could reasonably have been assumed before issuance of Letter of Acceptance from the information issued to Bidders (including the Site Investigation Reports), from information available publicly and form a visual inspection of the site.
- (g) The Engineer or his nominee gives an instruction for dealing with an unforeseen condition, caused by the Employer, or additional work required for safety or other reasons.
- (h) Other contractors, public authorities, utilities or the Employer does not work within the dates and other constraints stated in the Contract that cause delay or extra cost to the Contractor.
- (i) The effect on the Contractor of any of the Employer's Risks.
- (j) Other Compensation Events listed in the Contract Data or mentioned in the contract.

Whenever any compensation event occurs, the contractor will notify the employer, within 14 days and provide a forecast cost of the compensation event.

44.2 If a Compensation Event would cause additional cost or would prevent the work being completed before the Intended Completion Date, the Contract Price shall be increased and/or the Intended Completion Date shall be extended. The Engineer or his nominee shall decide whether and by how much he Contract Price shall be increased and whether and by how much

the Intended Completion Date shall be extended.

44.3 As soon as information demonstrating the effect of each Compensation Event upon the Contractor's forecast has been provided by the Contractor, it is to be assessed by the Engineer or his nominee and the Contract Price shall be adjusted accordingly. If the Contractor's forecast is deemed unreasonable the Engineer or his nominee shall adjust the Contract Price based on Engineer or his nominee's own forecast. The Engineer or his nominee will assume that the Contractor will react competently and promptly to the event.

45. Tax

45.1 The rates quoted by the Contractor to be inclusive of taxes if any excluding GST that the Contractor will have to pay for the performance of this Contract. The Employer will perform such duties in regard to the deduction of such taxes at sources as per applicable law. Any new Taxes, levies, duties imposed after signing the Contract shall be reimbursed by the employer on production of documentary evidence. The GST shall be quoted separately in tax invoice. The contractor shall file the applicable returns with tax department in time and submit the same as documentary evidence.

46. Currencies

46.1 All payments shall be made in Indian Rupees unless specifically mentioned.

47. Price Adjustment. (Not Applicable)

48. Retention

- 48.1 The Employer shall retain from each payment due to the Contractor the proportion stated in the Contract Data until Completion of the whole of the Works.
- 48.2 Retention Money shall be deducted at the rate of 10% of the toatal tax invoice, from first Running Bill onwards subject to a max of 5% plus of the contract price including GST. Retention money shall be refunded after completion of defect liability period along with performance security.

49. Liquidated Damages

- 49A In case of delay in completion of the contract, liquidated damages (L.D) may be levied at the rate of half per cent (½%) of the contract price per week of delay, or part thereof subject to a maximum of 10 per cent of the contract price.
- 49A(i)The Employer, if satisfied, that the works can be completed by the contractor within a reasonable time after the specified time for completion,

may allow further extension of time at its discretion with or without the levy of L.D. In the event of extension granted being with L.D, the Employer will be entitled without prejudice to any other right or remedy available in that behalf, to recover from the contractor as agreed damages equivalent to half per cent (½%) of the contract value of the works including GST for each week or part of the week subject to the ceiling defined in sub-Clause 49 A.

In the event of forfeiting the LD / EMD / SD performance guarantee and while imposing penalty GST at applicable rate is applicable.

- 49A(ii) The Employer, if not satisfied that the works can be completed by the contractor, and in the event of failure on the part of the contractor to complete work within further extension of time allowed as aforesaid, shall be entitled, without prejudice to any other right, or remedy available in that behalf, to rescind the contract.
- 49A(iii) The Employer, if not satisfied with the progress of the contract and in the event of failure of the contractor to recoup the delays in the mutually agreed time frame, shall be entitled to terminate the contract.
- 49A(iv) In the event of such termination of the contract as described in clauses 49A(ii) or 49A(iii) or both the Employer shall be entitled to recover L.D. up to ten per cent (10%) of the contract value and forfeit the security deposit made by the contractor besides getting the work completed by other means at the risk and cost of the contractor.
- 49A(v) In case Part / portions of the work can be commissioned and the Port operates the portion for commercial purposes, the rate of LD will be restricted to the uncompleted value of work, the maximum LD being on the entire contract value.

50. Nominated Subcontractors

All specialists, merchants, tradesmen and others executing any work or supplying any good, materials, Plant or services for which provisional Sums are included in the Contract, who may have been or be nominated or selected or approved by the Employer or the Engineer, and all persons to whom by virtue of the provisions of the Contract, the Contractor is required to subcontract shall, in the execution of such work or the supply of such goods, materials, Plant or services, be deemed to be subcontractors to the Contractor and are referred to in this Contract as "Nominated Subcontractors".

51. Advance payment (Not Applicable)

The Employer shall make the following advance payments:

- 51.1 Mobilization Advance shall be paid up to 10% of Contract price, payable in two equal installments. The first installment shall be paid after mobilization has started and next installment shall be paid after satisfactory utilization of earlier advance.
- 51.2 Construction / installation equipment Advance shall be paid up to 5% of Contract price, limited to 90% of assessed cost of machinery.
- 51.3 Mobilization Advance and Construction Equipment Advance shall be paid at SBI PLR + 2% p.a. (as on date of payment) interest rate at the discretion of the employer and against Bank Guarantee for Mobilization Advance and against hypothecation of Construction Equipment to the Employer.
- 51.4 Equipment advance will be paid in two or more installments. First installment shall be paid after Construction Equipment has arrived at the site and next installment shall be paid after satisfactory utilization of earlier advance (s).
- 51.5 Recovery of Mobilization and Construction Equipment advance will start when 15% of the work is executed and recovery of total advance should be completed by the time 80% of the original Contract work is executed.
- 51.6 Secured Advance: The Engineer or his nominee shall make advance payment in respect of materials and plant brought to site but not yet incorporated and installed in the Works in accordance with conditions stipulated in the Contract Data.

75% of cost of materials and plant brought to site for incorporation into the works only shall be paid as Secured Advance. Materials which are of perishable nature should be adequately insured.

52. Securities

- 52.1 Security deposit shall consist of two parts
 - a) Performance security to be submitted at award of the work
 - b) Retention Money to be recovered from Running Bills.
- 52.2 The Security deposit at 10% of the contract amount including GST, of which 5% of contract price should be submitted as Performance Security within 21 days of receipt of letter of acceptance and balance 5% recovered as retention money from running bills. Recovery of 5% of retention money shall commence from the first RA bill onwards @ 10% for each bill. Retention money shall be refunded after completion of

defect liability period. The performance Bank Guarantee will be released after completion of defect liability period.

53. Removal Of Craft Or Plant Which Has Sunk (NA)

The Contractor shall forthwith and with dispatch at his own cost raise and remove any craft or plant (floating or otherwise) belonging to him or to any sub-contractor employed by him (including also any plant which is held by the Contractor or any sub-contractor under agreement for hire or hire-purchase) which may be sunk in the course of the construction completion or maintenance of the Works or otherwise deal with the same as the Engineer may direct or until the same shall be raised and removed, the contractor shall set al such buoys and display at night such lights and do all such things for the safety of navigation as may be required by the Engineer or by Employer. In the event of the Contractor not carrying out his obligation imposed upon him by this clause the Employer may provide buoy and light such sunken craft or plant and raise and remove the same (without prejudice to the right of the Employer to hold the Contractor liable under General Conditions) and the Contractor shall refund to the Employer all costs incurred in connection therewith.

Contractor's Temporary Moorings

Should the Contractor need, in connection with implementing the Works, to provide temporary moorings for his craft he may be allowed to do so in location and manner approved by the Engineer subject to all necessary permissions being first obtained by the Contractor from the authorities concerned. The Contractor shall not lay his temporary moorings such as to interfere with the port traffic and such moorings shall be removed if and when required by the Employer.

54. Cost of Repairs

54.1 Loss or damage to the Works or Materials to be incorporated in the Works between the Start Date and the end of the Defects Correction period shall be remedied by the Contractor at the Contractor's cost if the loss or damage arises from the Contractor's acts or omissions.

E. FINISHING THE CONTRACT

55. Completion

After completion of the work, the contractor will serve a written notice to the Engineer or his nominee/Employer to this effect. The Engineer or his nominee/Employer upon receipt of this notice shall conduct a complete joint

survey of the work within 7 days and prepare a defects list jointly. The defects pointed out by the Engineer or his nominee/Employer would be rectified by the contractor within 14 days and thereafter acceptance report be signed jointly by the contractor and the Employer. This joint acceptance report shall be treated as 'Completion Certificate'.

Substantial Completion of Parts

If any part of the Permanent Works has been substantially completed and satisfactorily passed any Tests on Completion prescribed by the Contract, the Engineer may issue a Taking-Over Certificate in respect of that part of the Permanent works before completion of the whole of the Works and, upon the issue of such Certificate, the Contractor shall be deemed to have undertaken to complete with due expedition any outstanding work in that part of the Permanent Works during the Defects Liability Period.

Surfaces Requiring Reinstatement

Provided that a Taking-Over Certificate given in respect of any Section or part of the Permanent Works before completion of the whole of the Works shall not be deemed to certify completion of any ground or surfaces requiring reinstatement, unless such Taking-Over Certificate shall expressly so state.

56. Taking Over

The Employer shall take over the Site and the Works within seven days of the Engineer or his nominee issuing a certificate of Completion.

Taking-Over Certificate

When the whole of the Works have been substantially completed and have satisfactorily passed any Tests on Completion prescribed by the Contract, the Contractor may give a notice to that effect to the Engineer, with a copy to the Employer, accompanied by a written undertaking to finish with due expedition any outstanding work during the Defects Liability Period. Such notice and undertaking shall be deemed to be a request by the Contractor for the Engineer to issue a Taking- over Certificate in respect of the Works. The Engineer shall, within 21 days of the date of delivery of such notice, either issue to the Contractor, with a copy to the Employer, a Taking- Over Certificate, stating the date on which, in his opinion, the Works were substantially completed in accordance with the Contract, or give instruction in writing to the Contractor specifying all the work which in the Engineer's opinion, is required to be done by the Contractor before the issue of such Certificate. The Engineer shall also notify the Contractor of any defects in the Works affecting

substantial completion that may appear after such instructions and before completion of the Works specified therein. The Contractor shall be entitled to receive such Taking-Over Certificate within 21 days of completion, to the satisfaction of the Engineer, of the Works so specified and remedying any defects so notified.

Taking Over of Sections or Parts

Similarly, in accordance with the procedure set out in above Clause, the Contractor may request and the Engineer shall issue a Taking-Over Certificate in respect of:

- a. any Section in respect of which a separate Time for Completion is provided in the appendix to Tender, or
- b. any substantial part of the Permanent Works which has been both completed to the satisfaction of the Engineer and, otherwise than as provided for in the Contract, occupied or used by the Employer, or
- c. Any part of the Permanent Works which the Employer has elected to occupy or use prior to completion (where such prior occupation or use is not provided for in the Contract or has not been agreed by the Contractor as a temporary measure).

57. Final Account

The Contractor shall supply to the Engineer or his nominee a detailed account of the total amount that the Contractor considers payable under the Contract before the end of the Defects Liability Period. The Engineer or his nominee shall issue a Defects Liability Certificate and certify any final payment that is due to the Contractor within 60 days of receiving the Contractor's account if it is correct and complete. If it is not, the Engineer or his nominee shall issue within 15 days a schedule that states the scope of the corrections or additions that are necessary for the correction and certify payment of 50% of the undisputed amount to the contractor. If the Final Account is still unsatisfactory after it has been resubmitted the Engineer or his nominee shall decide on the amount payable to the Contractor and issue a payment certificate, within 60 days of receiving the Contractor's revised account.

58. Submission of 'As built Drawings (NA)

"As built" Drawings are required to be submitted by the Contractor and shall be supplied by them by the dates stated in the Contract Data. If the Contractor does not supply the Drawings and/or manuals by the dates stated in the Contract Data, or they do not receive the Engineer or his nominee's approval, the Engineer or his nominee shall withhold the amount stated in the Contract Data from payments due to the Contractor.

59. Termination

59.1 The Employer or the Contractor may terminate the Contract if the other

- party causes a fundamental breach of the Contract.
- 59.2 Fundamental breaches of Contract include, but shall not be limited to the following:
- (a) The Delay in signing of contract agreement beyond prescribed time limit.
- (b) The Contractor stops work for 28 days when no stoppage of work is shown on the current Program and the stoppage has not been authorised by the Engineer or his nominee.
- (c) the Engineer or his nominee instructs the Contractor to delay the progress of the Works and the instruction is not withdrawn within 28 days.
- (d) the Employer or the Contractor becomes bankrupt or goes into liquidation other than for a reconstruction restructure or amalgamation.
- (e) a payment certified by the Engineer or his nominee is not paid by the Employer to the Contractor within 50 days of the date of the Engineer or his Nominee's certificate:
- (f) The Engineer or his nominee gives Notice that failure to correct a particular Defect is a fundamental breach of Contract and the Contractor fails to correct it within a reasonable period of time determined by the Engineer or his nominee.
- (g) The Contractor does not maintain a security which is required.
- (h) the Contractor has delayed the completion of works by the number days for Which the maximum amount of liquidated damages can be paid as defined in The Contract data and
- (i) if the Contractor, in the judgment of the Employer has engaged in corrupt or Fraudulent practices in competing for or in the executing the Contract.

For the purpose of this paragraph: "corrupt practice" means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution. "Fraudulent practice" means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Employer, and includes collusive practice. Bidders (prior to or after bid submission) designed to establish bid prices at artificial non-competitive levels and to deprive the Employer of the benefits of free and open competition."

59.3 When either party to the Contract gives notice of a breach of contract to the Engineer or his nominee for a cause other than those listed under Sub Clause 59.2 above, the Engineer or his nominee shall decide whether the breach is fundamental or not.

- 59.4 Notwithstanding the above, the Employer may terminate the Contract for convenience subject to payment of compensation to the contractor including loss of profit on uncompleted works. Loss of profit shall be calculated on the same basis as adopted for calculation of extra/additional items.
- 59.5 If the Contract is terminated the Contractor shall stop work immediately, make the Site safe and secure and leave the Site as soon as reasonably possible.

60. Payment upon Termination

- 60.1 If the Contract is terminated because of a fundamental breach of Contract by the Contractor, the Engineer or his nominee shall issue a certificate for the value of the work done less advance payments received up to the date of the issue of the certificate, less other recoveries due in terms of the contract, less taxes due to be deducted at source as per applicable law and less the percentage to apply to the work not completed as indicated in the Contract Data. Additional Liquidated Damages shall not apply. If the total amount due to the Employer exceeds any payment due to the Contractor, the difference shall be a debt payable to the Employer.
- 60.2 If the Contract is terminated at the Employer's convenience or because of a fundamental breach of Contract by the Employer, the Engineer or his nominee shall issue a certificate for the value of the work done, the reasonable cost of removal of Equipment repatriation of the Contractor's personnel employed solely on the Works, and the Contractor's costs of protecting and securing the Works and loss of profit on uncompleted works less advance payments received up to the date of the certificate, less other recoveries due in terms of the contract and less taxes due to be deducted at source as per applicable law.

61. Property

All materials on the Site, Plant, Equipment, Temporary Works and Works for which payment has been made to the contractor by the Employer, are deemed to be the property of the Employer, if the Contract is terminated because of a Contractor's default.

62. Release from Performance

If the Contract is frustrated by the outbreak of war or by other event entirely outside the control of either the Employer or the Contractor, the Engineer or his nominee shall certify that the Contract has been frustrated. The

Contractor shall leave the Site and stop work as quickly as possible after receiving this certificate and shall be paid for all work carried out before receiving it and for any work carried out afterwards to which commitment was made.

F. SPECIAL CONDITIONS OF CONTRACT

The conditions of contract shall be the general conditions of contract in Section-III (v) as modified or added by the following condition of special conditions as provided in Section – III(vi) herein, which shall be read and construed with the general condition in Section – 3 A to E as if they were incorporated therein. In so far as any of the condition of the special conditions may conflict or be in consisting with any of general conditions of in Section -3F- Special condition of the contract shall prevail.

63. Labour

The Contractor shall, unless otherwise provided in the Contract, make his own arrangements for the engagement of all staff and labour, local or other, and for their payment, housing, feeding and transport.

The Contractor shall, if required by the Engineer or his nominee, deliver to the Engineer or his nominee a return in detail, in such form and at such intervals as the Engineer or his nominee may prescribe, showing the staff and the numbers of the several classes of labour from time to time employed by the Contractor on the Site and such other information as the Engineer or his nominee may require.

64. Compliance with labour regulations

During continuance of the contract, the Contractor and his sub contractors shall abide at all times by all existing labour enactment and rules made there under, regulations, notifications and bye laws of the State or Central Government or local authority and any other labour law (including rules) regulations, bye laws that may be passed or notification that may be issued under any labour law in future either by the State or Central Government or the local authority. Salient features of some of the major labour laws that are applicable to construction industry are given below. The Contractor shall keep the Employer indemnified in case any action is taken against the Employer by the competent authority on account of contravention of any of the provisions of any Act or rules made there under, regulations or notifications including amendments. If the Employer is caused to pay or reimburse such amounts as may be necessary to cause or observe, or for non-observance of the provisions stipulated in the notifications/bye laws/Acts/Rules/regulations including

amendments, if any, on the part of the Contractor the Engineer or his nominee/Employer shall have the right to deduct any money due to the Contractor including his amount of performance security. The Employer / Engineer or his nominee shall also have right to recover from the Contractor any sum required or estimated to be required for making good the loss or damage suffered by the Employer.

The employees of the Contractor and the Sub-Contractor in no case shall be treated as the employees of the Employer at any point of time.

65. Safety, Security and Protection of the Environment.

Subject and without prejudice to any other provision of the Contract, the Contractor shall take all reasonable precautions:

- (a) In connection with underground water resources (including percolating water) to prevent
- (b) Any interference with the supply to or abstraction from such sources Pollution of the water so as to affect adversely the quality thereof.
- (c) All works shall be carried out without unreasonable noise and disturbance. The Contractor shall indemnify the Employer from and against any liability for damages on account of noise or other disturbance created while or in carrying out the work and from and against all claims, demands, proceedings, damages, costs, charges and expenses whatsoever in regard or in relation to such liability.
- (d) The Contractor at his own cost shall make such provisions for lighting of Works, Temporary Works, Materials and Plant and shall provide all such marks and lights as may be required by the Employer or the Engineer or any other authority having jurisdiction over the Site together with all labour stores and services required for their efficient working and use at any time, day or night.
- (e) The Contractor shall also provide at his own cost every description of watching and maintenance required in connection with the foregoing, and all other services for protecting and securing all places dangerous whether to Contractor's workmen or to other persons until the Works are handed over to the Employer, or till such time when the Engineer decides that such services are no longer required.

All lights provided by the Contractor shall be placed or screened such as not to interfere with any navigation lights or with any traffic or signal lights of any local or other authority.

66. Insurance of Works and Contractor's Equipment

The Insurance shall be issued by Nationalized Insurance Company from its Mangalore Branch which has been determined by the Contractor to be

acceptable to the Employer.

The contractor shall at his own costs and expenses obtain and shall cause any subcontractor to obtain such insurance as may be necessary to cover the liability of the contractor or as the case may be of such subcontractor in respect of personal injuries and death arising out of or in the course of or caused during the execution of the works for a minimum amount of Rs. 25 lakhs and shall produce or cause any such subcontractor to produce for inspection the relevant policy or policies together with receipt for the premium paid under such policy/policies as and when required by the Employer.

- i. The Employer (NMPA) shall not be liable for any accident, damage or compensation payable to any workman or other person in the employment of the Contractor or any Subcontractor.
- ii. Employer Liability Insurance: The Contractor shall indemnify and keep indemnified the Employer i.e. NMPA against all damages or compensation payable at Law in respect of or in consequence of any accident or injury to any workman or other person in the employment of the Contractor or Sub-Contractor against all claims, demands, proceedings, costs, charges and expenses whatsoever in respect thereof or in relation thereto and the Employer shall be at liberty to deduct or adjust from the Contactor's bills an amount that Employer may be called upon to pay towards claims, demands, proceedings, costs, charges and expenses Whatsoever in respect of or in relation to any accident or injury referred to above without any reference to the Contractor.
- iii. The Contractor shall comply with all the Central State and Municipal Laws and Rules and shall be solely responsible for complying with the provisions of the Contract Labour (Regulations & Abolition) Act, 1970 & the contract labour (Regulation & Abolition) Karnataka Rules 1974 and rules there under and the enactments that may be applicable including ESI Act, the payment of wages act, Provident Fund Act, the Minimum Wages Act, the Factory's Act. The Workmen Compensation Act or any other applicable legislation and the Municipal by-laws or other statutory Rules and Regulations whatsoever in force if these are applicable. Any obligations finding or otherwise missed under any statutory enactments, rules & regulations there under shall be the responsibility of the Contractor and the NMPA will take no responsibility for the same. The Contractor should take Workmen's Compensation Policy for his Workers, who are not covered under ESI and submit the same to the EIC immediately after commencement of the work.

- iv. The Contractor is liable to pay all Statutory Compensation to the Labourers/persons engaged by him for the satisfactory execution of the works. If any claim is made against New Mangalore Port Authority on this work, the Port Authority shall have the right to deduct the same from the bill amount payable to the contractor after verification of the validity and if admissible as per rules.
- v. PERSONAL PROTECTIVE EQUIPMENTS The Contractor shall ensure the use of PPE such as helmets, safety shoes, nose masks, hand gloves, Safety Harness or any other equipment as required depending on nature of work by his staff at site.

67. War Risks Insurance

If the Contractor receives instructions from the Employer to insure against war risks, such insurance if normally available shall be effected, at the cost of the Employer, with the Insurance Company acceptable to the Employer and shall be in the joint names of the Employer and the Contractor.

68. Royalty

Except where otherwise stated, the contractor shall pay to the authority all tonnage and other royalties, rent and other payments or compensation if any, for getting stone, sand, gravel, clay or other materials by him and his subordinates and his subcontractors and required for the works, at the rates and such conditions as notified by the State Government. The applicable rates for royalty is enclosed as Schedule-A in Volume –III. The contractor should submit the Mineral Dispatch Permit (MDP) in original for the quantity executed by the contractor for the requisite quantity of material incorporated in works for which MDP is issued by the authorized supplier. If contractor fails to submit the MDP in original the amount equal to 5 times the royalty charges shall be deducted from the contractor's bills as per prevailing orders issued by the Authority.

69. Transport of Contractor's Equipment or Temporary Works

If it is found necessary for the Contractor to move one or more loads of heavy constructional plant or equipment materials or pre-constructed units or parts of units of work over roads, highways or bridges on which such oversized and over weight items are not normally allowed to be moved, the Contractor shall obtain prior permission from the concerned authorities. Payments for complying with the requirements, if any, for protection of or strengthening of the roads, highways or bridges shall be deemed to be included in his contract price.

70. Transport of Materials or Plant

The contractor shall save harmless and indemnify the Employer in respect of all claims, proceedings, damages, costs, charges and expenses whatsoever arising out of or in relation to any claim made by the concerned authorities in respect of damage or injury to roads, highways or bridges. In case of failure of the Contractor to settle such claims and in case the Employer is held responsible for payment to the authorities, then the Employer shall settle the claim and the Employer's expenses in this regard, as certified by the Engineer, may be deducted by the Employer from any money due or to become due to the Contractor and the Engineer shall notify the Contractor accordingly with a copy to the Employer.

71. Labour Laws & Regulations

The Contractor shall at all times during the continuance of the Contract comply fully with all existing Acts, regulations and bye-laws including all statutory amendments and re-enactment of State or Central Govt. and other local authorities and any other enactments and act that may be passed in future either by the State or the Central Govt. or local authority, including Indian Workmen's Compensation Act, Contract Labour (Regulation And Abolition) Act 1970 and Equal Remuneration Act 1976, Employees' State Insurance Act, 1948, Factories Act, Minimum Wages Act, Provident Fund Regulations. Employees' Provident Fund Act and schemes made under the same Act, Health and Sanitary Arrangements for Workmen, Insurance and other benefits and shall keep the Employer indemnified in case any action is commenced for contravention by the Contractor. If the Employer is caused to pay or reimburse any amounts as may be necessary to cause or observe, or for non-observance of the provisions stipulated here-forth on the part of the Contractor, the Engineer shall have the right to recover from the Contractor any sum required estimated to be required for making good the loss or damage suffered by the Employer. The Tenderers must have valid ESI and PF registration and shall maintain the records prescribed under ESI Regulations and PF Act & make the contribution towards ESI and PF in respect of persons employed by the Contractor. The contractor shall make available such records for inspection by ESI and PF authorities during inspection and furnish the copies of such records to the employer regularly. The EPF and ESI contribution on the part of the employer in respect of this contract shall be paid by the contractor. These contributions on the part of Employer paid by the contractor shall be reimbursed by the Engineer –in – charge to the contractor on actual basis. The minimum wages applicable for Mangalore City is enclosed as Schedule – B in Volume – III.

71.1. Accident Prevention/Safety Officer

The Contractor shall have on his staff on site an officer dealing with all matters regarding safety and protection against, accidents of all staff and labour. This officer shall be qualified for this work and shall have the authority to issue instructions and shall take protective measures to prevent accidents.

71.2 Disorderly Conduct

The Contractor shall at all times take all reasonable precautions to prevent any unlawful, riotous or disorderly conduct by or amongst his staff and labour and for the preservation of peace and protection of Persons and property in the neighborhood of the Works from the same.

71.3 Health and Safety

Due precautions shall be taken by the Contractor, and at his own cost, to ensure the safety of his staff and labour and, in collaboration with and to the requirements of the local health authorities, to ensure that medical staff, first aid equipment and stores, sick bay and suitable ambulance services are available at the camps, housing and on the site at all times throughout the period of the Contract and that suitable arrangements are made for the prevention of epidemics and for all necessary welfare and hygiene requirements.

71.4 Supply of Water

The Contractor shall, so far as is reasonably practicable, having regard to local conditions provide on the Site, to the satisfaction of the Engineer's Representative, an adequate supply of drinking and other water for the use of the Contractor's staff and work people.

71.5 Alcoholic Liquor or Drugs

The Contractor shall not, otherwise than in accordance with the Statues, Ordinances and Government Regulations or Orders for the time being in force, import, sell, give, barter or otherwise dispose of any alcoholic liquor, or drugs or permit or suffer any such importation, sale, and gift, barter disposal by his sub-contractions agents or employees.

71.6 Arms and Ammunition

The Contractor shall not give, barter or otherwise dispose of to any persons or

person, any arms or ammunition of any kind or permit or suffer the same as aforesaid.

71.7 Festivals and Religious Customs

The Contractor shall in all dealings with labour in his employment have due regard to all recognized festivals, days of rest and religious or other customs.

71.8 Epidemics

In the event of any outbreak of illness of an epidemic nature, the Contractor shall comply with and carry out such regulations, orders and requirements as may be made by the Govt., or the local medical or sanitary authorities for the purpose of dealing with and overcoming the same.

71.9 Employment of Person in the Service of Others

The Contractor shall not recruit or attempt to recruit his staff and labour from amongst persons in the service of the Employer or other agencies engaged for any works of the Employer.

71.10 Housing for Labour

Save in so far as the Contract otherwise provides, the Contractor shall provide and maintain such accommodation and amenities as he may consider necessary for all his staff and labour employed for the purposes of or in connection with the Contract, including all fencing water supply (both for drinking and other purposes), electricity supply, sanitation, cook houses fire prevention and fire-fighting equipment, crèche for children of his staff and labour employed for the purposes, furniture, other requirements in connection with such accommodation or amenities. On completion of the Contract, unless otherwise agreed with the Employer, the temporary camps/housing provided by the Contractor shall be removed and the site reinstated to its original condition, all to the approval of the Engineer. The land for construction of labour camps shall be allotted outside the security area to the extent available and such area allotted for labour camps will be charged a ground rent at TAMP approved rates. The ground rent is liable for change as per the prevailing TAMP rates from time to time during the currency of the contract.

71.11 Fair Wages, Records, Inspection

The Contractor shall pay the labourers engaged by him on the work not less than a fair wage which expression shall mean whether for time or piecework the respective rates of wages as fixed by the Public Works Department as fair wages for Dakshina Kannada District payable to the

different categories of labourers of those notified under the Minimum Wages Act.

The Contractor shall maintain records of Wages and other remuneration paid to his employee in such form as may be convenient and to the requirements of the Employer/Engineer and the Labour Enforcement Officer (Central), Ministry of Labour, Govt. of India, or such other authorized person appointed by the Central Govt. The Contractor shall allow inspection of the aforesaid Wage Records and Wage Slips to the Engineer and to any of his workers or to his agent at a convenient time and place after due notice is received, or to any other person authorized by him on his behalf.

71.12 Reporting of Accidents

The Contractor shall report to the Engineer details of any accident as soon as possible after its occurrence. In the case of any fatality or serious accident, the Contractor shall, in addition, notify the local police authorities immediately by the available means.

71.13 Observance by Sub-Contractors

The Contractor shall be responsible for observance by his subcontractors of the foregoing provisions.

71.14 Port Entry Permission

The Contractor shall submit prior application for Port entry passes to the concerned Port authority for his Materials, labors and the staffs engaged in the works. The Contractor has to get the vehicle and labor RIFD based passes for the entry inside the wharf area based on prevailing rates.

71.15 Site - Protected Area

The Site of Work is a protected area. Entry to the Port premises is regulated by entry passes. These passes will be issued by the Central Industrial Security Force or any other authority authorized by the Employer. The Contractor should furnish a list of person for whom the passes are to be issued to the Engineer and arrange to obtain the passes from the appropriate authority, based on the recommendation of the Engineer and abide by the Rules of the New Mangalore Port Authority with regard to entry etc. For the entry of trucks and other vehicles also, the Contractor should obtain necessary permits. The Contractor shall retain the original passes obtained by them in respect

of their labour and staffs engaged in the Works and produce the same to the Engineer as and when called for. It should not be either destroyed or allowed to be taken by the labour/staff after its use.

72. Life Saving Appliances and First Aid

The Contractor shall provide and maintain upon the Works sufficient proper and efficient life saving appliances and first aid equipment to the approval of the Engineer. The appliances and equipment shall be available for use at all times.

73. Diving Operations

- a) Any diving work shall be carried out in accordance with the Diving Operations Regulations of the Government of India.
- b) Before any diving work is undertaken the Contractor shall supply the Engineer or his representative with two copies of the Code of signals to be employed and is to have a copy of such Code Prominently displayed on the craft or structure from which the operations take place

74. Bribes

If the Contractor, or any of his Subcontractors, agents or servants gives or offers to give to any person any bribe, gift, gratuity or commission as an inducement or reward for doing or forbearing to do any action in relation to the Contract or any other contract with the Employer, or for showing or forbearing to show favour or disfavor to any person in relation to the Contract or to any other contract with the Employer, then the Employer may enter upon the Site and the works and terminate the employment of the Contractor and the provisions of Clause 63 hereof shall apply as if such entry and termination had been made pursuant to that Clause.

The bidders shall give an undertaking that they have not made any payment or illegal gratification to any person/authority connected with the bid process so as to influence the bid process and have not committed any offence under the PC Act in connection with the bid.

75. Details to be Confidential

The Contractor shall treat the details of the contract as private and confidential, save insofar as may be necessary for the purposes thereof, and shall not publish or disclose the same or any particulars thereof in any trade or technical paper of elsewhere without the previous consent in writing of the employer. If any dispute arises as to the necessity of any publication or

disclosure for the purpose of the Contract the same shall be referred to the decision of the Employer whose award shall be final.

76. Contractor's Temporary works, office, etc.

- The Contractor shall submit to the Engineer for his approval not less than 15 days before commencement of erection of any part of Temporary Works, drawings and detailed proposals for the method of construction of Temporary works such as office, store, false work and temporary platforms etc. which he intends to construct for the execution of the contract and no such work shall be constructed before obtaining the written approval of Chief Engineer. These temporary works, office, store etc. shall be erected at or near the work area subject to approval of the Employer and the land space for the same will be allotted free of ground rent to the extent available. The Contractor shall obtain permission for any Temporary Works and would ensure that during execution of works the statutory requirements of the concerned authorities such as New Mangalore Port Authority, Police, Customs, etc. would be complied with.
- 76.2 Submission of Reports, Returns, etc.

 All reports, statements, returns, drawings, diagrams etc. which the

 Contractor is required to submit to the Engineer during the progress of
 the Works, shall be furnished in triplicate without any additional cost.

77. Water Supply

Water to the extent available will be supplied to the Contractor at a fixed point on the main water supply line within the Port area. The plumbing connection and extension of necessary supply pipeline to the working area shall be arranged by the Contractor at his own cost. The Contractor shall also provide a water meter at his cost for metering the quantity of water used. Charges for the consumption of the water will be paid by the Contractor to the Employer at notify rate as applicable time to time during the currency of the Contract. For non-supply of water at any stage port will not be responsible and the Contractor shall not have any claim whatever for loss or damage.

78. Power Supply

The Electricity connection for lighting, welding and other mechanical works to the extent available will be made available by the Employer within the Port area. Drawing of power lines etc. from the available point of supply of power to the actual work site either by overhead lines or underground cables shall be arranged by the contractor at his cost. The temporary lines and connections by the Contractor shall be approved by the Engineer's representative before availing power. The Contractor shall provide Trivector Meter to read consumption in units, power demand and power factor.

The Contractor shall indicate his requirement of power to the Engineer within 15 days from the date of the letter of acceptance of the tender. If the power requirement is more than 50 KW, the Contractor has to avail the power supply at 11 KV and install his own transformer of suitable capacity and work carried out as per IE Rules & Regulations as approved by the CEA. The Contractor shall pay to the Employer, the power charges as per the prevailing Tariff schedule of MESCOM in force during the work of the Contractor. At present, it is Rs.7.46 per unit consumed and demand charges @ Rs. 190.00 per KVA or part thereof per month on connected load, security deposit Rs. 4,604.00 per KVA along with departmental charges @ 23.75% of the bill amount. The Contractor shall also pay the connection and disconnection charges as applicable.

The Contractor shall ensure that the power factor of the system does not fall below 0.90 at any time and shall provide at his cost required capacity capacitors bank to maintain the Power Factor of all power loads. If the capacity of the capacitor found less than stipulated as per regulation during inspection, surcharge at Rs. 0.03 per unit will be levied. The contractor shall pay refundable Security Deposit of Rs. 4,604/- per KVA of the sanctioned load, before availing the power supply in the form of a Demand Draft drawn in favour of FA&CAO, NMPA from any Scheduled Bank.

The Contractor shall submit a complete drawing of the power points, wiring, diagram indicating all electrical loads, earthing etc. in complete shape along with the completion report. The Trivector Meter provided is calibrated either by M/s. MESCOM or NITK, Surathkal, and such a Certificate to be produced. For non-supply of power at any stage port will not be responsible and the Contractor shall not have any claim whatever for loss or damage.

79. Taxes and Duties

- 79.1 The Contractor shall pay Tax if any and other levies as applicable from time to time. GST at applicable rate shall be shown separate line items in the Tax invoice.
- 79.2 Sales / Turnover Tax on Works Contract (Deleted)
- 79.3 Income Tax

The Contractor and his staff shall be responsible for payment of all personal income taxes to the concerned authorities as per the law in force from time to time. Deduction of Income Tax shall be made by the Employer from each certificate of payment to the contractor at the rate of 2% plus surcharge or such other rates as may be specified by the Central Government from time to time, on the gross amount of the Contractor's bill for payment.

79.4 Goods and Service tax

The contractor shall not include GST component in rate. The GST shall be paid to the contractor separately as applicable. The contractor shall submit running account bills indicating GST separately as applicable. The Contractor shall be responsible for the payment of GST applicable, to the GST authority. The contractor shall file the applicable returns with tax department in time and submit the same as documentary evidence.

The invoice with respect to supplies should contain following information:-

- Name of the Customer : New Mangalore Port Authority
- GSTIN of the Customer: 29AAALN0057A2ZG
- All other information as specified in GST act and GST tax invoice rules such as SAC code, Supplier address, Supplier GSTIN, IRN number QR code etc.

Noncompliance of the above result in rejection of invoice.

The Invoice should be uploaded to GST website on monthly basis with in the due date as specified by GST act. Input tax credit lost by Port due to any error, omission or non filing of return will be recovered from any amount due to the supplier Any input tax credit lost by the Port due to due to any error, omission or non filing of return will be recovered from the bills and other monies available with the Port

80. Price Adjustment (not applicable to this contract)

81. Noise and Disturbance

All works shall be carried out without unreasonable noise and disturbance. The Contractor shall indemnify the Employer from and against any liability for damages on account of noise or other disturbance created while or in carrying out the work and from and against all claims demands proceedings damages costs charges and expenses whatsoever in regard or in relation to such liability.

82. Safety Code

Necessary Indian Safety regulations for the safety purpose shall be adhered to by the contractor and he will be held responsible for any violations of the same. The set of such conditions (regulation) is available with NMPA and the contractor is required to go through it before tendering.

Besides the above, the Contractor shall also scrupulously adhere to and observe the following safety codes:

The Contractor has to provide sufficient barricades to site of work so that traffic plying nearby should not damage the recently concreted work. In case of any damage on account of above, the entire responsibility will remain with contractor and nothing extra will be paid on this account.

Suitable and strong scaffolds should be provided for the workmen for all work that cannot be safely done from ground. No portable single ladder shall be over 8 meters in length. Hoisting machines and tackles used in the works including their attachments, and supports shall be in perfect condition as per stipulations of the relevant Rules. The ropes used for hoisting or lowering materials or as means or suspension shall be of durable quality and adequate strength and free from defects.

The excavated material shall no be placed within 1.5 meters of the edge of the trench or half of the depth of the trench, whichever is more. All trenches and excavation shall be provided with necessary fencing to lighting. Every opening in the floor of a building or in a working platform shall be provided with suitable fence to prevent the fall of persons or materials. No floor, roof or other parts of the structure shall be so overloaded with debris or materials as to render it unsafe.

Workers employed on mixing and handling materials such cement, cement mortar, concrete, lime mortar and asphalt shall be provided with protective footwear and rubber hand gloves and thin cloth for covering face and head.

Those engaged in welding work shall be provided with welder protective eye shield and glove.

All safety rules shall be strictly followed while working on live electrical systems or installations as stipulated in the relevant Rules.

83. Port Authority Rules

The Contractor shall observe the Conservancy Rules relating to the harbour and shall always take such necessary additional steps to keep the harbour waters free of noxious or unhygienic matters coming from his works as are required by the Employer. Under no circumstances shall inflammable materials be allowed to spill into the harbour waters.

The Contractor shall always observe and comply with the working rules and regulations of the Port Authority in force or as issued from time to time.

84. Execution of work

The contractor shall be required to execute the work in such a way so as not

to cause any damage, hindrance or interference with port activities going on in the area or nearby. He should not also deposit the materials at such places which may cause inconvenience to the public and the work going on in the nearby area The Contractor shall have to make good all damages done by him to the structures nearby while executing the work and no extra payment shall be made to him on that account.

All the materials required to be used in the work shall have to be got approved from the Engineer-in-Charge before stacking at the site of work.

Barricading, including proper lighting arrangement in the night at the required places shall have to be provided by the contractor at his own cost, including necessary arrangements for proper movement of traffic by carefully maintained approaches and road diversions with suitable sign boards for indications of road signs etc. as directed by the Engineer-in-Charge.

85. Customs Duty

Being Port Development Project, Customs Duty shall be applicable as per project import chapter 9801.00 read with Notification 17-2001, serial No. 38 (vi) and Notification 42-96 amended by 21-2000 of customs tariff, Government of India.

Customs Duty leviable shall be paid directly by the Contractor to the Customs Authorities, Government of India. The Employer shall reimburse this amount upon submission of documentary evidence in original for the proof of payment of such Customs Duty. The reimbursement of such amount towards Customs Duty shall be limited to the Ceiling amount quoted by the Contractor in the Bill of Quantities as above. If the Contractor incurs Customs Duty Levy less than the said Ceiling Amount, the reimbursement by the Employer shall be limited to the documented cost of Customs Duty levies actually paid to the Customs Authorities, Government of India. If the Actual Customs Duty levies paid by the Contractor exceeds the said Ceiling Amount, then the reimbursement by the Employer shall be limited to the Ceiling Amount. The reimbursement of the Customs Duty will be limited only to the Imported Materials listed in "Preamble and Bill of Quantities", BOQ No..... During the execution of the Works, if it necessitates for expeditious completion of the Works, Contractor may resort to import of any of the materials not listed aforesaid, with the approval of the Employer. However, the aggregate amount of Customs Duty to be reimbursed shall not exceed the lump sum amount offered in the Priced Bill of Quantities.

It shall be the responsibility of the Contractor to provide the requisite particulars and documents to the customs and other Government authorities and get the Imported Materials cleared and transported in time. The Contractor shall be fully responsible for port and Customs clearance including stevedoring, handling, unloading, loading, storage, inland transportation, if any of materials, equipments and plant to storage godowns, yards, sites etc. The contractor shall be fully responsible for any delays, penalties charges and losses if any in this regard.

The Employer shall upon request from the Contractor along with necessary details, provide recommendatory letter(s) for Imported Materials at concession rate or Customs Duty as applicable. However, the responsibility for obtaining such concession rate of customs duty shall be that of the Contractor.

It shall be the responsibility of the Contractor to check the latest position on Customs duty levies applicable and the Employer does not accept any liability on the account. For bill of Lading, the "Consignee" for permanent materials to be incorporated into the Works will be the New Mangalore Port Authority. The Contractor will be "Notify Party". Notwithstanding the above, obtaining "Essentiality Certificate" (if any), payment of deposit (if any) towards Customs Duty, etc. shall be the responsibility of the Contractor.

The Contractor shall give an undertaking follows:

- a) Being the ultimate Employer of the materials to be imported and incorporated into the works covered under the Tender _____ we request New Mangalore Port Authority to be consignee in the matter of permanent materials to be imported by us at our cost (covering payments of materials by letter of credit) including freight, insurances, taxes and any other charges whatsoever payable in connection with the import and its incorporation into the work.
- c) New Mangalore Port Authority becoming a consignee is a matter of convenience and we undertake to abide by all the obligations, responsibilities etc. as if we are our self a consignee.
- d) In respect of nay consequences arising out of New Mangalore Port Authority becoming the consignee we hereby unequivocally and irrevocably agree to indemnify New Mangalore Port Authority for such consequences.
- e) We also undertake and confirm to obtained all permits and licenses etc. at our own

- cost. New Mangalore Port Authority's responsibilities in this regard will be the same as under the said contract and limited to issuing required recommendatory letters for obtaining such permits and licenses.

86. Drawings & Designs

- General details of the works are shown on the drawings accompanying this (a) tender document. The Engineer will supply to the Contractor from time to time during the progress of the works such further working drawings as will be necessary in his opinion for the proper and adequate execution and maintenance of the Works in accordance with the Engineer's designs and/or any modification thereof as decided by the Engineer and the Contractor shall carry out the work in accordance with the said working drawings. Two sets of such working drawings will be issued. If the Contractor requires more sets he will have to make his own arrangement at his cost. Residual Design, Detailing & Engineering: - The Engineer to the project has done the detailed design and engineering for the subject tender. During execution of the work the residual design, detailing and engineering, if needed, is to be carried out by the contractor at no extra cost to the Employer. For equipment/ Installations detailed drawings need to be produced by the contractor at no extra cost to the Employer. The contractor shall also get approved such design, detailing & engineering from the Engineer.
- (b) In the event of the Contractor proposing any alteration/modification to the Engineer's design, detail, method of construction, he shall at his own expenses prepare and submit for approval of the Engineer copies in duplicate (in the first instance) of detailed working drawings which may be required for such alteration/modification and at the same time call the attention of the Engineer to any alternative detail or modification of the contract drawings which the Contractor may wish to make at least 30 days prior to the commencement of the work or part of the work to which such drawings relate. The contractor shall at the same time, if so required by the Engineer, furnish calculation sheets in duplicate relating to the strength and anticipated deflections in respect of such altered/modified works. The Engineer will, after any such alteration which he may approve, record on the copies as amended his approval and will return one copy of the drawings and calculation sheets

the contractor, who shall carryout the work in accordance therewith. The contractor shall forward to the Engineer three additional copies of the working drawings and calculation sheets as approved in additions to these working drawings and calculation sheets as approved. In addition to these working drawings are also to be submitted (the same procedure as in the ease of the contractor) in respect of any work proposed to be executed by sub-contractors. The approval of the Engineer of all or any of the calculation sheets, drawings shall not relieve the contractor of responsibility in connection with the execution of the altered/modified or subcontractor's work.

(c) Submission of 'As built Drawings'

"As built" Drawings are required to be submitted by the Contractor and shall be supplied by them by the dates stated in the Contract Data. If the Contractor does not supply the Drawings and/or manuals by the dates stated in the Contract Data, or they do not receive the Engineer or his nominee's approval, the Engineer or his nominee shall withhold the amount stated in the Contract Data from payments due to the Contractor.

87. Monsoon Period

Monsoon period will be reckoned from 1st June to 30th September.

88. Progress Report

The following reports shall be submitted for review; as an input to the Management meeting to be held as per Clause No 31 of Conditions of Contract.

88.1 Daily reports

The contractor shall submit daily report indicating daily activities, weather condition, actual manpower, equipment and the prominent materials available and arriving to site. The contractor shall submit the daily report format to the Department for prior approval.

88.2 Monthly Reports

Monthly progress reports shall be prepared by the Contractor and submitted to the Engineer in triplicate. The first report shall cover the period up to the end of the first calendar month following the Commencement Date. Reports shall be submitted monthly thereafter, each within 7days after the last day of the period to which it relates. Reporting shall continue until the Contractor has completed all work, which is known to be outstanding at the completion

date, stated in the Taking-Over Each report shall include:

Certificate for the Works.

- a) Charts and detailed descriptions of progress, including each stage of design (if any), Contractor's Documents, procurement, manufacture, delivery to Site, construction, erection and testing; and including these stages for work by each Sub-Contractor,
- b) Photographs in hardcopy & digital copy and videography in two sets showing the various stages of progress on the Site monthly;
- c) For the supply of manufactured items, the name of the manufacturer, manufacture location, percentage progress, and the actual or expected dates of:
- i) Commencement of manufacture,
- ii) Contractor's/Engineer's inspections,
- iii) Tests,
- iv) Shipment and arrival at the Site;
- d) Copies of quality assurance documents, test results and certificates of Materials;
- e) Safety statistics, including details of any hazardous incidents and activities relating to environmental aspects and public relations; and
- f) Comparisons of actual and planned progress, with details of any events or circumstances which may jeopardize the completion In accordance with the Contract, and the measures being (or to be) adopted to overcome delays.

89. Completion Documents (not applicable)

To treat that the work has been completed and issue a final payment certificate, the following documents will be deemed to form the completion documents:

- i) The Technical documents according to which the work was carried out.
- ii) The set of construction drawings showing therein the modifications and corrections made during the course of execution signed by the Engineer.
- iii) Certificates of final levels and dimensions as set out for various works.
- iv) Certificates of tests performed for various works.
- v) "As Built" Drawings.

90. Submission of statutory documents

The successful bidder, with in 7days from the date of work order, shall submit self-attested copy of statutory documents such PAN card, GST registration certificate, ESI registration certificate, EPF registration certificate, Labour Identification Number (LIN) and any other documents required for successful completion of work.

G. SALIENT FEATURES OF SOME MAJOR LAWS APPLICABLE TO ESTABLISHMENTS ENGAGED IN CONSTRUCTION WORK

- (a) Workmen Compensation Act 1923:- The Act provides for compensation in case of injury by accident arising out of and during the course of employment.
- b) Payment of Gratuity Act 1972: Gratuity is payable to an employee under the Act on satisfaction of certain conditions on separation if an employee has completed 5 years service or more on death at the rate of 15 days wages for every completed year of service. The Act is applicable to all establishments employing 10 or more employees.
- (c) Employees P.F and Miscellaneous Provision Act 1952: The Act Provides for monthly contributions by the employer and workers @ 13.00% and 12% respectively. The benefits payable under the Act are:
 - (i) Pension to family pension on retirement or death, as the case may be.
 - (ii) Deposit linked insurance on the death in harness of the worker.
 - (iii) Payment of P.F accumulation on retirement/death etc.
- d) Maternity Benefit Act 1951:-The Act provides for leave and some other benefits to workmen/employees in case of confinement or miscarriage etc.
- e) Contract Labour (Regulation & Abolition) Act 1970:-The Act provides for certain welfare measures to be provided by the Contractor to contract labour and in case the Contractor fails to provide, the same are required to be provided, by the Principal Employer by Law. The Principal Employer is required to take Certificate of Registration and the Contractor is required to take license from the designated Officer. The Act is applicable to the establishments or Contractor of Principal Employer if they employ 20 or more contract labor.
- f) Minimum Wages Act 1948: The Employer is supposed to pay not less than the Minimum Wages fixed by appropriate Government as per provisions of the Act if the employment is a scheduled employment Construction of Buildings, Roads, Runways are scheduled employment.
- (g) Payment of Wages Act 1936:-It lays down as to by what date the wages are to be paid when it will be paid and what deductions can be made from the wages of the workers.
- (h) Equal Remuneration Act 1979:-The Act provides for payment of equal wages for work of equal nature to Male and Female workers and for not making discrimination against Female employees in the matters of transfers, training and promotions etc.
- i) Payment of Bonus Act 1965: The Act is applicable to all establishments employing 20 or more employees. The Act provides for payments of annual bonus subject to a

minimum of 8.33% of wages and maximum of 20% of wages to employees drawing Rs.3,500/- per month or less. The bonus to be paid to employees getting Rs.2,500/- per month or above up to Rs.3,500/- per month shall be worked out by taking wages as Rs.2,500/- per month only. The Act does not apply to certain establishments. The newly set-up establishments are exempted for five years in certain circumstances. Some of the State Governments have reduced the employment size from 20 to 10 for the purpose of applicability of this Act.

- J) Inter-State Migrant workmen's (Regulation of Employment & Conditions of Service) Act 1979: The Act is applicable to an establishment which employs 5 or more interstate migrant workmen through an intermediary (who has recruited workmen in one state for employment in the establishment situated in another state). The Inter-State migrant workmen, in establishment to which this Act becomes applicable, are required to be provided certain facilities such as housing, medical aid, travelling expenses from home upon the establishment and back,
- K) The Building and Other Construction workers (Regulation of Employment and Conditions of Service) Act 1996 and the Cess Act of 1996:-All the establishments who carry on any building or other construction work and employs 10 or more workers are covered under this Act. All such establishments are required to pay cess at the rate not exceeding 2% of the cost of construction as may be modified by the Government. The Employer of the establishment is required to provide safety measures at the Building or Construction work and other welfare measures, such as Canteens, First-Aid facilities. Ambulance, Housing accommodations for workers near the work place etc. The Employer to whom the Act applies has to obtain a registration certificate from the Registering Officer appointed by the Government.

v) CONTRACT DATA

Items marked "N/A" do not apply in this Contract.

SI.	Description	Reference
No.		CI. No.
1	The following documents are also part of the Contract	
	The Schedule of other contractors	(8)
	The Schedule of Key personnel	(9)
2	The above insertions should correspond to the information	
	provided in the Invitation of Bids.	
3	The Employer is	(1)
	New Mangalore Port Authority,	
	Panambur,	
	Mangalore – 575010	
	Name of Authorized Representative:	
	Name :	
	Chairman,	
	New Mangalore Port Authority,	
	Panambur, Mangalore – 575010	
4	The Engineer is	
	Name :	
	Chief Engineer (C),	
	New Mangalore Port Authority, Panambur,	
	Mangalore- 575010	
	Name of Nominee is	
	Name :	
	Superintending Engineer (SE(C-II))	
	Civil Engineering Department,	
	NMPA, Panambur, Mangalore- 575010	
5	The name and identification number of the Contract is	
	Name of Contract:- "Annual maintenance of fenders,	(1)
	mooring ladders, bollards, roofing sheet and rolling	

SI.	Description	Reference
No.		CI. No.
	shutters inside security compound wall for the year 2023-	
	24 and 2024-25 (Two Years)-Re Tender"	
	Tender no: 46/2023-24	
6	The works consist of "Annual maintenance of fenders,	(1)
	mooring ladders, bollards, roofing sheet and rolling	
	shutters inside security compound wall for the year 2023-	
	24 and 2024-25 (Two Years)-Re Tender".	
7	Schedule date of commencement 7 days from the date of	Conditions
	Issue of Letter of Acceptance.	of contract
		A-General
		1.Definitions
	However No work shall be commenced before signing of	
	contract Agreement.	59.2(a)
8	The Contract price is the price stated in the letter of	1.Definitions
	acceptance. However payment will be made as per actual	
	work done accordance with the contract provisions.	
9	The Intended completion Date for the whole of the Work is	(17,27)
	24 (Twenty Four) Months (including monsoon) with the	
	following milestones:	
10	Milestone dates:	(27)
	Physical works to be Period from the date of	
	completed commencement of work	
	Milestones dates shall be provided to the Contractor by	
	the Executive Engineer executing the work for	
	completion of the work as per the scheduled date.	
11	The following shall form part of the Contract Document:	(2.3)
	(1) Form of Agreement	
	(2) Letter of Acceptance	
	(3) Contractor's Bid	
	(4) Contract Data	
	(5) Conditions of Contract including Special Conditions	
	of Contract	
	(6) Specifications	

SI.	Description Description	Reference
No.		CI. No.
	(7) Drawings	
	(8) Bill of quantities and	
	(9) Any other documents listed in the Contract Data as	
	forming part of the Contract.	
	(10) Correspondence exchanged after the opening of the	
	Bid and before the issue of Letter of Acceptance by which	
	the Condition of Contract are amended, varied or modified	
	in any way by mutual consent (to be enumerated).	
12	The Contractor shall submit a Program for the Works	(27)
	within 14 days of delivery of the letter of Acceptance.	
13	The site possession date	(21)
	The site will be handed over immediately after issue of	
	Letter of acceptance and the site is free from	
	encumbrances.	
14	The site is defined in drawing No. 21/85-LP	
15	The Defects Liability Period is NIL	(35)
16	The minimum insurance cover for physical property,	13
	injury and death is Rs. 5,00,000/- (Rupees five Lakhs) per	
	occurrence with the number of occurrences limited to four.	
	After each occurrence, contractor will pay additional	
	premium necessary to make insurance valid for four	
	occurrences always.	
17	The following events shall also be Compensation Events:	(44)
	The Employer terminates the contract for his convenience.	
18	The period between Programme updates shall be 30 days.	(27)
19	The amount to be withheld for late submission of an	(27)
	updated Programme shall be Rs. 25,000/	
20	The Penalty for the delay in submission of the Performance	(52.2)
	guarantee shall be at the rate of 0.25% of the amount of	34.1
	performance guarantee for each week or part of the week	
	for the number of weeks delayed beyond the stipulated	
	date of submission.	

SI.	Description	Reference
No.	i i	CI. No.
21	The language of the Contract documents is English.	(3)
22	The law, which applies to the Contract, is the law of Union of India.	(3)
23	The currency of the Contract is Indian Rupees.	(46)
24	Fees and types of reimbursable expenses to be paid to the Dispute Review Board (Deleted) As per actuals and equally shared by both the parties. (NA)	(25)
25	The Dispute Review Board shall be constituted after signing of the agreement on mutually agreed terms. (Appendix 1). (Deleted) (NA)	(25)
26	Price Adjustment (deleted)	(47)
		(80)
27	The proportion of payments retained (retention money) shall be 10% of total tax invoice value from each bill subject to a maximum of 5% of the contract price including GST as applicable.	(48)
28	The maximum amount of liquidated damages for the whole of the works is 10 % of the contract price plus taxes and duties. The half per cent (½%) per week L.D is applicable for delay period of $\frac{1}{3}$ of contract period and thereafter 10% L.D is applicable.	[49]
29	Clause No. 49A (v) deleted.	
30	Advance payment is not applicable to this contract	[51]
31	Repayment of secured advance: deleted	(51.6)
32	The Securities shall be for the following minimum amounts equivalent as a percentage of the Contract Price.	(52)
33	Performance Security in the form of Bank guarantee for 5% of the contract price including GST.	(52.2)
34	The standard form of Performance Security acceptable to the Employer shall be an unconditional Bank Guarantee of the type as presented in Section III (iv) of the Bidding Documents.	Annexure-A
35	The Contractor has to submit the final claim for reimbursement of ESI and EPF contribution on the part of the employer in respect of this contract within 60 days from the date of completion of work.	(71)

vi) FORM OF SECURITIES

Acceptable forms of securities are annexed. Bidders should not complete the Performance Security form at this time. Only the successful Bidder will be required to provide Performance and Advance Payment Securities in accordance with one of the forms, or in a similar form acceptable to the Employer.

Annexure A: Performance Bank Guarantee

Annexure B: Bank Guarantee for Advance Payment

PERFORMANCE BANK GUARANTEE

To:	[name	of Employer]
[ac	dress of Employer]	
WHEREAS	[name an	d address of Contractor]
(hereinafter called "the Contractor") h	nas undertaken, in	pursuance of Contract
No	dated	to execute
	[name	of Contract and brief
description of Works] (hereinafter called	"the Contract").	
AND WHEREAS it has been stipulate	ed by you in the	said Contract that the
Contractor shall furnish you with a Ba	ink Guarantee by a	recognized bank for the
sum specified therein as security for co	mpliance with his o	obligations in accordance
with the Contract;		
AND WHEREAS we have agreed to give t	he Contractor such	a Bank Guarantee;
NOW THEREFORE we hereby affirm the	at we are the Guar	antor and responsible to
you, on behalf of the	Contractor, up	to a total of
	[amou	unt of guarantee]1
	[In words], such s	sum being payable in the
types and proportions of currencies in	which the Contract	Price is payable, and we
undertake to pay you, upon your file	rst written demand	d, and without cavil or
argument, any sum or	sums within	the limits of
[8	amount of guarante	e]1 as aforesaid without
your needing to prove or to show groun	nds or reasons for y	our demand for the sum
specified therein.		
We hereby waive the necessity of your c	lemanding the said	debt from the Contractor
before presenting us with the demand.		
We further agree that no change or add	lition to or other mo	dification of the terms of
the Contract or of the Works to be perfe	ormed there under	or of any of the Contract
documents which may be made between	en you and the Con	tractor shall in any way
release us from any liability under this g	guarantee, and we h	ereby waive notice of any
such change, addition or modification.		
This guarantee shall be valid until 28	days from the date	of expiry of the Defects
Liability Period.		
Notwithstanding anything mentioned ab	oove,	
Our liability against this guarantee	is restricted to Rs	s(Rupees

	103		
only) and unless a	claim in writing is lodged with us	3	
within 3 months of the date of expiry or the	e extended date of expiry of this guarantee	Š	
all our liabilities under this guarantee shall	stand discharges.		
IN WITNESS WHEREOF this guarantee h	nas been duly executed on this day	y	
of			
Signature and seal of the guarantor			
Name of Bank			
Address	Date		

1An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract and denominated in Indian Rupees.

BANK GUARANTEE FOR ADVANCE PAYMENT (NOT APPLICABLE)

To:	[name of Employer]
	[address of Employer]
	[name of Contract]
Gentlemen:	
In accordance with	the provisions of the Conditions of Contract, Sub-clause 51.1
("Advance Payment") of the above mentioned Contract,[name
and address of C	ontractor] (hereinafter called "the Contractor") shall deposit
with	[name of Employer] a bank guarantee to guarantee his
proper and faithful _l	performance under the said Clause of the Contract in an amount
of	
1	
	_[amount of guarantee][in words].
We, the	[bank or financial institution], as instructed by
the Contractor, ag	ree unconditionally and irrevocably to guarantee as primary
obligator and	not as Surety merely, the payment
to	[name of Employer] on his first demand without
	f objection on our part and without his first claim to the
Contractor, in the	amount not exceeding[amount of guarantee]1
	[in words].
We further agree th	at no change or addition to or other modification of the terms of
the Contract or of	Works to be performed there under or of any of the Contract
documents which	may be made between[name of
Employer] and the	Contractor, shall in any way release us from any liability under
this guarantee, an	d we hereby waive notice of any such change, addition or
modification.	
The guarantee shal	I remain valid and in full effect from the date of the advance
payment under th	ne Contract until[name of
Employer] receives f	ull repayment of the same amount from the Contractor.
Notwithstanding any	ything mentioned above,
Our liability agair	st this guarantee is restricted to Rs(Rupees
on	lly) and unless a claim in writing is lodged with us within 3
months of the date	of expiry or the extended date of expiry of this guarantee all our

liabilities under this guarantee shall

stand discharges.

IN WITNESS WHEREOF	this guarantee has been duly executed on thisday		
of			
Yours truly,			
Signature and seal:			
Name of Bank/Financial Institution:			
Address:			
Date:	1. An amount shall be inserted by the bank or financial		
institution representing the	amount of the Advance Payment, and denominated in		
Indian Rupees.			

BANK GUARANTEE FOR RETENTION MONEY (NOT APPLICABLE)

To,

New Mangalore Port Authority, Administrative Building, Panambur, Mangalore – 575 010.

1.	Mangalore (hereinafter called "The Board" having agreed to refund
	(hereinafter called
	"the said contractor(s)") under the terms and conditions of an Agreement
	No made between New Mangalore Port Authority and
	(hereinafter called "the said Agreement") the
	retention money for the due fulfillment by the said contractor(s) of the terms and
	conditions contained in the said agreement on production of a bank guarantee for
	We (hereinafter referred to as "the Bank")
	at the request of M/s do hereby undertake to pay the Board
	an amount not exceeding on demand.
2.	We do hereby undertake to pay the amounts due
	and payable under this guarantee without any demur, merely on a demand from the
	Board stating that the amount claimed is required to meet the recoveries due or
	likely to be due from the said Contractor(s). Any such demand made on the bank
	shall be conclusive as regards the amount due and payable by the Bank under this
	guarantee. However, our liability under this guarantee shall be restricted to an
	amount not exceeding
	Rs
3.	We undertake to pay the Board any money so
	demanded notwithstanding any dispute or disputes raised by the Contractor(s) in
	any suit or proceeding pending before any Court or Tribunal relating there to, our
	liability under this present being absolute and unequivocal.
	The payment so made by us under this bond shall be a valid discharge of our
	liability for payment there under and the Contractor(s) shall have no claim against
	us for making such payment.

4.	We further agree that the guarantee herein
	contained shall remain in full force and effect during the period that would be taker for the performance of the said Agreement and that it shall continue to be enforceable till all the dues of the Board under or by virtue of the said Agreemen have been fully paid and its claims satisfied or discharged or till Engineer-in-charge on behalf of the Board certifies that the terms and conditions of the said Agreemen have been fully and properly carried out by the said Contractor(s) and accordingly discharges this guarantee.
5.	We further agree with the Board that Board shall have the fullest liberty without our consent and without affecting in any manner our obligations here under to vary any of the terms and conditions of the said agreement or to extend time of performance by the said Contractor(s) from time to time or to postpone for any time or from time to time any of the powers exercisable by the Board against the said Contractor(s) and to forbear or enforce any of the terms and conditions relating to the said Agreement and we shall not be relieved from our liability by reason of any such variation, or extension being granted to the said Contractor(s) or for any forbearance act or omission on the part of the Board or any indulgence by the Board to the said Contractor(s) or by any such matter or thing whatsoever which under the law relating to sureties would but for this provision have effect so relieving us.
6.	This guarantee will not be discharged due to the change in the constitution of the Bank or the Contractor(s).
7.	We lastly undertake not to revoke this guarantee except with the previous consent of the Board in writing.
8.	This guarantee shall be valid up to unless extended on demand by Board Notwithstanding anything mentioned above, our liability against this guarantee is restricted to Rs and unless a claim in writing is lodged with us within three months of the date of expiry or such extended date of expiry of this guarantee all our liabilities under this guarantee shall stand discharged.

herein.

Our liability under this Bank Guarantee restricted to a sum of Rs		
	Only).	
2.	This bank guarantee shall be valid up toWe are lia	ble
	to pay the guaranteed amount or any part thereof under this bank guarantee o	nly
	and only if you serve upon us a written claim or demand on or before	

APPENDIX 1TO GENERAL CONDITIONS OF CONTRACT (NA)

DISPUTES REVIEW BOARD AGREEMENT (NOT APPLICABLE)

this age	REEMENT, mad	de and entered	into this		Day
of	.20	Between		("the	Employer")
and					
			the Contr	actor"),and	the Disputes
Review Boa	ard ("the Board")) consisting of One	/ three Bo	ard Members	S,
(2)					
(3)					
[Note:	Delete	whatever	is	not	applicable]
WITNESSE	ETH, that				
WHEREAS	, the Employer	and the Contracto	or have con	tracted for th	ne construction
of	the				
(the "Cont	ract") and WHE	REAS, the contra	ct provides	for the esta	blishment and
operation (of the Board NO	W THEREFORE, th	ne parties h	ereto agree a	s follows :
The partie	s agree to the e	stablishment and	operation	of the Board	in accordance

- 1. The parties agree to the establishment and operation of the Board in accordance with this Board Agreement.
- 2. Except for providing the services required hereunder, the Board Members should not give any advice to either party or to the Engineer or his nominee concerning conduct of the Works.

The Board Members:

- a. shall have no financial interest in any party to the contract or the Engineer or his nominee, or a financial interest in the contract, except for payment for services on the Board.
- b. shall have had no previous employment by, or financial ties to, any party to the contract, or the Engineer or his nominee, except for fee based consulting services on other projects, all of which must be disclosed prior to appointment to the Board.
- c. shall have disclosed in writing to the parties prior to signature of this Agreement any and all recent or close professional or personal or personal relationships with any director, officer, or employee of any party to the contract, or the Engineer or his nominee, and any and all prior involvement in the project to which the contract relates;

- d. shall not, while a Board Member, be employed whether as a consultant or otherwise by either party to the contract, or the Engineer or his nominee, except as a Board Member.
- e. shall not, while a Board Member, engage in discussion or make any agreement with any party to the contract, or with the Engineer or his nominee, regarding employment whether as a consultant or otherwise either after the contract is completed or after services as a Board Member is completed;
- f. shall be and remain impartial and independent of the parties and shall disclose in writing to the Employer, the Contractor, the Engineer or his nominee, and one another any fact or circumstances which might be such to cause either the Employer or the Contractor to question the continued existence of the impartiality and independence required of Board Members.
- 3. Except for its participation in the Board's activities as provided in the contract and in this Agreement none of the Employer, the Contractor, the Engineer or his nominee, and one another any fact or circumstances which might be such to cause either the Employer or the Contractor to question the continued existence of the impartiality and independence required of Board Members.

4. The Contractor shall:

- a) furnish to each Board Members one copy of all documents which the Board may request including contract documents, progress reports, variation orders, and other documents, pertinent to the performance of the Contract.
- b) in co-operation with the Employer, co-ordinate the Site visits of the Board, including conference facilities, and secretarial and copying services.
- 5. The Board shall serve throughout the operation of the contract. It shall begin operation following execution of this Agreement, and shall terminate its activities after issuance of the taking over Certificate and the Board's issuance of its Recommendations on all disputes referred to it.
- 6. Board Member shall not assign or subcontract any of their work under this Agreement.
- 7. The Board Members are independent and not employees or agents of either the Employer or the Contractor.
- 8. The Board Members are absolved of any personal or professional liability arising

from the activities and the Recommendations of the Board.

9. Fees and expenses of the Board Member[s] shall be agreed to and shared equally by the Employer and the Contractor. If the Board requires special services, such as accounting, data research, and the like, both parties must agree and the costs shall be shared by them as mutually agreed.

10. Board Site visits:

- a. The Board shall visit the Site and meet with representatives of the Employer and the Contractor and the Engineer or his nominee at regular intervals, at times of critical construction events, and at the written request of either party. The timing of Site failing agreement shall be fixed by the Board.
- b. Site meetings shall consist of an informal discussion of the status of the construction of the works followed by an inspection of the works, both attended by personnel from the Employer, the Contractor and the Engineer or his nominee.
- c. If requested by either party or the Board, the Employer will prepare minutes of the meetings and circulate them for comments of the parties and the Engineer or his nominee.
- 11. Procedure for disputes referred to the Board:
- a. If either party objects to any action or inaction of the other party or the Engineer or his nominee, the objecting party may file a written Notice of Dispute to the other party with a copy to the Engineer or his nominee stating that it is given pursuant to Clause 65 and stating clearly and in detail the basis of the dispute.
- b. The party receiving the Notice of Dispute will consider it and respond in writing within 7 days after receipt.
- c. This response shall be final and conclusive on the subject, unless a written appeal to the response is filed with the responding party within 7 days of receiving the response. Both parties are encouraged to pursue the matter further to attempt to settle the dispute. When it appears that the dispute cannot be resolved without the assistance of the Board either party may refer the dispute to the Board by written Request for Recommendation to the Board, the other party and the Engineer or his nominee stating that it is made pursuant to Clause 65.
- d. The Request for recommendation shall state clearly and in full detail the specific issues of the dispute to be considered by the Board.
- e. When a dispute is referred to the Board, and the Board is satisfied that the dispute requires the Board's assistance, the Board shall decide when to conduct a hearing on the dispute. The Board may request that written documentation and arguments from both parties be submitted to each Board Members before the hearing begins.

The parties shall submit insofar as possible agreed statements of the relevant facts.

f. During the hearing, the Contractor, the Employer, and the Engineer or his nominee shall each have ample opportunity to be heard and to offer evidence. The Board's Recommendations for resolution of the dispute will be given in writing, to the Employer, the Contractor and the Engineer or his nominee as soon as possible, and in any event not more than 28 days after the Board's final hearing on the dispute.

12. Conduct of Hearings:

- a. Normally hearing will be conducted at the Site, but any location that would be more convenient and still provide all required facilities and access to necessary documentation may be utilised by the Board. Private sessions of the Board may be held at any location convenient to the Board.
- b. The Employer, the Engineer or his nominee and the Contractor shall have representatives at all hearings.
- c. During the hearings, no Board Member shall express any opinion concerning the merit of any facet of the case.
- d. After the hearing are concluded, the Board shall meet privately to formulate its Recommendations. All Board deliberations shall be conducted in private, with all individual views kept strictly confidential. The Board's Recommendations, together with an explanation of its reasoning shall be submitted in writing to both parties and to the Engineer or his nominee. The Recommendations shall be based on the pertinent contract provisions, applicable laws and regulations, and the facts and circumstances involved in the dispute.
- e. The Board shall make every effort to reach a unanimous Recommendation. If this proves impossible, the majority shall decide, and the dissenting member any prepare a written minority report for submission to both parties.

[Note: Delete if it is one member Board]

13. If during the contract period, the Employer and the Contractor are of the opinion that the Dispute Review Board is not performing its functions properly; the Employer and the Contractor may together disband the Disputes Review Board. In such an event, the disputes shall referred to Arbitration straightaway.

The Employer and the Contractor shall jointly sign a notice specifying that the Board shall stand disbanded with effect from the date specified in the notice. The notice shall be posted by a registered letter with AD or delivery of the letter, even if he refuses to do so.



NEW MANGALORE PORT AUTHORITY Panambur, Mangalore

Annual maintenance of fenders, mooring ladders, bollards, roofing sheet and rolling shutters inside security compound wall for the year 2023-24 and 2024-25 (Two Years)-Re Tender

TENDER DOCUMENT Volume - II

NEW MANGALORE PORT AUTHORITY CIVIL ENGINEERING DEPARTMENT Tender no: CIVIL/CE(C)/EE(C)/46/2023-24

Tender for

"Annual maintenance of fenders, mooring ladders, bollards, roofing sheet and rolling shutters inside security compound wall for the year 2023-24 and 2024-25 (Two Years)-Re Tender"

Volume	Section I	i)	Notice Inviting Tenders
<u>l</u>		i)	Instructions to Tenderers
		ii)	Annexure (1 to 13)
	Section II	i)	Form of Agreement
	Section III	i)	Conditions of Contract: Part A -
			E: General Conditions
		ii)	Conditions of Contract : Part F:
			Special Conditions
		iii)	Contract Data
		iv)	Form of Securities (A & B)
		v)	Appendix - I and Appendix - II
Volume	Section IV	i)	Technical Specifications
<u>II</u>			
	Section V	ii)	Drawings
Volume	Section VI	i)	Preamble
<u>III</u>		ii)	Bill of Quantities
		iii)	For of tender
	Section VII	i)	Schedules (A & B)
-			

Table of Contents

CTION	IV	. 117
CHNIC	CAL SPECIFICATIONS117	
Α.	GENERAL	. 117
1.	INTRODUCTION	. 117
2.	SPECIAL CONDITION OF CONTRACT	. 121
B. W	Vorks – Scope of work	. 124
1.	Servicing of rolling shutter	. 124
2.	Replacing steel laths	. 124
3.	Replacing the bottom plate	. 124
4.	Providing & fixing top covers	. 124
5.	Replacing the rolling shutter springs	. 124
6.	Replacing the gear attachment	. 124
7.	Providing & fixing pull & push type rolling shutters	. 124
8.	line and slope roofing with corrugated cement sheets	. 125
9.	Providing & fixing hooks	. 125
10.	Cutting and removing hooks	. 125
11.	Cleaning gutter	. 125
12.	polyethylene pipes	. 126
13.	Angular Truss	. 126
14.	Dismantling of existing structures	. 126
15.	galvalume sheet	. 126
16.	Iron Accessories	. 127
17.	Gypsum anhydrous	. 127
18.	bituminous membrane	. 127
	A. 1. 2. B. W 1. 2. 3. 4. 5. 6. 7. 8. 10. 11. 12. 13. 14. 15. 16. 17.	1. INTRODUCTION

19. Giant Tyre Fender	127
20. Dismantling the dislocated Giant Tyre Fender	128
21. Periodical inspection of Fenders	128
22. fender bolts	128
23. Dismantling the damaged V / W type fender	128
24. painting	129
25. enamel metal paint	129
26. Turbo Ventilators	129
27. STEEL, IRON AND ALLUMINIUM WORKS	129
28. SPECIFICATION FOR FINISHING WORKS	136
SECTION V	144
DRAWINGS	

SECTION IV

TECHNICAL SPECIFICATIONS A.GENERAL

1. INTRODUCTION

The intent of this technical specification covers construction of all Mechanical/fabrication works as covered in the scope of contract as per drawings supplied by Owner.

All Mechanical/fabrication works shall be carried out as per design / drawings standardized by the Consultant / Owner and the specification provided by the Consultant / Owner. All standard drawings are enclosed with the tender documents. In case any item is not covered under specification then the same shall be carried out as per CPWD specification and applicable Standards and Codes. Any item for which specification is not provided herein and is not covered under CPWD specification shall be executed as per manufacturer guidelines. All materials shall be of best quality conforming to relevant Standards and Codes. In case of any conflict between Standards / Code and Technical Specification, the provisions of Technical Specification shall prevail, and the Engineer's decision on interpretation shall be final.

The Contractor shall furnish all labor, tools, equipment, materials, temporary works, constructional plant and machinery, fuel supply, transportation and all other incidental items not shown or specified but as may be required for complete performance of the Works in accordance with drawings, specifications and direction of Owner.

Excavated earth is to be disposed from site as instructed, only into approved landfill areas and dump yard. The cost of excavation to include for necessary lead and lift as specified.

All materials including cement, reinforcement steel and structural steel etc. shall be arranged by the Contractor. All testing required shall be arranged by the Contractor at his own cost. The contractor shall execute the work as per the standard Field Quality Plan (FQP) of NMPA.

The bidder shall fully apprise himself of the prevailing conditions at the proposed site, climatic conditions including monsoon patterns, local conditions and site specific parameters and shall include for all such conditions and contingent measures in the bid, including those which may not have been specifically brought out in the specifications.

Level and date of concreting shall be marked on the building from outside at every floor level with proper paint, etc.

All levels and survey work shall be measured by total station and electronic level machine at all floors and places.

Brief Description of Works

The scope of work is defined in the Notice Inviting Tender. The Contractor shall provide all necessary materials, equipment and labour etc. for the execution and maintenance of the work till completion.

The work shall be executed in accordance with the specification stipulated in the Bill of Quantity and other bidding documents read along with CPWD (Central Public Works Department) specifications for civil works and IS codes with up-to-date revisions. For non-schedule items specification as given along with tender document and similar items of CPWD shall be applicable.

The list of references for civil works are CPWD specifications, relevant IS codes and best practices.

For deep excavations, necessary shoring is to be done, the design of which will be provided by the contractor, after assessing site and soil conditions, and work only to be commenced on site after the same is duly approved by NMPA. Any approval if required from the Mineral department or any other statutory body that has jurisdiction on such excavations has to be obtained by the contractor.

All earth used for back filling should be of approved quality.

Portland Cement of IS 8112 shall be used for all cement & concrete works. This will supersede other specifications of cement to be used for the works.

For ready mixed cement concrete, in addition to the CPWD specification, the following also to be noted:

The cost towards cement quantity reduced from the specified quantity in the item due to mixing of fly ash shall be deducted as per relevant BOQ item. The design mix shall be submitted to Engineer in Charge for approval.

All hard ware fittings shall be of best quality and shall be selected as per the Instructions of Engineer in Charge.

Site location, Boundaries and Possession

The location and boundaries of the Site are shown on the Drawing No: 20/82-LP. The Contractor shall confine his activities strictly to the allotted site area(s) and shall not allow his personnel to trespass upon any other areas occupied by the Employer.

1.4 Site Datum and Base Lines

A base line shall be established within the working area by the Contractor. The base line shall be referenced to the site co-ordinate system (based on the Local Coordinates of New Mangalore Port). This bench mark and base line will be the basis for the setting-out for all the Works. The main levels and lines for each portion of the Works shall be established from the bench mark and base line by the Contractor.

1.5 Site Conditions

1.5.1 Location of Work

As per enclosed location plan.

1.5.2 Climate

The climate at Mangalore is tropical with high humidity and a maximum shade temperature of 36°C. The average annual rainfall is approximately 3330 mm and concentrated in the south-west monsoon months of June, July, August and September during which period the average rainfall is as much as 82% of the total annual rainfall.

1.5.3 Wind

The wind in the monsoon months of June, July and August are predominantly from south-west and west with a maximum intensity of 5 on the Beaufort Scale. The winds in the remaining months of the year are predominantly from the north-west and the maximum intensity during this period is also of 5 on the Beaufort Scale.

1.5.4 Cyclones

Even though Mangalore is within the cyclonic area of storms originating in the Arabian Sea and those that enter across the Indian Peninsula from Bay of Bengal, cyclones are not as severe or frequent as in the Bay of Bengal. The maximum wind speed so far recorded in cyclonic storm, generally does not exceed 62 kmph (16.9 m/sec.) except one during 1965 when the maximum speed recorded was 97 kmph (26.9 m/sec.)

1.5.5 Visibility

Thirty year period observations conducted by the Indian Meteorological Departm1.5 ent reveal that poor visibility (visibility less than 4 Kms) is encountered for about 10 days in the south-west monsoon period. The maximum number of foggy days in a year is only 3.

1.5.6 Site Preparation

The Contractor shall furnish all necessary supervision, labour, materials, equipment and tools for Site Preparation, clearing and all other works. Clearing shall mean to completely demolish, remove and dispose with all leads, lifts and descents from the area marked, trees, bushes, deadfalls, embedded logs, dislodged roots, stumps, snogs, boulders, mounds, existing structures and other objectionable materials. The areas required to be cleared shall consist of the work Site, ditches, borrow pits, diversions and all other areas necessary for the construction work as directed by the Engineer-in-Charge.

Before any Temporary Works are commenced, the Contractor shall submit his proposal along with complete drawings of all Temporary Work, he may require for the execution of the Works in advance to the Engineer for approval. The Contractor shall also submit his calculations relating to the design of temporary works, strength, etc. if required by the Engineer and shall carry out the modifications that the Engineer may require of such temporary works at Contractor's own cost. The Contractor shall be solely responsible for the stability and safety of all Temporary Work.

It will be the responsibility of the Contractor to make timely procurement of all materials and mobilize all essential equipment for both Temporary and Permanent Works.

1.6 Site Information

The detailed drawing No.21/85-LP of the construction site for adaptation of methodology for the construction. However, on account of this change in the geographical profile of site, no extra cost for additional arrangement required to be made will be paid for.

1.7 The Nature of Soil Profile

The site comprises of ordinary soil. The details furnished herein are only for the information/guidelines of the tenderers and the successful contractor shall not claim for any deviation in the actual subsoil profile encountered at site.

1.8 Records

Complete records of all operations connected with the work shall be kept by the Contractor. The Contractor shall submit to the Engineer-in-charge for approval his proposal of the manner of presentation of these records. Three copies of all such records shall be furnished to the Engineer-in-charge on completion of each test or operation.

2. SPECIAL CONDITION OF CONTRACT

The following special conditions of contract shall be covered under this contract, which shall be read in conjunction with the general conditions:-

- 1. The work shall be carried out on an annual contract basis for a period of Two year from the date of award.
- 2. All the buildings and other structures in and around wharf area is covered under this contract.
- 3. A list of fenders, bollards and ladders inside wharf area is enclosed for references.
- 4. The Contractor has to appoint an authorized representative for receiving day to day instructions from the department, attending complaints and successful execution of the work. A list of the persons employed by the Contractor shall be submitted for reference and record.
- 5. The Contractor has to deploy required number of workmen for timely completion of the specified job and at times of requirement, shall increase the work force as necessitated. Also the workmen deployed by the Contractor for carrying out maintenance works shall be skilled in their respective field having good experience and should be able to discharge their duties diligently as per instruction given by the department.
- 6. The nature of work includes working at a vertical height upto 15.00 m above ground level for carrying out repairs of roof trusses and roofing sheets etc., and upto 3.00 m below ground level for repairs/replacement of fenders and mooring ladders etc., The Contractor has to be well acquainted about the nature of work and working condition and abide with all applicable safety regulations before commencing the work.
- 7. The method of entrustment of the job will be either preventive maintenance or based on the complaints received from departments and various users of offices, buildings or sheds inside wharf area. This shall be received by the Engineer-incharge in the wharf maintenance sub division office on day to day basis and shall be entered in the Complaint Register. The Contractor or his authorized representative shall collect or receive the complaint and make necessary arrangement for attending the same. After completion of the work, the same

- shall be shown to the Engineer-in-Charge who shall inspect the same and record the measurements jointly for preparation of running bills.
- 8. Based on the nature of work/Complaint, the Contractor shall chart out a programme incorporating various items of work provided in the BOQ along with required men, material and equipment for completion of the job and submit the same to the Engineer-in-Charge. The routine inspection works such as periodical cleaning and servicing of rolling shutters, fenders, bolts and nuts, mooring ladders etc., shall be carried out as per routine schedule.
- 9. Item No. 1, i.e. servicing/greasing of rolling shutters and gates is to be carried out regularly, which will be informed by the Departmental Representative as and when required. The qty. proposed for this item is for maintaining the shutters and gates in perfect working throughout the year.
- 10.All the materials used for the works shall be of good quality and conforming to relevant Standards.
- 11.It may be noted that Fuel, Water or Electricity shall not be provided by the department for execution of works under this Contract. The Contractor has to make his/their own arrangements for the same.
- 12. Before taking up any welding, chipping or any other hot works inside wharf area, Hot Work Permission shall be obtained by the contractor from the competent authorities of NMPA.

DETAILS OF FENDERS

Berth No	Fender Type	Fender No	Location	Year of Installation	Remarks
		S1	× 1 1 2	2018	1 1
		S2		2018	
0	Cuman Call	S 3		2018	
8	Super Cell	S 4		2018	
		S 5		2018	
	48	S 6	16E	2018	
	Super Cell	S 1	BD North .	Mar-2012	
		T 1			
. 9	Tyre	T 2	9		
	Super Cell	S 2	BD South	Dec-2016	F 18
		S 1	BD North	May-2009	
		S 2	DD NOITH	May-2009	
10	Super Cell	S 3	The state of the s	Dec-2016	+
		S 4	BD South	Aug-2016	
	+			-	
		S 1	BD North	2014	4 10 40
11	Super Cell	S 2		2014	
		S 3		2014	
		S 4	BD South	2014	
12	Super Cell	S 1	BD South	Aug-2017	
12	Ouper Ocii	S 2	BD North	Aug-2017	
		S 1	BD North	2014	
		S 2	120	2014	
	Super Cell	S 3	BD South	2014	
13		S 4		2014	
	Super Cell	800H 1	FD North	2018	Replaced Rubber without Frame
		800H2	FD South	2014	
14	Hyper Cell	1	11 U = 12	2007	*
14	Hyper Cell	2		2018	
14	Hyper Cell	3	, 2 m I	2016	1 18 A 18 18 18 18 18 18 18 18 18 18 18 18 18
14	Hyper Cell	4		2007	1 H H E
14	Hyper Cell	5		2006	
14	Hyper Cell	6		2006	F 10 10
14	Hyper Cell	7	-	2006	
14	Hyper Cell	8		2006	
14	Hyper Cell	9	41	2006	
14	Hyper Cell	10	0 9 4	2006	165
14	Hyper Cell	11		2006	1
14	Hyper Cell	12		2006	
14	Hyper Cell	13	* A	2006	
14	Hyper Cell	14	p _ 11	Jan-2010	4
14	Hyper Cell	15		2006	
14	Hyper Cell	16		2006	Darler
14	Hyper Cell	17		2006	Broken
14	Hyper Cell	18	E .	2006	-
14 14	Hyper Cell	19	- 10	2006 Nov 2000	
14	Hyper Cell	20		Nov-2009	
14	Hyper Cell	21	7	2016	
14	Hyper Cell	22		2006	A 10 10
1-7	V/ W & Tyre Type	1 to 70	Wharf Wall	= 104 · · · · · · · · · · · · · · · · · · ·	

STOOLS DECS

EEQU.T)

B. Works – Scope of work

1. Servicing of rolling shutter

Servicing of rolling shutter by providing and applying multipurpose grease to all parts of the rolling shutters of all sizes such as 'U' channels, side guides, latches, locks, coil springs and gear type arrangements etc. after thoroughly cleaning the surface so as to make the movement of the shutter free including cost and conveyance of all materials, labour charges, climbing arrangements, hire charges of T&P and all other incidental charges etc. complete for successful completion of the work.

2. Replacing steel laths

Replacing steel laths of 18 gauge and 75mm width including cutting to the required length, providing interlocking arrangements for steel laths by means of alternate end clips to the existing laths etc. complete as directed by the Engineer in charge.

3. Replacing the bottom plate

Replacing the bottom plate with 12 gauge plates including providing locking arrangements, handling and providing other acessories to the required length, cost of all materials, labour charges for fixing, painting two coats over a coat of primer etc. complete. as directed by Engineer in charge.

4. Providing & fixing top covers

Providing & fixing top covers made out of 20 guage MS sheet over pull and push rolling shutters bent to shape including cost of red lead primer coat painting, materials, labour etc. complete.

5. Replacing the rolling shutter springs

Replacing the rolling shutter springs with approved make 3 gauge 3 1/2" dia 13" to 14" length coil springs including removing the rolling shutter centre shaft & fixing the springs with required tension, greasing the required parts etc. complete as directed by the Engineer in charge.

6. Replacing the gear attachment

Replacing the gear attachment and gear box for the rolling shutter for free movement of folding including gear shaft of approved quality, fixing firmly on wall with bolts of standard size including cost of all materials & tools etc. complete.

7. Providing & fixing pull & push type rolling shutters

Providing & fixing pull & push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with

side guides and bottom rail with interlocking arrangements for steel laths by means of alternate cilps, suspension shaft with high tension coil type springs two number, mounted on specially designed pipe shaft with bracket plates, guide channels, ball bearing arrangements for inside & outside locking with push & pull operations complete including pulling hooks, 4 nos. handles with all fittings and accessories, painted with a coat of red lead paint (with out top cover) cost of all materials labour, HOM of machinary complete as per specifications.

8. line and slope roofing with corrugated cement sheets.

Providing & laying to required line and slope roofing with corrugated cement sheet 6mm thick fixed with galvanized iron J or L hooks, bolts and nuts 8mm dia, CI plain and bitumen washers over the existing purlins, rafter and truss including cost of materials labour and all other incidental charges with removing the old damaged sheets. Etc., complete.

9. Providing & fixing hooks

Providing & fixing ridges, hips with cement sheet roofing with GI or L hooks bolts and nuts 8mm dia with CI and bitumenn washers including cost of all materials labour etc. complete

10. Cutting and removing hooks

Cutting and removing the existing, corroded, damaged GI 'J' / 'L' hooks provided on the roofing of Transit sheds / Overflow sheds / go-downs and other A.C. sheet roof buildings / sheds using suitable cutting equipment without damaging other structural members and stacking the dismantled materials and providing & fixing new GI 'J' / 'L' hooks with nuts and washers and fixing the same over the existing AC / galvalume sheet roofing, purlins, rafters, channels and trusses including capping the top of bolt and cleaning the surface and sealing the 'J' bolts with APP modified bitumen membrane of approximately 15 cms x 10 cms in size by torching method using 90/15 blown bitumen including cost of all materials, cost of form work / scaffolding, cost of labour, Tools & Plants and all other incidental charges etc. complete as directed by the department.

11. Cleaning gutter

Cleaning the vally gutter water gutter removing all deposited materials and disposing the same with a lead of 50m including cost of all tools & plants, labour charges all necessary arrangements for working over the AC sheet

roofing with necessary scaffolding/ stagging, and all other incidental charges etc. complete as directed by the department.

12. polyethylene pipes

KSRB 13-18.1: Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure 160mm outside diameter with all necessary specials, special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM of equipment and testing complete as per specifications.

13. Angular Truss

Fabricating, supplying & erecting Angular Truss for all spans, Mooring ladders, Manhole Chamber Covers, grill gates, hand railings, barricades, repairs to frontal frame and covers of rubber dock fenders, fabrication of mooring hooks, repairs of bollards using Mild Steel sections such as plates, tubes, angles, channels, beams and any other section as directed by the Engineer-in-charge as per approved designs and drawing. The fabricated items shall either be welded or anchored suitably by using M.S. anchor bolts at each support with base plates, shoe plates etc. The work includes, cutting, straightening, placing in position of M.S. section and welding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of materials, labour charges, & hire charges of machineries for cutting, welding, grinding & erection equipment's, etc., complete as per specification for the successful completion of the work.

14. Dismantling of existing structures

Dismantling of existing structures comprising of steel work in all type of sections up to a height of 5 m above plinth level including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking serviceable material with all lifts complete as per specification including credit for taking away dismantled materials.

15. galvalume sheet

Providing and installing of pre-painted galvalume iron Traphezoidal profiled sheet of approved make 1060mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at

the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ 150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self-drilling / self-tapping screws of 25mm length, to be fixed over the existing purlins, rafters, channels and trusses.

16. Iron Accessories

Providing and installing of approved make pre-painted galvalume iron Accessories like, plain ridges, plain gutter, plain flashing, corner trim, etc. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ 150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using using GI 'J' / 'L' hooks with nuts & washers of required size and length or self drilling / self tapping screws of 25mm length, (width up to 500-600mm only), to be fixed over the existing purlins, rafters, channels and trusses and making holes and fixing arrangements for rain water down take pipes etc. complete.

17. Gypsum anhydrous

Providing and fixing in position 12mm thick plaster of paris (Gypsum anhydrous) for ceiling reinforced with heissian cloth flat surface with ceiling tiles upto a height of 5 m above above floor level over aluminium strips and rendered smooth with plaster of paris including cost of materials, labour, curing complete as per specifications.

18. bituminous membrane

Providing & applying water proofing bituminous membrane reinforced with non-woven polyester fabric, weighing 180gm/sqm granular finish 4mm thick by torch on application method confirming the standard manufacturers specification and as directed by the department.

19. Giant Tyre Fender

Dismantling the damaged Giant Tyre Fender from the Berth and Fixing the New / Released tyre fenders with GI chain, nylon rope etc., including stacking the released fender at stack yard, transporting the new tyre fender to worksite, providing necessary holes for inserting the GI chain and fixing at site including cost of all materials, tools and plants, hire charges of crane, transportation, labour charges etc. complete as per site

requirement. (Excluding the cost of tyre fender, GI chain, shackels, nylon rope etc which will be supplied by department.)

20. Dismantling the dislocated Giant Tyre Fender

Dismantling the dislocated Giant Tyre Fender from the Berth and Refixing the same in required position, with GI chain, nylon rope etc., including cost of all materials, labour, tools and plants, hire charges of cranes etc., complete as per the site requirements. (Excluding the cost of tyre fender, GI shackels, nylon rope etc. which will be supplied by Department)

21. Periodical inspection of Fenders

Periodical inspection of Fenders, tightening of all loosened bolts properly, checking the holding chains, hooks including chipping and cleaning the rust and other loose particles such as iron ore fines, coal dust, fungal and algae growth from fender frontal frames, chains etc., of all the fenders from Berth Nos. 1 to 8 and Berths Nos. 13 to 18, including cost of all materials, ladders, labours, tools and plants and all other incidental charges etc., complete.

22. fender bolts

Replacing the damaged / missing / rusted fender bolts with sleeves including drilling holes in the concrete by core cutting machine at required place suitable for fixing sleeves, fixing the sleeve to the holes and grouting with Epoxy mortar etc., including cost of all materials, scaffolding, labour charges, tools and plants, and all other incidental charges etc. complete as per the site requirement.

23. Dismantling the damaged V / W type fender

Dismantling the damaged V / W type fender from the berth and refixing the new V / W type fender with necessary bolts etc., including removal of all bolts fixed to the sleeves, lifting fender by using Escort / Hydra crane, transporting and stacking at departmental stack yard, transporting new fender and fixing at site, including cost of all materials, labour charges, tools & plants, hire charges of crane, transportation, scaffolding charges and all other incidental charges etc. complete as per site requirements. (Excluding the cost of fender, bolts etc. which will be supplied by department)

24. painting

Providing and painting of letters of 16 cms. height in english for numbering of fenders by providing and applying synthetic enamel paint of approved colour & shade including cost of all materials, labour, T&P, hire charges, etc., complete as directed by the department.

25. enamel metal paint

KSRB 15-18.3: Providing and applying enamel metal paint one coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.

26. Turbo Ventilators

Providing and installing turbo ventilators at suitable places including all labours and incidental charges etc. complete.

27. STEEL, IRON AND ALLUMINIUM WORKS

7.1 Materials

- 7.1.1. Steel All finished steel shall be well and cleanly rolled to the dimensions and weight specified by Bureau of Indian Standards subject to permissible tolerances as per relevant IS codes. The finished materials shall be reasonably free from cracks, surface flaws laminations, rough and imperfect edges and all other harmful defects.
- 7.1.2. Steel sections, shall be free from excessive rust, scaling and pitting and shall be well protected. The decision of the engineer regarding rejecting any steel section on account of any of the above defects shall be final and binding.
- 7.1.10.Bolts These are of two type's namely turned and fitted bolts and black bolts. Turned & fitted bolts are turned to exact diameter in automatic lathe. For these bolts, whether reamed or drilled bolts, the same unit stresses are allowed as for rivets. In case of black bolts which are not finished to exact sizes, a lower working stress other than for turned bolts is adopted. They shall conform to IS: 1367 Technical supply conditions for threaded steel fasteners.
- 7.1.11.Electrodes The electrodes required for metal arc welding shall be covered electrodes and shall conform to IS: 814-1991.

7.2. Workmanship – General

- 7.2.1. Structural steel work riveted, bolted or welded shall be carried out described in relevant IS code of practice for use of structural steel in general building construction.
- 7.2.2. Straightening and bending All material shall be straight and if necessary, before being worked shall be straightened and flattened by pressure, unless required to be of curvilinear form and shall be free from twists. Straightening of steel by hammer blows is not permitted. All bending and cutting shall be carried out in cold condition, unless otherwise directed, in such manner as not to impair the strength of the metal.
- 7.2.3. Cutting and machining Member shall be cut mechanically by saw or shear or by oxyacetylene flame. All sharp rough or broken edges and all edges of joints which are subjected to tensile or oscillating stresses shall be grounded. No electric metal arc cutting shall be allowed. All edges cut by oxyacetylene pores shall be cleaned of impurities and slag prior to assembly, cutting tolerance shall be as follows (a) For member connected at ends ± 1 mm. (b) Elsewhere ± 3 mm.
 - When compression members depend on contact surfaces for stress transmission, then ends of columns and bases together with gussets, angles and channels (after riveting / welding together) shall be accurately measured so that the parts connected butt over the entire surfaces of contact. Columns at bases or at caps or at butt joints need to be machined.
- 7.2.4. Holes All holes shall be accurately marked and drilled. Holes through more than one thickness shall preferably be drilled together after the members are assembled and tightly clamped or bolted together. In such cases, if required, these parts shall be separated after drilling and burrs removed. For thickness of materials less than 16 mm the holes may be punched 3 mm less in diameter than the required size and may be reamed to the full diameter after assembly. Finished holes for rivets and black bolts shall be more than 1.5 mm (2.0 mm for rivets and bolts of diameter more than 25 mm) in diameter larger than the diameter of rivets and bolts passing through them. All matching holes for rivets shall be so prepared that a gauge 0.8 mm diameter less than the hole can pass freely through the members assembled for riveting. Holes other than those required for close tolerance may be punched full size through material not less than 12 mm thick.

All holes shall have their axis perpendicular to the surface bored through Holes through two or more members shall be truly concentric. No rivet or bolt hole shall be nearer the edge of the member than a distance equal to its own diameter. Holes shall not be formed by gas cutting process.

7.2.5. Assembly

7.2.5.1. Laying out - Steel structure shall be laid out on a level platform to full scale and to full size or in parts as shown on working drawings or as directed by engineer. Wooden templates 12 mm to 19 mm thick or metal sheet templates shall be made to correspond to each member and part; rivet holes shall be marked accurately on them and drilled. The templates shall be laid on the steel members and holes for riveting and bolting marked on them. The ends of the steel members shall also be marked for cutting. The base of steel columns and the positions of anchor bolts shall be carefully set out. The component parts shall be assembled in such a manner that they are neither twisted nor otherwise damaged and shall be so prepared that the specified cambers, if any, are provided. All box sections shall be sealed so as to prevent the access of moisture to the inside of the members.

Assembly shall be done by using assembly fixtures, jigs and stands which facilitate high quality assembly with proper safety. Misalignment and distortion of parts after assembly shall not be allowed; only thoroughly straightened parts free from burrs, grease, rust, etc. shall be allowed for assembly.

Temporary connection of parts during assembly shall be done in the following way:

For welded structures joining shall be done by means of tack weld, fastening devices and fixtures.

Tack welding shall be done on the side and along the line of the weld. Tack weld dimension all be minimum, welding being carried out with similar electrodes as the final welding and the tacks shall completely fuse with the final weld metal. In case splicing is necessary, the individual members shall be spliced first before assembly and before final welding with other members. For riveted structures, members shall be well tightened by assembly bolts in every third hole maximum distance between bolts shall not exceed 500 mm. To prevent stiffening drift pins shall be used 30 per cent of the assembly bolts. After tightening, the gap between members to be jointed shall be

checked by 0.2 mm thick feeler gauge which should not go inside by more than 2 mm, looseness of bolts shall be checked by tapping with a test hammer.

7.2.7. Bolting

Bolt heads and nuts shall be of such length as to project one clear thread beyond the nuts when fixed in position, and these shall fit in the holes without any shake. The nuts shall fit in the threaded ends of bolts properly. Round washers shall be placed under the heads and nuts of permanent bolts. Maximum two washers for one nut and one for each bolt head shall be used. Both threads shall be outside the limits of joining members and unthreaded portion of bolt shall not be outside the washer.

Where there is risk of the nuts being removed or becoming loose due to vibration or reversal of stresses, these shall be secured from slackening by the use of lock-nuts or spring washers, as directed by the engineer. Bolts, nuts and washers shall be thoroughly cleaned and dipped in double boiled linseed oil before use. Quality of lightening of bolts shall be inspected by tapping them with a hammer. The bolt shall not be shaken or shifted. The bolts shall be tightened starting from centre of the joint towards the edge.

7.2.8. Welding

Welding shall be done by metal arc process unless otherwise permitted by the engineer, in writing, in accordance with IS: 816-1969 Code of Practice for use of metal arc welding of general construction in mild steel, and IS: 9595-1980. Recommendation of Metal Arc Welding, regarding workmanship welding method, welding procedure with suitable electrodes and wire flux, combinations, quality of welds, correction of weld faults etc.,

7.2.9. Preparation of members for welding

Assembly of structural members shall be made with proper jigs and fixtures to ensure correct positioning of members (angles, axis, nodes etc.).

Sharp edges, rust of cut edges, notches, irregularities and fissures due to faulty cutting shall be chipped or ground or filed over the length of the affected area, deep enough to remove faults completely. Edge preparation for welding shall be carefully and accurately made so as to facilitate a good joint. Generally no special edge preparation shall be required for members under 8 mm thick.

The members to be assembled shall be clean and dry on the welding edges. Under no circumstances shall wet, greasy rust of dirt covered parts be assembled. Joints shall be kept free from any foreign matter, likely to get into the gaps between members to be welded.

Before assembly, the edges to be welded as well as adjacent areas extending for at least 20 mm shall be cleaned (Until metallic polish is achieved). When assembling members proper care shall be taken of welding shrinkage and distortions, as the drawing dimensions cover finished dimensions of the structure. The elements shall be got checked and approved by the engineer before assembly wherever it is specified. The permissible tolerances for assembly of members preparatory to welding shall be as per IS: 9595. After assembly has been checked, temporary tack welding in position shall be done by electric welding; keeping in view finished dimensions of the structure. Preheating of members to be joined to be carried put as per standards wherever necessary.

7.2.10. Butt welds

The form of joint, angle between fusion faces, gap between parts and the welding procedure shall be such that the welded joint shall comply with the design requirements. The ends of butt joints in plate shall be welded so as to provide full throat thickness. In the gas welded condition, the weld face shall be proud of the surface of the parent metal. Where a flush surface is required, the excess metal shall be dressed off. Where no dressing is to be carried out, the permissible weld profile shall be as specified in the relevant IS.

For butt weld, where these are to be welded for both sides, certain welding procedures allow this to be done without back going, but where complete penetration cannot be achieved, the back of the first run shall be gouged out to clean sound metal before welding is started on the gouged outside.

7.2.11. Fillet Welds

A fillet weld as deposited shall be not less than the specified dimensions indicated as throat thickness and/or leg thickness taking into account penetration processor partial penetration. For concave fillet welds the actual throat thickness shall be not less than 0.7 times the specified leg length. For convex fillet welds, the actual throat thickness shall be not less than 0.9 times the specified leg length.

7.2.12. Preparation of joint faces

If preparation or cutting of material is necessary, this shall be done by shearing, chipping, grinding, machining, thermal cutting or thermal gouging. When shearing is used the effect of work hardening shall be taken care of to ensure that there is no cracking of the edges. Removal of 1 mm to 2 mm from a cut face normally eliminates the layer of hardness.

7.2.13. Fusion faces

Fusion faces and adjacent surfaces shall be free from cracks, notches or other irregularities which might be the cause of defects or would interfere with the deposition of the weld. They shall also be free from heavy scale, moisture, oil, paint and any other substance which might affect the quality of weld or impede the progress of welding.

7.2.14. Assembly for welding

Jigs and manipulators should be used, where practicable, so that the welding can be carried out in the most suitable position. Jigs shall maintain the alignment with the minimum restraint so as to reduce the possibility of lock in stresses.

7.2.15. Alignment of butt joint

The root edges or root faces of butt joints shall not be out of alignment by more than 25 per cent of the thickness of the thinner material for material up to 12 mm thick or by more than 3 mm for thicker material. For certain applications closer tolerances may be necessary for proper alignment.

7.2.16. Fit up of parts jointed by fillet welds

The edges and surfaces to be jointed by fillet welds shall be in as close contact as possible since any gap increases the risk of cracking but in no case should the gap exceed 3 mm.

7.2.17. Tack welds

Tack welds shall be not less than the throat thickness or leg lengths of the root run to be used in the joint. The length of the tack weld shall not be less than four times the thickness of the thicker part or 50 mm whichever is similar. If smaller tack welds are desired, these shall be so indicated.

Where the tack weld is incorporated in a welded joint, the shape of the tack shall be suitable for incorporation in the finished weld and it shall be free from cracks and other deposition faults.

7.2.18. Protection from weather

Surface to be welded shall be dry. When rain or snow is falling or during periods of high wind, necessary precautions shall be taken for outdoor welding arc. Warming shall be carried out at all ambient temperatures below 10 degree C.

7.2.19. Inter-run cleaning

Each run of weld bead and each layer of weld shall be thoroughly cleaned of slag, spatters, etc. before depositing subsequent bead or weld with particular reference to thorough cleaning of toes of the welds. Visible defects such as cracks, cavities and other deposition faults, if any, shall be removed to sound metal before depositing subsequent run or layer of weld.

7.2.20. Welding procedure

Welding shall be carried out only by fully trained and experienced welders as tested and approved by the engineer. Qualification tests for welders as well as tests for approval of electrodes will be carried out as per IS: 823-1964. The nature of test for performance qualification for welders shall commensurate with the quality of welding required on this work as judged by the engineer. The steel structures shall be automatically, semi automatically or manually welded. Welding shall be only after the checks have been carried out. Welding procedures and Tests for welders shall be conducted as per IS: 9595 and approved by the engineer. The welder shall mark with his identification mark on each element welded by him. When welding is carried out in open air steps shall be taken to protect the places of welding against wind or rain. The electrodes wire and parts being weld on shall be dry. Before beginning the welding operation each joint shall be checked to assure that the parts to be welded are clean and root gaps provided as per IS: 9595. For continuing the welding of seams discontinued due to some reasons the end of the discontinued seam shall be melted in order to obtain a good continuity. Before resuming the welding operation the groove as well as the adjacent parts shall be well cleaned for a length of approximately 50 mm. For single butt welds (in V, ½ V or U) and double butt welds (in K, double U, etc.) the re-welding of the root butt is mandatory but only after the metal deposition on the root has been cleaned by back gouging or chipping. The welding seams shall be left to cool slowly. The contractor shall not be allowed to cool the welds quickly by any method. For multilayer welding before welding the following layer, the formerly welded layer shall be cleaned

metal bright by light chipping and wire brushing. Backing strips shall not be allowed. The order and method of welding shall be so that (a) no unacceptable deformation appears in the welded parts. (b) due margin is provided to compensate for contraction due to welding in order to avoid any high permanent stresses. The defects in welds must be rectified according to IS: 9595-1980 and as per instruction of engineer.

28. **SPECIFICATION** FOR FINISHING WORKS

PAINTING

Materials - Paints, oils, varnishes etc. of approved brand and manufacture shall be used. Only ready mixed paint (Exterior grade) as received from the manufacturer without any admixture shall be used.

If for any reason, thinning is necessary in case of ready mixed paint the brand of thinner recommended by the manufacturer or as instructed by the Engineer shall be used.

Approved paints, oil or varnishes shall be brought to the site of work by the contractor in their original containers in sealed condition. The material shall be brought in at a time in adequate quantities to suffice for the whole work or at least a fortnight's work. The materials shall be kept in the joint custody of the contractor and the engineer. The empties shall not be removed from the site of work, till the relevant item of work has been completed and permission obtained from the engineer.

15.33.2. Commencing Work - Painting shall not be started until the engineer has inspected the items of work to be painted, satisfied himself about their proper quality and given his approval to commence the painting work. Painting of external surface should not be done in adverse weather condition like hail storm and dust storm.

Painting, except the priming coat, shall generally be taken in hand after practically finishing all other building work.

The rooms should be thoroughly swept out and the entire building cleaned up, at least one day in advance of the paint work being started.

15.33.3. Preparation of Surface - The surface shall be thoroughly cleaned and dusted off. All rust, dirt, scales, smoke splashes, mortar droppings and grease shall the thoroughly removed before painting is started. The prepared surface shall have received the approval of the engineer after inspection, before painting is commenced.

- 15.33.4. Application
- 15.33.4.1. Before pouring into smaller containers for use, the paint shall be stirred thoroughly in its containers, when applying also, the paint shall be continuously stirred in the smaller containers so that its consistency is kept uniform.
- 15.33.4.2. The painting shall be laid on evenly and smoothly by means of crossing and laying off, the latter in the direction of the grains of wood. The crossing and laying off consists of covering the area over the paint, brushing the surface hard for the first time over and then brushing alternately in opposite direction, two or three times and then finally brushing lightly in a direction at right angles to the same. In this process, no brush marks shall be left after the laying off is finished. The full process of crossing and lying off will constitute one coat.
- 15.33.4.3. Where so stipulated, the painting shall be done by spraying. Spray machine used be (a) high pressure (small air aperture) type, or (b) a low pressure (large air gap) type, depending on the nature and location of work to be carried out. Skilled and experienced workmen shall be employed to the requisite consistency by adding a suitable thinner.
- 15.33.4.4. Spraying should be done only when dry condition prevails. Each coat shall be allowed to dry out thoroughly and rubbed smooth before the next-coat is applied. This should be facilitated by thorough ventilation. Each one except the last coat, shall be lightly rubbed down with sand paper or fine pumice stone and cleaned off dust before the next coat is laid.
- 15.33.4.5. No left over paint shall be put back into the stock tins. When not in use, the containers shall be kept properly closed.
- 15.33.4.6. No hair marks from the brush or clogging of paint puddles in the corners of panels, angles of moldings etc. shall be left on the work.
- 15.33.4.7. In painting doors and windows, the putty round the glass panes must also be painted but care must be taken to see that no paint stains etc. are left on the glass. Tops of shutters and surfaces in similar hidden locations shall not be left out in painting. However, bottom edge of the shutters where the painting is not practically possible, need not be done nor any deduction on this account will be done but two coats of primer of approved make shall be done on the bottom edge before fixing the shutters.
- 15.33.4.8. On painting steel work, special care shall be taken while painting over bolts, nuts, rivets overlaps etc.

14.33.4.9. The additional specifications for primer and other coats of paints shall be as according to the detailed specifications under the respective headings.

15.33.5. Brushes and containers - After work, the brushes shall be completely cleaned of paint and linseed oil by rinsing with turpentine. A brush in which paint has dried up is ruined and shall on no account be used for painting work. The containers when not in use shall be kept closed and free from air so that paint does not thicken and also shall be kept safe from dust. When the paint has been used, the containers shall be washed with turpentine and wiped dry with soft clean cloth, so that they are clean, and can be used again.

15.33.6. Measurements

15.33.6.1. The length and breadth shall be measured correct to a cm. The area shall be calculated in sqm (correct to two places of decimal), except otherwise stated.

15.33.6.2. Small articles not exceeding 10 sq. decimeter (0.1 sqm) of painted surfaces where not in conjunction with similar painted work shall be enumerated.

15.33.6.3. Painting up to 10 cm in width or in girth and not in conjunction with similar painted work shall be given in running meters and shall include cutting to line where so required.

Note: Components of trusses, compound girders, stanchions, lattices and similar work shall, however, be given in sq. meters irrespective of the size or girth of members. Priming coat of painting shall be included in the work of fabrication.

15.33.6.4. In measuring painting, varnishing, oiling etc. of joinery and steel work etc. The coefficients as indicated in following tables shall be used to obtain the area payable. The coefficients shall be applied to the areas measured flat and not girthed.

Table 1 Equivalent plain areas of uneven surface

SI. No	Description of work	How measured	Multiplying coefficients
1	2	3	4
I.	Wood work doors, windows etc.		
1	Panelled or framed and braced doors, windows etc.	•	1.30 (for each side)

2	Ledged and battened or ledged, battened and braced doors, windows etc.		
3	Flush doors etc.	- do -	1.20 (for each side)
4	Part panelled and part glazed or gauzed doors, windows etc. (Excluding painting of wire gauze portion)	- do -	1.00 (for each side)
5	Fully glazed or gauged doors, windows etc. (Excluding painting of wire gauze portion)	- do -	0.80 (for each side)
6	Fully venetianed or louvered doors,	- do -	1.80 (for each windows etc. side)
7	Trellis work one way or two way	Measured flat overall, no deduction shall be made for open spaces, suppor ting members shall not be measured separately	2 (for pain- ting all over)
8	Carved or enriched work	Measured flat	2 (for each side)
9	Weather boarding	Measured flat (not girthed supporting frame work shall not be measured separately)	each side)
10	Wood shingle roofing	Measured flat (not girthed)	1.10 (for each side)
11	Boarding with cover fillets and	Measured flat (not girthed)	1.05 (for each match boarding side)
12	Tile and slate battening	Measured flat overall no deductions shall be made for open spaces	0.80 (for painting all over)
II.	Steel Work Doors, Windows, etc		

13	Plain sheeted steel doors or windows	Measured flat (not girthed including frame edges etc.)	1.10 (for each side)
14	Fully glazed or gauzed steel doors and windows (excluding painting of wire gauze portion)	- do -	0.50 (for each side)
	Partly panelled and partly glazed doors and windows (excluding painting of wire gauze portion)	- do -	0.80 (for each side)
16	Corrugated sheeted steel doors or windows	- do -	1.25 (for each side)
17	Collapsible gates	Measured flat	1.50 (for painting all over)
18	Rolling shutters of interlocked laths	Measured flat (size of opening) all over; jamb guides, bottom rails and locking arrangement etc. shall be included in the item (top cover shall be measured separately)	1.10 (for each side)
Ш.	General		
19	Expanded metal, hard drawn steel Wire fabric of approved quality, grill works and gratings in guard Bars, balustrades, railing partitions and MS bars in windows frames	no deduction shall be made for open spaces; supporting members shall not be measured separately.	all over)
	Open palisade fencing and gates inclu ding standards, braces, rails stays etc. in timber or steel.	- do - (see note No. 12)	1 (for paint all over)
	Corrugated iron sheeting in roofs, side cladding etc.	- do – Measured flat (not girthed)	1.14 (for each side)
	AC semi-corrugated sheeting in roofs, side cladding etc.	- do -	1.20 (for each side)

AC semi-corrugated sheeting in roofs, side cladding etc. or Nainital pattern using plain sheets	- do -	1.10 (for each side)
Wire gauze shutters including painting of wire gauze.	- do-	1.00 (for each side)

Explanatory notes for Table 1:

- 1) Measurements for doors windows etc., shall be taken flat (and not girthed) over all including frames, where provided. Where frames are not provided, the shutter measurements shall be taken.
- 2) Where doors, windows, etc., are of composite types other than those included in Table 1 the different portion shall be measured separately with their appropriate coefficients, the center line of the common rail being taken as the dividing line between the two portions.
- 3) The coefficients for door and windows shall apply irrespective of the size of frames and shutter members.
- 4) In case steel frames are used the area of doors, windows shutters shall be measured flat excluding frames.
- 5) When the two faces of a door, window etc. are to be treated with different specified finishes, measurable under separate items, the edges of frames and shutters shall be treated with the one or the other type of finish as ordered by the Engineer and measurement of this will be deemed to be included in the measurement of the face treated with that finish.
- 6) In the case where shutters are fixed on both faces of the frames, the measurement for the door frame and shutter on one face shall be taken in the manner already described, while the additional shutter on the other face will be measured for the shutter only excluding the frame.
- 7) Where shutters are provided with clearance at top or / and bottom each exceeding 15 cm height, such openings shall be deducted from the overall measurements and relevant coefficient shall be applied to obtain the area payable.
- 8) Collapsible gates shall be measured for width from outside to outside of gate in its expanded position and for height from bottom to top of channel verticals. No

- separate measurements shall be taken for the top and bottom guide rails rollers, fittings etc.
- 9) Coefficients for sliding doors shall be the same as for normal types of doors in the table. Measurements shall be taken outside to outside of shutters, and no separate measurements shall be taken for the painting guide rails, rollers, fittings, etc.
- 10) Measurements of painting as above shall be deemed to include painting all iron fittings in the same or different shade for which no extra will be paid.
- 11) The measurements of guard bars, expanded metal, hard drawn steel wire fabric of approved quality, grill work and gratings, when fixed in frame work, painting of which is once measured else where shall be taken exclusive of the frames. In other cases the measurements shall be taken inclusive of the frames.
- 12) For painting open palisade fencing and gates etc., the height shall be measured from the bottom of the lowest rail, if the palisades do not go below it, (or from the lower end of the palisades, if they project below the lowest rail), up to the top of rails or palisades whichever are higher, but not up to the top of standards when the latter are higher than the top rails or the palisades.
- 15.33.6.5. Width of moulded work of all other kinds, as in hand rails, cornices, architraves shall be measured by girth.
- 15.33.6.6. For trusses, compound girders, stanchions, lattice girders, and similar work, actual areas shall be measured in sq. meters and no extra shall be paid for painting on bolt heads, nuts, washers etc. even when they are picked out in a different tint to the adjacent work.
- 15.33.6.7. Painting of rain water, soil, waste, vent and water pipes etc. shall be measured in running metres of the particular diameter of the pipe concerned. Painting of specials such as bends, heads, branches, junctions, shoes, etc. shall be included in the length and no separate measurements shall be taken for those or for painting brackets, clamps etc.
- 15.33.6.8. Measurements of wall surfaces and wood and other work not referred to already shall be recorded as per actual.
- 15.33.6.9. Flag staffs, steel chimneys, aerial masts, spires and other each objects requiring special scaffolding shall be measured separately.
- 15.33.7. **Precautions -** All furniture's fixtures, glazing, floors, etc. shall be protected by covering and stains, smears, splashing's, if any shall be removed and any damages done shall be made good by the contractor at his cost.

15.33.8. **Rate** - Rates shall include cost of all labour and materials involved in all the operations described above and in the particular specifications given under the several items.

Dismantling

The term "dismantling" implies carefully taking up or down and removing the building materials without damaging them. The articles dismantled shall be lowered to the ground and not thrown. Dismantling work shall cover complete removal of the existing structure or part of a work including all relevant items as indicated or as directed, clearing the site, sorting out useful materials and stacking them as described, and disposing of the unserviceable materials

8.17.2 Serviceable materials

Any material which is in the opinion of the engineer could be refused or otherwise useful will be considered as serviceable

8.17.3 Unserviceable materials -

Any material declared by the engineer are not serviceable shall be considered as unserviceable.

A register shall be opened at the work site to show day-to-day account of the turn out of salvaged materials. The register shall also indicate whether dismantled materials are properly stacked or wasted.

The contractor shall be reasonable for the safe custody of serviceable materials until handed over to the engineer's representative or incorporated in the work and a written receipt for the same obtained.


SECTION V

DRAWINGS

Brief Description of drawing

The Works are shown in the following drawings that are issued as a part of the Tender Documents:

SI. No	Drawing No.	Description
1	21/85-LP	LOCATION PLAN



21/85-LP	LOCATION PLAN



NEW MANGALORE PORT AURHORITY Panambur, Mangalore

ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER

TENDER DOCUMENT
Volume - III

Table of Contents

SECTION VI	148
(i) PREAMBLE TO BILL OF QUANTITIES	148
1. General Instructions	148
2. Civil Works	151
3. Abbreviations	154
ii) ii) BILL OF QUANTITIES	156
(iii) FORM OF TENDER	164
SECTION VII	166
SCHEDULE - A	166
ROYALTY	166
SCHEDULE - B	172

VOLUME III

SECTION VI

(i) PREAMBLE TO BILL OF QUANTITIES

1. General Instructions

1.1 General

- 1.1.1 This Bill of Quantities must be read with the Drawings, Conditions of Contract and the Specifications, and the Contractor shall be deemed to have examined the Drawings, Specifications, Conditions of Contract and to have acquainted himself with the detailed descriptions of the Works to be done, and the way in which they are to be carried out.
- 1.1.2 Notwithstanding that the work has been sectionalized every part of it shall be deemed to be supplementary to and complementary of every other part and shall be read with it or into it so far as it may practicable to do so.
- 1.1.3 The detailed descriptions of work and materials given in the Specifications are not necessarily being repeated in the Bill of Quantities.
- 1.1.4 The Contractor shall be deemed to have visited the Site before preparing his tender and to have examined for himself the conditions under which the work will proceed and all other matters affecting the carrying out of the works and cost thereof.
- 1.1.5 The Tenderer will be held to have familiarised himself with all local conditions, in so far as they affect the work, means of access and the locality of existing services, in order to execute the Works measured and described hereinafter. No claims for want of knowledge in this respect will be reimbursed.

1.2 Rates and Prices to be Inclusive

1.2.1 Rates and prices set against items are to be the all inclusive value of the finished work shown on the Drawings and/or described in the Specification or which can reasonably be inferred there from and are to cover the cost of provision of plant, labour, supervision, materials, test charges, freight,

transportation, erection, installation, performance of work, care of works, insurance, maintenance, overheads and profits and every incidental and contingent cost and charges whatsoever including all taxes if any excluding GST and every kind of temporary work executed or used in connection therewith (except those items in respect of which provision has been separately made in the general condition of contract) and all the Contractor's obligations under the Contract and all matters and things necessary for the proper completion and maintenance of the Works.

- 1.2.2 The rates and prices set down against the items are to be the full inclusive value of the finished work shown on the Drawing and/or described in the Specification or which can reasonably be inferred the reform and to cover the cost of every description of Temporary Works executed or used in connection therewith (except those items in respect of which specific provision has been separately made in these Bills of Quantities) and all the Contractor's obligations under the Contract including testing, giving samples and all matters and things necessary for the proper execution, completion and maintenance of the Works.
- 1.2.3 The Specifications are intended to cover the supply of material and the execution of all work necessary to complete the works. Should there be any details of construction or material which have not been referred to in the Specifications or in the Bill of Quantities and Drawings, but the necessity for which may reasonably be implied or inferred there from, or which are usual or essential to the completion of all works in all trades, the same shall be deemed to be included in the rates and prices entered in the Bill of Quantities. The rates and prices are to cover the item as described in the Bill of Quantities and if there is inconsistency in the description between the Bill of Quantities, Specifications or Drawings, the interpretation will be done according to General Conditions of Contract.
- 1.2.4 The quantities given in the Bill are approximate and are given to provide a common basis for tendering. They are not to be taken as a guarantee that the quantities scheduled will be carried out or required or that they will not be exceeded. The Employer / Engineer reserves the right to delete any item and / or increase / reduce quantities indicated in the Bills of Quantities at any

time. Payment will be made according to the actual quantities of work ordered and carried out in the contract. However, the rates quoted shall be valid for any extent of variation in quantity of each individual item provided that the total contract value does not get altered by more than indicated in conditions of contract. No claim whatsoever for extra payment due to variation of quantities within the above said limit would be entertained.

- 1.2.5 The drawings for tender purposes are indicative only of the work to be carried out. However, the Tenderer must allow within his price for the items of work included in the Tender Documents for the details which will appear on subsequent drawings developed for construction purposes. Rate and price shall include any additional design/ detailing to be carried out by contractor.
- 1.2.6 The rates and prices shall include (except where separate items are given) for the provision and operation of the following items, for compliance with the Conditions of Contract, Special Conditions, the specifications and Tender drawings:
 - i) Supervision and labour for the Works;
 - ii) All materials, installation/erection, handling and transportation;
 - iii) All Contractor's Equipment;
 - iv) All testing, commissioning, insurance, maintenance, security, welfare facilities, overheads and profit and every incidental and contingent costs and charges whatsoever including;
 - v) All temporary fencing, watching, lighting, sanitary accommodation, general security arrangements, welfare facilities and first aid provision;
 - vi) Provision and maintenance of Contractor's site offices, cabins, huts, maintenance and storage areas;
 - vii) All taxes if any excluding GST on the transfer of property in goods in the execution of works, Excise Duty, Duties, etc. (other than Customs Duty for materials to be permanently incorporated into the Works);
 - viii) All necessary temporary services including fresh water, compressed air lines, electrical cabling and switchgear, telephone, walkie-talkie and facsimile facilities;
 - ix) The maintenance of all Contractor's services:
 - x) All insurances for the Works;
 - xi) Allowance for complying with all environmental aspects as specified;
 - xii) Detail design of components of temporary works, wherever

necessary as directed by Engineer.

1.4 Method of Measurement

- 1.4.1 Measurement of Work shall be in accordance with IS 1200 and shall be net off the dimensions of the works shown on the drawings except as mentioned below:
- 1.4.2 Units of Measurement: The units of measurement used in this Bill of Quantities are in metric units as follows:
 - i) Linear: Linear metre, centimeter or millimeter abbreviated to 'Rm', 'cm' or 'mm' respectively.
 - ii) Superficial: Square metre or Square centimeter abbreviated to 'Sq.M' or 'sq.cm' respectively.
 - iii) Volumetric: Cubic metre abbreviated to 'cu.m'. Litre abbreviated to 'L'
 - iv) Weight: Tonne = 1000 Kilograms, abbreviated to 'T', / 'MT' Kilogram abbreviated to 'kg'
 - v) Numbers: Numbers abbreviated to Nos. or No.
 - vi) Lump sum: Lump sum abbreviated to 'L.S.'

1.5 Currency

1.5.1 All monetary reference herein and the Bill of Quantities shall be priced in Indian Rupee Currency.

2. Civil Works

- 2.2 Precast Concrete
- 2.2.1 Shuttering for precast concrete shall not be measured and paid for separately.
- 2.2.2 Effort for placement of precast concrete at the final locations shall not be measured unless a specific item is provided in the Bill of Quantities.
- 2.2.3 The precast concrete units shall be measured as shown on the detailed drawings.
- 2.3 In-situ Concrete
- 2.3.1 Shuttering for In-situ concrete shall not be measured and paid for separately.
- 2.3.2 No deduction will be made for chamfers smaller than 50 sq.cm. sectional area, reinforcement bolts and other embedded parts unless larger than 0.1 sq.m. sectional area and 0.03 cu.m. in volume. No extra volume will be measured for splays or fillets smaller than 50 sq.cm. sectional area.

- 2.3.3 The rates for reinforced concrete shall include for all batching, mixing, transporting, hoisting or lowering to any height / depth, placing in position and compaction in work of any sectional area or thickness including shuttering, forming necessary construction joints, shear keys and stop ends, and for curing and protecting etc. all as specified.
- 2.3.4 The rates shall include for preparing construction joints, shear keys and surfaces against which next stage concrete is to be cast and building in fittings including pipes and bolts except where specifically billed separately. No separate payment will be made for making openings/pockets/pits of any size and shape. Where surfaces are to receive finishes the rates shall include for leaving the surface rough or for hacking and roughening the surface to form a key.
- 2.3.5 Unless otherwise noted, rates shall include for inserting pipes and other inserts in position accurately, concreting while they are in position and also for protecting the same as the work proceeds.
- 2.3.6 Unless otherwise noted, the rates for concrete items shall include for finishing the top surface to levels and slopes and surface finish as specified. Rates for concrete shall include for finishing the slab to specified slope towards drains, etc.

2.4 Reinforcement

- 2.4.1 Steel reinforcement will be measured by weight and fixed in accordance with Drawings and Specifications. The weight of reinforcement bars -whether plain, deformed or ribbed etc., -of various diameters will be calculated in accordance with Table 1 of IS:1732 'Dimensions for Round and Square Steel Bars for Structural and General Engineering Purposes'.
- 2.4.2 The rates shall include for laps, cutting and waste, straightening short and long lengths, bending, fixing, rolling margin and the provision of spacer bars or support, chairs, binding wire, saddles, forks and all dense concrete spacer blocks, etc., including preparing bending schedules from the Drawings.

- 2.4.3 The rates shall include for all necessary descaling, wire brushing and cleaning to remove all rust and mill scale, dirt, grease and other deleterious matter before fixing and whilst still exposed during construction.
- 2.5 Structural and Miscellaneous Steel work
- 2.5.1 Rates for structural steel work and iron work shall include supply, fabrication, delivery and erection/embedment in concrete at Site and all charges for welding, cutting, bending, bolting, site connections, fixing to foundations.
- 2.5.2 The rates for Structural Steelwork shall include:
 - i) Supply, fabrication, delivery and erection
 - ii) Rolling margin, cutting and waste, weld metal, bolts, fixings and fittings
 - iii) Hoisting, drilling, bolting or welding and fixing in the manner specified or indicated in the drawing
 - iv) Fabrication drawings
 - v) Welding trials and tests
 - vi) Erection trials
 - vii) Protective treatment (painting, hot dip galvanizing etc), including making good any damage if provided in the BOQ item.
- 2.5.3 Metalwork items are described in the Bills of Quantities and the Tenderer is to include for all the fittings, etc., described. All items shall include the necessary fabrication, joints, angles, intersections and ends, all bolts or fixing lugs, all hoisting and scaffolding required and casting in fixings or later cutting out or forming pockets for same, grouting, supporting and making good.
- 2.5.4 Rates are to include for all necessary scaffolding, working over water and at any height staging and hoisting and tarpaulin or other protective covers and the cleaning and removal of paint stains and spots, etc.
- 3.4.1 The Contractor's unit rates and prices shall include all equipment, apparatus, material indicated in the Drawings, and/or Specifications in connection with the item in question and also associated labour as well as all additional equipment, apparatus, material, consumables usually necessary to complete the system even though not specifically shown, described or

otherwise referred to and also associated labour.

3.4.2 The rate for providing and fixing above items shall include all fittings, fixtures, base and sole plates, anchor bolts, including epoxy grouting, etc. all complete as specified, including the necessary additional supervision to ensure accurate alignment

3. Abbreviations

4.1.1 The following abbreviations are used in the Specifications and Bill of Quantities:

IS: Indian Standard BS: British Standard Oty.: Quantity mm: Millimeters Cm: Centimeters M / m: Meters LM: linear metre LS: lump sum Rs.: Rupees P.: Paise Nos.: Numbers do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) squm. / m² / square metre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Circular set: Set / sets c/c centre to centre	Bill of Qual	
Oty.: Quantity mm: Millimeters cm: Centimeters M / m: Meters LM: linear metre LS: lump sum Rs.: Rupees P.: Paise Nos.: Numbers do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m²/ sqmt sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately incl: lincluding circ: Circular set: set / sets	IS:	Indian Standard
mm: Millimeters cm: Centimeters M/m: Meters LM: linear metre LS: lump sum Rs.: Rupees P.: Paise Nos.: Numbers do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m²/ square metre sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: lincluding circ: Circular set: set / sets		
Cm: Centimeters M / m: Meters LM: Ilinear metre LS: Ilump sum Rs.: Rupees P.: Paise Nos.: Numbers do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m² / square metre sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Circular set: set / sets		
M / m :		
LM: linear metre LS: lump sum Rs.: Rupees P.: Paise Nos.: Numbers do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m² / square metre sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Circular set: set / sets		
LS: lump sum Rs.: Rupees P.: Paise Nos.: Numbers do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m² / square metre sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Circular set: set / sets		
Rs.: Rupees P.: Paise Nos.: Numbers do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m² / square metre sqnt sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: lincluding circ: Set: set / sets		
P.: Paise Nos.: Numbers do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m² / square metre sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: circ: Set: set / sets		
Nos.: Numbers do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m² / sqmt sq.cm.: square metre mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Circular set: set / sets		,
do: Ditto MS: mild steel T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m²/ sqmt sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Circular set: set / sets		
MS: Times Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m² / sqmt sq.cm.: square metre mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: lincluding circ: Circular set: set / sets		
T: Tones Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m² / sqmt sq.cm.: square metre sq.cm.: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Circular set: set / sets		
Kg: Kilogram EO: Extra over (previous sum unless specified otherwise) sq.m. /m² / sqmt sq.cm.: square metre mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Set: set / sets		
EO: Extra over (previous sum unless specified otherwise) sq.m. /m²/ sqmt sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Circular set: set / sets		
otherwise) sq.m. /m² / sqmt sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: clircular set: set / sets		· ·
sq.m. /m² / sqmt sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: circ: Set : set / sets	EO:	
sqmt sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: circ: Circular set: set / sets		,
sqmt sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: circ: Circular set: set / sets	sa.m. /m ² /	square metre
sq.cm.: square centimeters mm²: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Set: set / sets		
mm 2: Square Millimetre Cu.m. / cum: cubic meters YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Set : set / sets	sq.cm. :	square centimeters
YST: yield stress dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Set: set / sets	mm ² :	Square Millimetre
dia: Diameter wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Circular set: set / sets	Cu.m. / cum:	cubic meters
wt.: Weight Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Circular set: set / sets	YST:	yield stress
Drg.No.: drawing number max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Circular set: set / sets	dia:	Diameter
max.: Maximum min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Circular set: set / sets	wt.:	Weight
min: Minimum approx: Approximately n.e.: not exceeding incl: Including circ: Circular set: set / sets	Drg.No.:	drawing number
approx: Approximately n.e.: not exceeding incl: Including circ: Circular set: set / sets	max.:	Maximum
n.e.: not exceeding incl: Including circ: Circular set: set / sets		
incl: Including circ: Circular set: set / sets	approx:	Approximately
circ: Circular set: set / sets	n.e.:	not exceeding
set: set / sets	incl:	Including
	circ:	Circular
c/c centre to centre	set:	set / sets
	c/c	centre to centre

@:	at the rate of
QtI	Quintal

ii) ii) BILL OF QUANTITIES

NAME OF WORK: ANNUAL MAINTENANCE OF FENDERS, MOORING LADDERS, BOLLARDS, ROOFING SHEET AND ROLLING SHUTTERS INSIDE SECURITY COMPOUND WALL FOR THE YEAR 2023-24 AND 2024-25 (TWO YEARS)-RE TENDER

	NO)-RE TENDER			RATE	
Ite m No.	DESCRIPTION OF ITEM	QTY	UNIT	IN figures / WORD S	AMOUNT (Rs. Ps.)
1	Servicing of rolling shutter by providing and applying multipurpose grease to all parts of the rolling shutters of all sizes such as 'U' channels, side guides, latches, locks, coil springs and gear type arrangements etc. after thoroughly cleaning the surface so as to make the movement of the shutter free including cost and conveyance of all materials, labour charges, climbing arrangements, hire charges of T&P and all other incidental charges etc. complete for successful completion of the work.	100.00	Nos	770.00	77,000.00
2	Replacing steel laths of 18 gauge and 75mm width including cutting to the required length, providing interlocking arrangements for steel laths by means of alternate end clips to the existing laths etc. complete as directed by the Engineer in charge.	200.00	Rm	171.88	34376.00
3	Replacing the bottom plate with 12 gauge plates including providing locking arrangements, handling and providing other accessories to the required length, cost of all materials, labour charges for fixing, painting two coats over a coat of primer etc. complete. as directed by Engineer in charge.	20.00	Rm	742.50	14850.00

4	Providing & fixing top covers made out of 20 gauge MS sheet over pull and push rolling shutters bent to shape including cost of red lead primer coat painting, materials, labour etc. complete	20.00	Rm	696.30	13926.00
5	Replacing the rolling shutter springs with 3 gauge 3 1/2" dia. 13" to 14" length coil springs including removing the rolling shutter center shaft & fixing the springs with required tension, greasing the required parts etc. complete as directed by the Engineer in charge.	24.00	Nos	1925.00	46200.00
6	Replacing the gear attachment and gear box for the rolling shutter for free movement of folding including gear shaft, fixing firmly on wall with bolts of standard size including cost of all materials & tools etc. complete.	4.00	Nos	9625.00	38500.00
7	Providing & fixing pull & push type rolling shutters out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with high tension coil type springs two number, mounted on specially designed pipe shaft with bracket plates, guide channels, ball bearing arrangements for inside & outside locking with push & pull operations complete including pulling hooks, 4 nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of all materials labour, HOM of machinery complete as per specifications.	50.00	m2	3091.00	154550.00

8	Providing & laying to required line and slope roofing with corrugated cement sheet 6mm thick fixed with galvanized iron J or L hooks, bolts and nuts 8mm dia., CI plain and bitumen washers over the existing purlines rafter and truss including cost of materials, labour and all other incidental charges with removing the old damaged sheets. etc., complete	600.00	m2	428.45	257070.00
9	Providing & fixing ridges, hips with cement sheet roofing with GI or L hooks bolts and nuts 8mm dia with CI and bitumen washers including cost of all materials labour etc. complete	60.00	Rm	291.50	17490.00
10	Cutting and removing the existing, corroded, damaged GI 'J' / 'L' hooks provided on the roofing of Transit sheds / Overflow sheds / go-downs and providing & fixing new 600mm long GI 'J' / 'L' hooks with nuts and washers over the existing AC / galvalume sheet roofing, purlins, rafters, channels and trusses including cleaning the surface and sealing the 'J' bolts with CI and bitumen washers including cost of all materials, cost of form work / scaffolding, cost of labour, Tools & Plants and all other incidental charges etc. complete as directed by the department.	4000.00	Nos	41.25	165000.00
11	Cleaning the valley gutter, water gutter, removing all deposited materials and disposing the same with a lead of 50m including cost of all tools & plants, labour charges, all necessary arrangements for working over the AC sheet roofing with necessary scaffolding/ staging, and all other incidental charges etc. complete as directed by the department.	300.00	Rm	6.66	1998.00

12	KSRB 13-18.1 : Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure 160mm outside diameter with all necessary specials, special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM of equipment and testing complete as per specifications.	60.00	Rm	911.35	54681.00
13	Fabricating, supplying & erecting Angular Truss for all spans, Mooring ladders, Manhole Chamber Covers, grill gates, hand railings, barricades, repairs to frontal frame and bollards using Mild Steel sections such as plates, tubes, angles, channels, plate section as directed by the Engineer-in-charge as per approved designs and drawing. The fabricated items shall either be welded or anchored suitably by using M.S. anchor bolts at each support with base plates, shoe plates etc. The work includes, cutting, straightening, placing in position of M.S. section and welding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of materials, labour charges, & hire charges of machineries for cutting, welding, grinding & erection equipment's, etc., complete as per specification for the successful completion of the work.	11000.00	Kg	140.25	1542750.00
14	Dismantling of existing structures comprising of steel work in all type of sections up to a height of 5 m above plinth level including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking serviceable material in stack yard with all lifts complete as per specification.	6600.00	Kg	21.04	138864.00

15	Providing and installing of prepainted galvalume iron Trapezoidal profiled sheet 1060mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the center for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ 150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling / self tapping screws of 25mm length, to be fixed over the existing purlins, rafters, channels and trusses.	1200.00	m2	847.00	1016400.00
16	Providing and installing prepainted galvalume iron Accessories like, plain ridges, plain gutter, plain flashing, corner trim, etc. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ 150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using using GI 'J' / 'L' hooks with nuts & washers of required size and length or self-drilling / self tapping screws of 25mm length, (width upto 500-600mm only), to be fixed over the existing purlins, rafters, channels and trusses and making holes and fixing arrangements for rain water down take pipes etc. complete.	400.00	m2	814.00	325600.00

17	Providing and fixing in position 12mm thick plaster of paris (Gypsum anhydrous) for ceiling reinforced with heissian cloth flat surface with ceiling tiles upto a height of 5 m above floor level over aluminium strips and rendered smooth with plaster of paris including cost of materials, labour, curing complete as per specifications.	200.00	m2	1025.75	205150.00
18	Providing & applying water proofing bituminous membrane reinforced with non-woven polyester fabric, weighing 180gm/sqm granular finish 4mm thick by torch on application method confirming the standard manufacturers specification and as directed by the department.	200.00	m2	528.00	105600.00
19	Dismantling the damaged Giant Tyre Fender from the Berth and Fixing the New / Released tyre fenders with GI chain, nylon rope etc., including stacking the released fender at stack yard, transporting the new tyre fender to worksite, providing necessary holes for inserting the GI chain and fixing at site including cost of all materials, tools and plants, hire charges of crane, transportation, labour charges etc. complete as per site requirement. (Excluding the cost of tyre fender, GI chain, shackels, nylon rope etc which will be supplied by department.)	30.00	Nos	4576.00	137280.00
20	Dismantling the dislocated Giant Tyre Fender from the Berth and Refixing the same in required position, with new GI chain, nylon rope etc., including cost of all materials, labour, tools and plants, hire charges of cranes etc., complete as per the site requirements. (Excluding the cost of tyre fender, GI shackles, chains etc. which will be supplied by Department)	80.00	Nos	2576.00	206080.00

21	Periodical inspection of Fenders, tightening of all loosened bolts properly, checking the holding chains, hooks including chipping and cleaning the rust and other loose particles such as iron ore fines, coal dust, fungal and algae growth from fender frontal frames, chains etc., of all the fenders from Berth Nos. 1 to 8 and Berths Nos. 09 to 14, including cost of all materials, ladders, labours, tools and plants and all other incidental charges etc., complete.	24.00	Opn	10264.00	246336.00
22	Replacing the damaged / missing / rusted fender bolts with sleeves including drilling holes in the concrete by core cutting machine at required place suitable for fixing sleeves, fixing the sleeve to the holes and grouting with Epoxy mortar etc., including cost of all materials, scaffolding, labour charges, tools and plants, and all other incidental charges etc. complete as per the site requirement.	80.00	Nos	1925.00	154000.00
23	Dismantling the damaged V / W type fender from the berth and refixing the available V / W type fender with necessary bolts etc., including removal of all bolts fixed to the sleeves, lifting fender by using Escort / Hydra crane, transporting and stacking at departmental stack yard, transporting new fender and fixing at site, including cost of all materials, labour charges, tools & plants, hire charges of crane, transportation, scaffolding charges and all other incidental charges etc. complete as per site requirements. (Excluding the cost of fender, bolts etc. which will be supplied by department)	10.00	Nos	10874.40	108744.00

24	Providing and painting of letters of 16cms height in english for numbering of fenders by providing and applying synthetic enamel paint of approved colour & shade including cost of all materials, labour, T&P, hire charges, etc., complete as directed by the department.	550.00	Nos	55.00	30250.00
25	Painting with synthetic enamel paint of required colour to give an even shade: One coats on old work as per specifications and as per directions of Engineer in charge.	6000.00	m2	59.00	354000.00
26	Providing and installing Turbo ventilators at suitable place including all labour and incidental charges etc. complete	10.00	Nos	7700.00	77000.00
27	Credit to taking away of the steel scrap materials / (Buy back) inclusive of cost of labour, hire charges of machineries, cost of tools and plants, loading unloading and all other incidental charges etc., complete as directed by the department.	-6600.00	Kg	31.53 OTAL Rs	208098.00
		53,15,597.00			
	Excess/Less (Ir				
		Quoted Ar	mount i	n Figures	

(Quoted amo	unt in Words	s Rupees	
-------------	--------------	----------	--

Note: GST as applicable shall be claimed as separate line item in tax invoice

and the same will be paid separately.1. Contractor shall file the applicable returns with tax department in time and submit the same as documentary evidence

SIGNATURE OF THE BIDDER

(iii) FORM OF TENDER

NAME	E OF CONTRACT
New N Panar	utive Engineer (Civil) Mangalore Port AURHORITY mbur alore - 575 010
Sir	
1.	We have examined the Conditions of Contract, Specification, Drawings, Bill of Quantities, and Addenda Nos for the execution of the above-named Works, and we the undersigned, offer to execute and complete such Works and remedy any defects therein in conformity with the Conditions of Contract, Specifications, Drawings and Bill of Quantities and Addenda
2	We acknowledge that the Appendix forms part of our Tender.
3.	We undertake, if our Tender is accepted, to commence the Works as soon as is reasonably possible after the receipt of the Engineer's notice to commence, and to complete the whole of the Works comprised in the Contract within the time stated in the Appendix to Tender.
4.	We agree to abide by this Tender for the period of 120 days from the last date fixed for receiving the same and it shall remain binding upon us and may be accepted at any time before the expiration of that period.
5.	Unless and until a formal Agreement is prepared and executed, this Tender together with your written acceptance thereof shall constitute a binding Contract between us.
6	We understand that you are not bound to accept the lowest or any tender you may receive.
Dated	d this day of 201
Signa autho	in the Capacity of duly orised to sign Tenders for and on behalf of

(IN BLOCK LETTERS)

	Address:
Witnesses	
1. Signature : Name : Address :	
2. Signature : Name : Address :	

SECTION VII

SCHEDULE - A

ROYALTY SCHEDULE II

(See sub rule (1) of Rule 36)

SI.	Name of the Mineral	Present Rate of	Royalty to be	
No.		Royalty	revised	
			Export	Domestic
1	Ornamental and Decorative Building Stones as defined under clause(m) of Rule 2 A)Dyke Rock (i)Black granites:	15% of Sale Value or	Rs.1,200	Rs.600
	(a)Chamarajanagar District:	of Average Selling Price on advalorembasisor Rs.4,500 per m3 which is higher.	per MT	per MT
	(b)All other Districts other than(a)above	15% of Sale Value or of Average Selling-Price on advalorem basis orRs.1,500 per m3 which is higher.	Rs.1700 per MT	Rs.400 per MT
	(ii)Other varieties of dyke other than black granites(Entire State)	15% of Sale Value or of Average Selling Price on advulorembasis or Rs.1,500per m3 which is higher.	Rs.500 per MT	Rs.375 per MT
	(B)(I)Pink and Red Granites (Ilkal Pink Variety) (i) Hungunda and BadamiTaluk of Bagalkot District, Kustagi of Koppal District.	15%of Sale Value or of Average Selling Price on advalorembasis or Rs.1,200	Rs.1,000 per MT	Rs.400pe rMT
	(ii) Pink and Red Granites, Gneissess and their structural verities (other than Ilkal Pink Variety)	15% of Sale Value or Average Selling Price on advalorem basis or Rs.1,800 Variety) per m3	Rs.600 per MT	Rs.350 per MT

		which is higher		
	C)Grey and White Granites	15% of SaleValue or		
	and their varieties:	of Average Selling		
	(i) Very fine grained Grey	Price on		
	granite	advalorembasisor	Rs.500	Rs.350
	(SiragreyVariety)	Rs.1,350 per m3	per MT	per MT
	Price on Chintanmi,	which is higher.		
	SiddlaghattaofChikkab			
	allapuraDistrictHoskot			
	e of Bangalore			
	District.			
	(ii) Greyandwhitegranites	15% of SaleValue or	Rs.375	Rs.250
	and textural varieties	of Average Selling	per MT	per MT
	having shades of grey,	Price on		
	balckand white	advalorembasisor		
	colours (other than (i)	Rs.1,050 per m3		
	above Entire State.	which is higher.		
		-		
	(iii) Grey granite of	15% of SaleValue	Rs.300	Rs.200
	DevanahalliTaluk of	or of Average	per MT	per MT
	Bangalore Rural District	Selling Price on		
	and	advalorembasisor		
	Chikkaballapurtaluk	Rs.600 per m3		
	of Chikkaballapur	which is higher.		
	District			
2	Felsite and its varieties	15% of SaleValue	Rs.900 pe	r MT
	suitable for use as	or of Average		
	Ornamental Stone-	Selling Price on		
	Entire State	advalorembasisor		
		Rs.1800 per m3		
		which is higher.	D 000	N 4T
3	Quartzite and sand	15% of Sale Value	Rs.900 pe	rIVII
	stone and their varieties	or of Average		
	suitable for use as	Selling Price on		
	Ornamental Stone-	advalorembasisor		
	Entire State	Rs.1800 per m3		
		which is higher.	D 4000	D 4-
4	Marable and	15% of Sale Value	Rs.1000 p	er IVI I
	Crystalline Limestone	or of Average		
	as ornamental Stone-	Selling Price on		
	Entire State	advalorembasisor		
		Rs.1800 per m3		
5	Pontonito Entiro Stato	which is higher.	Dc 500 pc	r MT
5	Bentonite-Entire State	Rs.400 per MT	Rs.500 pe	I IVI I

6	Fuller Earth-Entire	Rs.125 per MT	Rs.125 per MT
7	State Buff colour (waste) the permits notexceed20% of permit issued For Fullers Earth	Rs.60 per MT	Rs.70 per MT
8	Limestone under the title "Shahabad Stone"	Rs.70 per 10 Sqmeters or Rs.70 per MT	Rs.50 per 10 Sqmeters or Rs.50 per MT
9	Limestone(non-cement) when used for building stone-Entire State	Rs.25 per MT	Rs.60 per MT
10	Ordinary Building Stone(Entire State as defined under clause(g) of Rule2(1)	Rs.60 per MT	Rs.70 per MT
11	Limeshell-Entire State	100 per MT	120 per MT
12	Lime Kankar(non cement) Entire State	50 per MT	80 per MT
13	Agate, Chalcedony, Flint-Entire State	240 per MT	300 per MT
14	Ordinary Sand-Entire State	60 Per MT	80 Per MT
15	Steatite and sand stone used formakinghousehold utensils / articles-Entire State.	40 Per MT	80 Per MT
16	(i)Murram (All types of soils)-Entire State	20 per MT	40 per MT
	(ii)Clay used for manufacturing tile sand bricks	40 per MT	60 per MT
17	Waste rocks generated in ornamental stone quarry-which is suitable for ornamental purpose Entire State (See explanation under Rule36)	300 per MT or 850 CUM	300perMT
18	Irregular shaped waste rock generated in Ornamental stone quarry, which is not suitable for ornamental purpose (used for making aggregates and	60 per MT	40 per MT

	m-sand) Entire State.		
19	Waste rocks generated in Shahabad stone quarry- Entire State (See explanation under Rule- 36)	60 per MT	40 per MT
20	Finished Kerb stones/cubes not exceeding 30 cms each face-Entire State.	110per MT	150 per MT
21	Barytes (i) A Grade (Grey colour (ii) B Grade (Greycolour) (iii) C, D Grade &Waste	6.5% of average selling price or of sale value whichever is higher on ad-valorem basis	400 per MT 300 per MT 200 per MT
22	Calcite	15% of average selling price or of sale value whichever is higher on advalorem basis	80 per MT
23	China clay and Kaolin (including Ball clay, White shell, Fireclay and white clay) i)Crude/Raw	8% of average selling price or of sale value whichever is higheronad-valorem basis.	80 Per MT
	ii)Processed	12% of average selling price or of sale value whichever is higher on advalorem basis	600 per MT
24	Corundum	12% of average sellingpriceor of sale value whichever is higher on advalorem basis	15% of Sale Value or of Average Selling Price on ad valorem basis which is higher.
25	Dolomite	Rs.75 per MT	100 per MT
26	Dunite and Pyroxenite	Rs. 30 per MT	60 per MT
27	Felsite (Other than for ornamental purpose)	12% of average selling price or of sale value whichever	120 per MT

	Г	ic higher on od	Г
		is higher on ad-	
28	Gypsum	valorem basis 20% of average	150 per MT
		selling price or of	
		sale value	
		whichever is higher	
		on ad-valorem	
		basis	
29	Jasper	12% of average	150 per MT
		selling price or of	
		sale value	
		whichever is higher	
		on ad-valorem	
		basis	
30	Quartz, feldspar	15% of average	100 per MT
		selling price or of	
		sale value	
		whichever is higher	
		on ad-valorem	
0.1		basis	1500
31	Mica	4% of average	1500 per MT
	i. Crude	selling price or of	500 per MT
	ii. Waste	sale value	
		whichever is	
		higher on ad-	
22	O	valorem basis	100 14
32	Quartzite & Fuchsite	12% of average	100 per MT
	Quartzite not suitable	selling price or of	
	for use as Ornamental	sale value	
	/Gemstones	whichever is	
		higher on ad-	
33	Laterite	valorem basis	
33	i) /dispatched for use	Rs.60 per MT	160 per MT
	in cement or	KS.00 per ivi i	100 per ivi i
	chemical industries		
	or Abrasive or		
	Refractory purpose		
	(below threshold		
	value as specified by		
	IBM from time to		
	time)		
	ii) For use as building		60 per MT
	stone (below		
	threshold value as		
	threshold value as		

	specified by IBM)		
34	Ochre	Rs.24 per MT	60 per MT
35	Pyrophyllite	20% of average	200 per MT
		selling price or of	
		sale value	
		whichever is	
		higher on ad-	
		valorem basis	
36	Shale	Rs.60 per MT	150 per MT
37	Slate	Rs.45 per MT	150 per MT
38	Silica Sand	10% of average	100 per MT
		selling price or of	
		sale value	
		whichever is higher	
		on ad-valorem	
		basis	
39	Steatite or Soapstone	18%of average	200perMT
	(Other than for house	selling price or of	
	hold articles)	sale value	
		whichever is higher	
		on ad-valorem	
	Tala	basis	200manMT
10	Talc		200perMT
40	All other minerals (which	30% of sale value on	30% of Sale Value
	is not specified in	ad-valorem basis	or of Average
	schedule-II) Entire State		Selling Price on ad-
			valorem basis
			which is higher.

As per order of Deputy Director mines and Geological department dated 11-11-2021. The prevailing rates as per the updated order of the Geological Department during the course of the project will be applicable.

Note: Except where otherwise stated, the contractor shall pay to the authority all tonnage and other royalties, rent and other payments or compensation if any, for getting stone, sand, gravel, clay or other materials by him and his subordinates and his subcontractors and required for the works, at the rates and such conditions as notified by the State Government. The contractor should submit the Mineral Dispatch Permit (MDP) in original for the quantity executed by the contractor for the requisite quantity of material incorporated in works for which MDP is issued by the authorized supplier. If contractor fails to submit the MDP in original the amount will be deducted at 5 times the royalty charges from the contractor's bills as per prevailing orders issued by the Authority.

SECTION VII

SCHEDULE - B

MINIMUM RATES OF WAGES

ABSTRACT OF MINIMUM RATES OF WAGES FROM RELEVANT NOTIFICATIONS

MINIMUM RATES OF WAGES APPLICABLE IN THE BEAT OF ALC(C), MANGALORE WITH EFFECT FROM **01.04.2023**

Minimum Wages applicable "Construction or maintenance of roads, runways or in building operations including laying down underground electric, wireless, radio, television, telephone and overseas communication cables and similar other underground cabling work, electric lines, water supply lines and sewerage pipelines"-

Category			
	Area: A	Area:B	Area:C
Unskilled	736.00	616.00	494.00
Semiskilled/	816.00	695.00	577.00
Unskilled Supervisory			
Skilled/Clerical	897.00	816.00	695.00
Highly Skilled	973.00	897.00	816.00

(Kindly Note: Area A: Bangalore (UA), Area B: Mangalore (UA), Mysore (UA), Belgaum (UA), Hubli-Dharwar, Area C: All other places in Karnataka not specified above as per Ministry of Labour and Employment F.No.1/5 (3)/2023-LS-II dated 03.04.2023.)

"Employment of Sweeping and Cleaning excluding activities prohibited under the Employment of Manual Scavengers and Construction of Dry latrines (Prohibition) Act, 1933".

Area	Rates of wages Rs.
'A'	736.00
'B'	616.00
'C'	494.00

"Employment of Watch and Ward"-Rates of wages for employees employed in watch and ward – Govt. of India, Ministry of Labour

	Without arms	With arms
Area	Rates of wages Rs.	Rates of wages Rs.
'A'	897.00	973.00
'B'	816.00	897.00
'C'	695.00	816.00

For further details log on to Ministry of Employment