

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/321/CIVIL/Mtc-I/2023-TS dated 16.10.2023

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;
Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: एनएमपीए में टेनिस क्ले कोर्ट की मरम्मत
Name of work	: Repairs to the Tennis clay Court at NMPA
अनुमानित लागत /Estimated Cost	: Rs.89,389.03
ईएमडी /EMD	: Rs.2,110.00
खुलने की तिथि /Date of opening	: 23.10.2023
समापन अवधि /Completion Period	: 30 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **23.10.2023** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.


कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
खरखाव प्रभाग-I / Maintenance Division-I,

नव मंगलोर पत्तन प्राधिकरण / **NEW MANGALORE PORT AUTHORITY**
सिविल इंजीनरिंग विभाग / **DEPARTMENT OF CIVIL ENGINEERING**
अनुरक्षण प्रभाग -I / **MAINTENANCE DIVISION-I**
कोटेशन/QUOTATION No.5/321 /CIVIL/Mtc-I/2023-TS dated 16.10.2023

BILL OF QUANTITIES

कार्य का नाम: एनएमपीए में टेनिस क्ले कोर्ट की मरम्मत					
Name of work: Repairs to the Tennis clay Court at NMPA					
SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Clearing Grass and Removal of Rubbish & dumping to outside periphery by manual means	1120.00	Sqm	2.85	3,192.00
2	Hacking the entire tennis court area manually for an average depth of 30 mm, removing all the dirt, roots , grass etc, Supplying red murrum, seiving the red murrum, spreading on the surface of the court for an average thickness of 75mm, watering the entire area, compacting to the desired density manually using wooden rammer repeatedly to give an even surface, re-compacting to prevent any development of cracks on the surface, neatly marking the court with the dimennsions, the marking lines shall be of the exact thickness as per the International standards, painting the court over 2 coats of black Japan paint, including cost of labour, materials, transport, T&P, etc. all complete as directed by the Engineer-in-charge..	710.00	Sqm	107.96	76,652.15
3	Removing the existing cover slabs carefully without damaging the slabs, cleaning the drain, dumping the removed material to the designated dumping area, refixing the cover slab, including cost of labour, materials, transport, T&P, etc. all complete as directed by the Engineer-in-charge.	100.00	Rm	95.45	9,544.88
Amount put to quotation (excluding GST) Rs. :					89,389.03
ADD: % ()					
Above the estimate amount put to quotation.				Rs.	
LESS: % ()					
Below the estimate amount put to quotation				Rs.	
Total Amount Rs.					
Rupees :					

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR