

नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY  
सिविल इंजिनरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING  
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I  
कोटेशन / QUOTATION No.2/443/CIVIL/Mtc-I/2023-TS dated 19.03.2024

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;  
Sealed quotations are invited on percentage rate basis from the reputed and experienced Railway contractors for the following work;

कार्य का नाम;	: एओबी, एनएमपीए प्रशासनिक भवन में विजिलेंस के दक्षिणी तरफ प्रदान की गई छत का विस्तार
Name of work	: Extension of roofing provided on the southern side of Vigilance in AOB, NMPA Administrative building
अनुमानित लागत / Estimated Cost	: Rs.52,857.90
ईएमडी / EMD	: Rs.1250.00
खुलने की तिथि / Date of opening	: 26.03.2024
समापन अवधि / Completion Period	: 45 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **26.03.2024** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

  
कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),  
रखरखाव प्रभाग-I / Maintenance Division-I,



**नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY**  
**सिविल इंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING**  
**अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I**  
**कोटेशन/QUOTATION No.2/443/CIVIL/Mtc-I/2023-TS dated 19.03.2024**

**BILL OF QUANTITIES**

कार्य का नाम: एओबी, एनएमपीए प्रशासनिक भवन में विजिलेंस के दक्षिणी तरफ प्रदान की गई छत का विस्तार					
Name of work: Extension of roofing provided on the southern side of Vigilance in AOB, NMPA Administrative building					
SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Carefully dismantling the old AC sheet roof and masonry provided above the slab of the toilet of CVO's chamber, conveying and dumping the dismantled materials at the location shown by the department including cost of labour, T&P, transportation and all other incidental charges etc. complete for successful completion of the job.	1.00	L.S	2780.70	2,780.70
2	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvalume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses.	20.00	Sqm	688.00	13,760.00
3	Providing and installing of approved make pre painted Galvalume iron Accessories, like, plain, ridges, plain gutter, plain flashing, corner Trim, etc. The total coated thickness (TCT) of the sheet shall be 0.47 mm +/- 0.02 tolerance mm Zinc-Alu Alloy coating AZ 150 gsm as per ASTM 1397/755 -550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling / self tapping screws of 25 mm length. (width upto 500-600 mm only), to be fixed over the existing purlins, rafters, channels and trusses.	11.00	Sqm	660.00	7,260.00

4	Providing and Fabricating of GI pipe 'B' class dia pipe verticle support of 100mm pipe as per the Department drawing, cutting , welding , gusset plates, bolts & nuts , applying 2 coats of painting of metal enemal paint over a coat of primer & conveyance of all materials , transportation to work site , cost of all labours, all tools , lead & lift, bolts & nuts , plates & errection , fixing charges etc complete as per specification	2.00	Rm	1087.26	2,174.52
5	Providing and Fabricating of GI pipe 'B' class dia pipe rafters of 65mm pipe support as per the Department drawing, cutting , welding , gusset plates, bolts & nuts , applying 2 coats of painting of metal enemal paint over a coat of primer & conveyance of all materials , transportation to work site , cost of all labours, all tools , lead & lift, bolts & nuts , plates & errection , fixing charges etc complete as per specification	10.00	Rm	639.58	6,395.80
6	Providing and Fabricating of GI pipe 'B' class dia pipe rafters of 50mm pipe double stiched support as per the Department drawing, cutting , welding , gusset plates, bolts & nuts , applying 2 coats of painting of metal enemal paint over a coat of primer & conveyance of all materials , transportation to work site , cost of all labours, all tools , lead & lift, bolts & nuts , plates & errection , fixing charges etc complete as per specification	8.00	Rm	422.11	3,376.88
7	Providing and fixing Steel work in built up in MS plates, tubular, round, square or rectangular flats or hollow tubes etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge	100.00	Kgs	109.00	10,900.00
8	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 m <sup>2</sup> and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge. (For Roof and Water Tanks).	15.00	Sqm.	414.00	6,210.00



Amount put to quotation (excluding GST) Rs. :	52,857.90
ADD:             % (                     ) Above the estimate amount put to quotation. Rs.	
LESS:            % (                     ) Below the estimate amount put to quotation. Rs.	
Total Amount Rs.	
Rupees :	

Note: GST will be reimbursed as applicable

**SIGNATURE OF THE CONTRACTOR**