

नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY  
सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING  
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

**कोटेशन / QUOTATION No.5/342/CIVIL/Mtc-I/2023-TS dated 29.04.2024**

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;

Sealed quotations are re-invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम; Name of work	: एनएमपीए कॉलोनी में 20वें एवेन्यू में सुरक्षा परिसर की दीवार का निर्माण : Raising of Security Compound wall at 20th Avenue at NMPA Colony
अनुमानित लागत / Estimated Cost	: Rs.1,63,432/-
ईएमडी / EMD	: Rs.3,860.00
खुलने की तिथि / Date of opening	: 06.05.2024
समापन अवधि / Completion Period	: 45 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **06.05.2024** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorised representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

  
कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),  
खरखाव प्रभाग-I / Maintenance Division-I,

नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY

सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING

अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन/QUOTATION No.5/342 /CIVIL/Mtc-I/2023-TS dated 29.04.2024

**BILL OF QUANTITIES**

कार्य का नाम: एनएमपीए कॉलोनी में 20वें एवेन्यू में सुरक्षा परिसर की दीवार का निर्माण					
Name of work: Raising of Security Compound wall at 20th Avenue at NMPA Colony					
SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. In all kinds of soils upto 300 mm depth.	50.00	M3	65.00	3,250.00
2	Demolishing cement concrete manually/mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge	2.50	M3	1274.00	3,185.00
3	Providing Coursed rubble masonry (second sort) with hard stone in super structure with Cement mortar 1:6 (1 cement : 6 coarse sand)	27.00	M3	5266.00	1,42,182.00
4	Providing and laying in position plain cement concrete for Damp proof course for all works . The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	2.50	M3	5926.00	14,815.00
Amount put to quotation (excluding GST) Rs. :					<b>1,63,432.00</b>
ADD: % ( ) Above the estimate amount put to quotation.				Rs.	
LESS: % ( ) Below the estimate amount put to quotation				Rs.	
Total Amount Rs.					
Rupees					