



नव मंगलूर पत्तन प्राधिकरण
NEW MANGALORE PORT AUTHORITY
यांत्रिक अभियंता विभाग
Mechanical Engineering Department
इलेक्ट्रिकल इंजिनियरिंग डिविजन, पणंबूर, मंगलूर
Electrical Engineering Division
Panambur, Mangalore – 575010

E-mail: praveenkumark.k@nmpt.gov.in

Phone: 0824 2887736/756

GSTIN: 29AAALN0057A2ZG

No.8/9/ESD-I/AC/2024

Date: 06-05-2024

REQUEST FOR BUDGETARY OFFER

Sir,

Sub: “Supply, Installation, Testing and Commissioning of Wall mounted Split Air conditioner units to the PS to Chairman and Deputy Conservator Chamber at Administrative Building, NMPA”.

Budgetary Offer in sealed covers prescribed as **“Supply, Installation, Testing and Commissioning of Wall mounted Split Air conditioner units to the PS to Chairman and Deputy Conservator Chamber at Administrative Building, NMPA”** at NMPA may please be submitted addressed to **“The Executive Engineer (Ele), Electrical Division, New Mangalore Port Authority, Panambur, Mangalore- 575010”** not later than **3.00 PM on or before 13-05-2024.**

Sl. No	Description	Qty.	Unit	Rate (Rs)	Amount (Rs)
	PART-1				
1	Supplying of 2 TR (2/3 Star) wall mounting, Non Inverter type Split Air Conditioner units suitable for operation on A/C supply single phase 50Hz 230V with EER Rotary Compressor with air cooled copper condenser, motor capacitor and start run capacitors, relay and over load protector internal unit, with one indoor and one anti corrosive outdoor unit including standard length of suitable size copper	03	No's		

	tubing covered with insulation tube, suitable capacity 3 core sheathed/PVC copper cable and a battery operated wireless remote unit etc., as a complete unit. REFRIGERANT: R32				
	Total				
	Applicable GST @ 28%				
	Grand Total				
	PART-II				
1	Supplying of 5KVA Electronic Voltage stabilizers for the 2 Ton Air Conditioner. Working Range: 170V -270V AC, 50Hz. Time Delay: 3Mts. ± 20 Secs. ITDS Capacity: 15 Amps.	03	No's		
2	Supplying and fixing of 3/4" heavy duty PVC drain pipe with required elbows/Tee/bend/saddles etc. as a complete job.	10	Mtrs		
3	Supplying and fixing of 3/8" Air Conditioner copper pipe.	10	Mtrs		
4	Supplying and fixing of 5/8" Air Conditioner copper pipe.	10	Mtrs		
5	Supplying and drawing flexible Multicore cable manufactured with electrolytic grade flexible copper with low conductor confirming to IS 8130-1984 and PVC insulation sheathed suitable for working voltage up to 1100V as per IS:694:2010. a) 3C X 4 Sq.mm.	10	Mtrs		
6	Supply and fixing of Metal socket set of 2 pole and earth plugs and socket for incorporating SP MCB (without MCB).The entire plug and socket shall be mounted in a thermoplastic/power coated metal box and wired completely. a) 25 Amps SP & N	3	No's		

7	Supplying and fixing miniature circuit breakers on existing MCB distribution board using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. a) 25 Amps DP	3	No's		
8	Supplying and fixing of DP 2way enclosure Metal box flush mounting using with provision for fixing suitable type Capacity MCB's DP with power coated painting.	3	No's		
9	Supplying and fixing of Outdoor Air Conditioner's Mounting bracket stand with required items as a complete job.	1	Set		
10	Supplying and fixing of Outdoor Air Conditioner's Heavy duty Floor Mounting stand with required items as a complete job.	2	Sets		
11	Core Cutting.	1	No.		
12	Installation, testing & commissioning of New Split Air Conditioner Units using required hardware and supply of required items as a complete job.	3	Sets		
	Total				
	Applicable GST @ 18%				
	Grand Total				
	Total (PART I+PART II)				
	Applicable GST (PART I+ PART II)				
	Grand Total (including GST)				

TERMS & CONDITIONS:

1. The rate quoted for the items shall be firm and exclusive of applicable Taxes and F.O.R destination basis.
2. Applicable GST will be paid as per actual.

3. The supplied AC units and Stabilizers should have Guarantee /warranty as per the manufacturer leaflet.
4. The carried out work shall have one year Guarantee from the date of handing over after satisfactory completion of work.
5. The Tenderers should quote their rates in figures as well as in words the amount tendered by them. The amount per each item should be worked out and requisite total should be given. All rates shall be quoted in proper form in the tender schedule enclosed. **The rates quoted should be valid for 90 days.**
6. The Tenderer shall have experience in Supply and Installation of Air conditioner Units. Documentary evidence/supporting documents such as Work order/Work Completion Certificate shall be submitted along with the offer without which the offer will not be considered for evaluation and liable for rejection.
7. **The Tenderer may visit the work site and get acquainted himself with the site conditions, nature of work involved before tendering.** Any assistance, in this regard will be provided by the department under prior appointment and the undersigned may be contacted for the purpose.
8. The Tenderer shall be responsible for making good of all the damages done during the work and has to employ skilled & competent workers for carrying out the work.
9. The Tenderer shall be responsible for taking precautionary measures for the safety of the workmen working under him and the responsibility arising due to any mishap during the execution of work, payment of any compensation etc., lies entirely on the part of the Contractor. Safety Items required while working are to be provided by the Contractor.
10. No tools, plant, Labour, equipment, transport, etc., required for the work will be supplied departmentally and contractor has to make his own arrangements.

Sd/-
Executive Engineer (E)
Electrical Division, NMPA