



भारत 2023 INDIA
ONE EARTH - ONE FAMILY - ONE FUTURE



Mechanical Engineering Department
Electrical Division, Administrative
Building, Panambur,
Mangalore-575010, Karnataka
Phone- 0824-2887749.

नव मंगलूर पत्तन प्राधिकरण
New Mangalore Port Authority
पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार
Ministry of Ports, Shipping & Waterways, Govt. of India

यांत्रिक अभियांत्रिकी विभाग,
विद्युत प्रभाग, प्रशासनिक भवन
पनम्बूर, मंगलूर - ५७५ ०१०, कर्नाटक
दूरभाष : 0824-2887749

सं./No. NMPA/EE(E)/Maintenance/2024/0770

दिनांक/Date: 29.07.2024

To,

Prospective bidders

Sir,

Sub: - NMPA-EE (E) - "Providing illumination to the Panambur Junction" -
Quotation invited - Reg.

Quotation in sealed covers superscribed as "Providing illumination to the Panambur Junction" invited in accordance with the instructions to the Tender Terms & Conditions as detailed below. The quotation may please be submitted addressed to "**The Executive Engineer (Elec.), Electrical Division, Administration Building, New Mangalore Port Authority, Panambur, Mangalore- 575010**" not later than **3.00 PM on or before 06.08.2024**. Quotation will be opened on the same day at 3.30 PM in the presence of the tenderers who wish to be present.

Sl. No.	Description of Items	Qty / Unit	Rate (in ₹)	Rate in Words	Amount (in ₹)
1.	Supply of 150 watt LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti-glare clear diffuser with Injection moulded polycarbonate/clear glass material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over	10 Nos.			

	voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mauling with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100 V to 270V 50/60Hz application. Compliance to IS 10322/ IEC 60598, LM 79 & LM 80 Adherence with RoHS. Power consumption. LED Efficiency> 130lm/w, nominal CRI >75. Technical Specification as per the Karnataka PWD SR.				
2.	Supplying of hot dip Galvanized M.S. circular bracket of suitable ID as per site requirement, fabricated with 40mm dia pipe, head frame & supports, mounting plates suitable for mounting 5 Nos. outdoor LED flood light luminaries on 11 mtr Octagonal pole using necessary bolts, nuts etc. complete	2 Nos.			
3.	Fixing of LED flood lights to the brackets, removing the existing double arm brackets from the existing 11 mtr height poles at Panambur Junction and fixing the new brackets to the poles complete in all respects	1 JOB			
Total (excluding GST)					

(Rupeesonly)

Terms & Conditions:

1. The rate quoted for the items shall be firm and F.O.R destination basis. Please note that NMPA is not issuing any concessional **C or D forms**.
2. Applicable GST will be paid as extra as per actual.
3. The time allowed to complete the work is **10 days** from the date of issue of work order.
4. **The Sky lift will be arranged by NMPA for the subject work at free of cost.**
5. Please note that no advance payment will be made. But payment will be made within 15 days after receipt of batteries in good condition.

6. The Tenderers should quote their rates in figures as well as in words the amount tendered by them. The amount per each item should be worked out and requisite total should be given. All rates shall be quoted in proper form in the tender schedule enclosed. The rates quoted should be valid for **90 days**.
7. The Items to be supplied should conform to the specifications and standards of IS & **warranty period of 12 months from the date of completion of work**.
8. The acceptance of the tender will rest with competent authority of NMPA who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all of the tenders received without assigning any reason.
9. The evaluation shall be done on the basis of total lowest value (L1) quoted. The GST element if any will not be considered for evaluation.
10. No tools, plant, labour, equipment, transport, etc. required for the work will be supplied by the Department except sky lift and the Contractor has to make his own arrangements.
11. The Contractor shall be responsible for making good of all the damages done during the work and has to employ skilled & competent workers for carrying out the work.
12. The Contractor shall be responsible for taking precautionary measures for the safety of the workmen working under him and the responsibility arising due to any mishap during the execution of work, payment of any compensation etc., lies entirely on the part of the Contractor. Safety Items required while working are to be provided by the Contractor.
13. **LIQUIDATED DAMAGES:**

In case of delay in completion of the contract, liquidated damages (L.D) may be levied at the rate of 0.5% of the contract price plus applicable GST per week of delay, or part thereof subject to a maximum of 10 per cent of the contract price.
14. If the Tenderer after award of work/contract fail to execute the work in the specified allotted period, then the Tenderer may be debarred for a period of three (3) years from participating for tenders at New Mangalore Port Authority.

Sd/-
Executive Engineer (E)
Electrical Division, NMPA

Seal and sign of Tenderer