

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/370/CIVIL/Mtc-I/2024-TS dated 14.10.2024

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: एनएमपीए कॉलोनी में गेट नंबर 22, 2 एवेन्यू में ढही परिसर की दीवार की मरम्मत
Name of work .	: Repairs to the collapsed compound wall at door no.22, 2nd Avenue in the NMPA colony
अनुमानित लागत / Estimated Cost	: Rs.1,57,658.50
ईएमडी / EMD	: Rs.3,725.00
खुलने की तिथि / Date of opening	: 21.10.2024
समापन अवधि / Completion Period	: 60 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **21.10.2024** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan .The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.



कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
रखरखाव प्रभाग-I / Maintenance Division-I,

नव मंगलोर पत्तन प्राधिकरण / **NEW MANGALORE PORT AUTHORITY**
सिविल इंजिनीरिंग विभाग / **DEPARTMENT OF CIVIL ENGINEERING**
अनुरक्षण प्रभाग -I / **MAINTENANCE DIVISION-I**
कोटेशन/QUOTATION No.5/370/CIVIL/Mtc-I/2024-TS dated 14.10.2024

BILL OF QUANTITIES

कार्य का नाम: एनएमपीए कॉलोनी में गेट नंबर 22, 2 एवेन्यू में ढही परिसर की दीवार की मरम्मत Name of work: Repairs to the collapsed compound wall at door no.22, 2nd Avenue in the NMPA colony					
SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	29.00	CuM	242.00	7,018.00
2	Providing and laying in position Cement Concrete for all Foundation works.The granite /trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes,labour, Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. -M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	1.50	CuM	6217.00	9,325.50
3	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	17.50	CuM	6389.00	1,11,807.50
4	Providing and constructing laterite size stone masonry including cost and conveyance of all materials curing etc complete as per specification I.S. 3620/1979 having compressive strength not less than 3.5 N/mm ² for saturated dry samples - For Super structure in CM	3.50	CuM	6755.00	23,642.50

	1:6				
5	Providing Flush/ Ruled pointing: Pointing on stone work with cement mortar 1:3 (1 cement: 3 fine sand) after raking joints to depth nicely lining, including cost of materials, labour, curing as per specifications and as per directions of Engineer-in-charge.	23.00	CuM	255.00	5,865.00
Amount put to quotation (excluding GST) Rs. :					1,57,658.50
ADD: % () Above the estimate amount put to quotation. Rs.					
LESS: % () Below the estimate amount put to quotation Rs.					
Total Amount Rs.					
Rupees :					

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR