

## नव मगंलुर पत्तन प्राधिकरण

## **NEW MANGALORE PORT AUTHORITY**

यांत्रिक अभियंता विभाग

## Mechanical Engineering Department इलेक्ट्रिकल इंजिनियरिंग डिविजन, पणंबूर, मंगलूर

Electrical Engineering Division
Panambur, Mangalore – 575010

E-mail: <u>ele-section@nmpt.gov.in</u> GSTIN: 29AAALN0057A2ZG Phone: 0824 2887750/740/738 Fax: 0824 2408200/2408300

No. 8/3/2025/Ele. Dvn/CISF-Solar

Date: 07.01.2025

To,

Sir,

Sub: -NMPA-EE (E) - "Removing & Re-fixing of 50KW Solar system on Galvalume sheet roofing at CISF barrack" - **Budgetary Offer requested**- Reg.

Budgetary offer for the work of "Removing & Re-fixing of 50KW Solar system on Galvalume sheet roofing at CISF barrack" invited in accordance with the instructions to the Tendered Terms & Conditions as detailed below, may please be submitted addressed to "The Executive Engineer (Elec.), Electrical Division, Administration Building, New Mangalore Port Authority, Panambur, Mangalore- 575010" not later than 3.00 PM on or before 14.01.2025.

| SL  | Description of work   | Qty      | Rate | Rate in | Amount |
|-----|---|----------|------|---------|--------|
| No. |   |          | Rs.  | words   | Rs.    |
| 1   | Supply of Aluminium rooftop structure<br>materials including mounting railing,<br>Middle & End clamp, self drill screws,<br>Aluminium structure jointer and fixing<br>materials etc. complete | 350 Mtrs |      |         |        |
| 2   | Supply of MC4 connectors & fixing   | 60 Nos.  |      |         |        |
| 3   | Supply of DC cable of size: 6 Sq.mm, single core (Black)  | 600 Mtrs |      |         |        |
| 4   | Supply of Earth cable -6 Sq.mm (Green)  | 90 Mtrs  |      |         |        |
| 5   | Supplying of UPVC pipe of 2" dia including bend, joints etc. with clamps wherever required  | 100 Mtrs |      | ,       |        |
| 6   | Supplying of UPVC pipe of 1"dia including bend, joints etc. with clamps wherever required.  | 80 Mtrs  |      |         |        |
| 7   | Labour charges for removing and shifting, storing of existing 50KW Solar Panels and mounting structure etc. complete.   | 1 Job    |      |         |        |
| 8   | Installation of Aluminium roof structure<br>and fixing of solar panels, testing, laying<br>/fixing of UPVC pipes, cables etc.<br>complete   | 1 Job    |      |         |        |

| 9 | Labour charges for making of Walkway by using existing GI structure materials | 1 Job |   |  |
|---|---|-------|---|--|
|   | - Total   |       | 8 |  |
|   | Applicable GST  |       |   |  |
|   | Grand Total   |       |   |  |

## **TERMS & CONDITIONS:**

- 1. The rate quoted for the items shall be firm and F.O.R destination basis. Please note that NMPA is not issuing any concessional C or D forms.
- 2. Applicable GST will be paid extra as per actual.
- 3. The time allowed to complete the entire work is 60 days from the date of issue of work order.
- 4. Please note that no advance payment will be made. But full payment will be made within 15 days after satisfactory completion of work & against submission of bill.
- 5. The rates quoted shall be valid for **90days.**
- 6. No tools, plant, labour, transport ,safety equipments etc. required for the work will be supplied departmentally and the firm has to be make their own arrangements.

Executive Engineer (E) Electrical Division, NMPA

Seal and sign of Tenderer