



नव मंगलूर पत्तन प्राधिकरण
NEW MANGALORE PORT AUTHORITY
यांत्रिक अभियंता विभाग
Mechanical Engineering Department
इलेक्ट्रिकल इंजिनियरिंग डिविजन, पणंबूर, मंगलूर
Electrical Engineering Division
Panambur, Mangalore - 575010

E-mail: ele-section@nmpt.gov.in
GSTIN: 29AAALN0057A2ZG

Phone: 0824 2887750/740/738
Fax: 0824 2408200/2408300

No. 8/3/2025/Ele. Dvn/ETS.II/04/01

Date: 23.04.2025

To,

Sir,

Sub: -NMPA-EE (E) - "Electrification for Air Conditioner Units at Second Floor of Administrative Building, NMPA" - Quotation invited - Reg.

Quotation in sealed covers superscribed as **"Electrification for Air Conditioner Units at Second Floor of Administrative Building, NMPA"** invited in accordance with the instructions to the Tendered Terms & Conditions as detailed below, may please be submitted addressed to **"The Executive Engineer (Elec.), Electrical Division, Administration Building, New Mangalore Port Authority, Panambur, Mangalore-575010"** not later than **3.00 PM on or before 30.04.2025**. Quotation will be opened on the same day at 3.30 PM in the presence of the tenderers who wish to be present.


Sl. No.	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Laying for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:2010 a) 6 sq.mm	600	Mtrs		
2	Laying for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:2010 a) 2.5 sq.mm	700	Mtrs		
3	Supplying and fixing of PVC casing and capping on the wall or ceiling using necessary material like bends, junction box, elbows, and screws at an interval of 300mm as required. a) 25mm	100	Mtrs		

4	Supplying and fixing of 5KVA Electronic Voltage stabilizers for the 2 Ton Air Conditioner. Working Range: 170V -270V AC, 50Hz. Time Delay: 3Min. ± 20Secs. ITDS Capacity: 15 Amps.	6	Nos.		
5	Supplying and fixing of 4KVA Electronic Voltage stabilizers for the 1.5 Ton Air Conditioner. Working Range: 170V -270V AC, 50Hz. Time Delay: 3Min. ± 20Secs. ITDS Capacity: 15 Amps.	11	Nos.		
6	Supplying 3/4" heavy duty PVC drain pipe with required elbows/Tee/bend/ saddles etc. as a complete job.	20	Mtrs		
7	Supplying of 5/8" Air Conditioner copper pipe with nitrile rubber insulation.	10	Mtrs		
8	Supplying of 3/8" Air Conditioner copper pipe with nitrile rubber insulation.	10	Mtrs		
9	Supplying of flexible Multicore cable manufactured with electrolytic grade flexible copper with low conductor confirming to IS 8130-1984 and PVC insulation sheathed suitable for working voltage up to 1100V as per IS:694:2010 a) 4C x 2.5 Sq.mm.	20	Mtrs		
10	Supply and fixing of 25A Metal socket set of 2 pole earth plug and socket. The entire plug and socket shall be mounted in a thermoplastic/power coated metal box and wired completely.	17	Nos.		
11	Supplying and fixing of DP 2way enclosure box flush mounting using with provision for fixing suitable type Capacity MCB's DP with power coated painting.	17	Nos.		
12	Core Cutting (Wall width-1.5 feet)	15	Nos.		
13	Supplying and fixing of Outdoor Air Conditioner's MS Wall mounting brackets with required items as a complete job.	17	Nos.		
	Total				
	Applicable GST @18%				
	Grand Total				

TERMS & CONDITIONS:

1. The rate quoted for the items shall be firm and F.O.R destination basis. Please note that NMPA is not issuing any concessional C or D forms.
2. The Tenderer shall submit Valid Electrical Contractor License and GST Registration Certificate along with their offer, without which the offer is liable for rejection.
3. Applicable GST will be paid as extra as per actual.

4. The time allowed for completion of work is **30 days** from the date of issue of work order.
5. The carried out work shall have one year Guarantee from the date of handing over after satisfactory completion of work.
6. Please note that no advance payment will be made. But payment will be made within 15 days after satisfactory completion of Work.
7. Offer shall be submitted in NMPA format only along with Terms & Conditions of Enquiry. Offer submitted in other format will not be considered for evaluation and liable for rejection.
8. The Tenderers should quote their rates in figures as well as in words the amount tendered by them. The amount per each item should be worked out and requisite total should be given. All rates shall be quoted in proper form in the tender schedule enclosed. The rates quoted should be valid for **90 days**.
9. The Tenderer shall be responsible for making good of all the damages done during the work and has to employ skilled & competent workers for carrying out the work.
10. The Tenderer shall be responsible for taking precautionary measures for the safety of the workman working under them and the responsibility arising due to any mishap during the execution of work, the payment of any compensation etc., lies entirely on the part of the Contractor.
11. No tools, plant, Labour, equipment, transport, etc., required for the work will be supplied departmentally and contractor has to make his own arrangements.
12. The evaluation shall be done on the basis of total lowest value (L1) quoted. The GST element if any will not be considered for evaluation.
13. The acceptance of the tender will rest with competent authority of NMPA who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all of the tenders received without assigning any reason.
14. LIQUIDATED DAMAGES:
 - i. In case of delay in completion of the contract, liquidated damages (L.D) may be levied at the rate of 0.5% of the contract price plus applicable GST per week of delay, or part thereof subject to a maximum of 10 per cent of the contract price.
15. Department standard operating procedure will be shared with the successful bidder before commencing the work and an undertaking will be obtained for complying with the same. In case if the Contractor does have a defined SOP for carrying out the work, the same shall be scrutinized and approved by the Executive Engineer (E)-I for its applicability.
16. If the Tenderer after award of work/contract fail to execute the work in the specified allotted period, then the Tenderer shall be debarred for a period of two (2) years from participating for tenders at New Mangalore Port Authority.


Executive Engineer (E)
Electrical Division, NMPA

Seal and sign of Tenderer