

नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल एंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING

अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/397/CIVIL/Mtc-I/2025-TS dated 05.05.2025

निम्नलिखित कार्य के लिए प्रतियुक्त एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;
Sealed quotations are re-invited on percentage rate basis from the reputed and experienced contractors for the following work;

| | |
|---------------------------------|--|
| कार्य का नाम; | : एनएमपीए के बिजनेस डेवलपमेंट सेंटर की उत्तरी दीवार पर इकट ओपनिंग में एल्युमिनियम कम्पोजिट पैनल उपलब्ध कराना और लगाना |
| Name of work | : Providing and fixing aluminium composite panel to the duct openings on northern wall Business Development Centre, NMPA |
| अनुमानित लागत / Estimated Cost | : Rs.1,99,701.00 |
| ईएमडी /EMD | : Rs.4,715.00 |
| खुलने की तिथि /Date of opening | : 09.05.2025 |
| समाप्त अवधि / Completion Period | : 30 days |

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **09.05.2025** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.

The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

- NMPA Bank Details for remittance of Tender fee and EMD.
1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
 2. Bank A/C No. 10205649448
 3. IFSC Code: SBIN0002249
 4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool, and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

Sd/-

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
रखरखाव प्रभाग-I / Maintenance Division-I,

Date: 09.05.2025

The above subject work will be extend upto **12.05.2025** and submission on or before 3.00P.M on **12.05.2025**

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
रखरखाव प्रभाग-I / Maintenance Division-I,

नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल एंगिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I
कोटेशन/QUOTATION No.5/397/CIVIL/Mtc-I/2025-TS dated 05.05.2025

BILL OF QUANTITIES

कार्य का नाम: एनएमपीए के बिजनेस डेवलपमेंट सेंटर की उत्तरी दीवार पर इक्ट ओपनिंग में एल्युमिनियम कम्पोजिट पैनल उपलब्ध कराना और लगाना

Name of work: Providing and fixing aluminium composite panel to the duct openings on northern wall Business Development Centre, NMPPA

| SI No | Description of items | Qty | Unit | Rate in Figures | Amount Rs. Ps. |
|--|--|-------|------|-----------------|--------------------|
| 1 | Providing and fixing of Aluminium composite panel of approved make and colour for wall cladding for Brick/Rcc/stone walls & columns/beams with necessary aluminium frame works at required level made out of 50x25x4mm C section or equivalent. The panel should consist of 3mm thick non-halogenated FR grade mineral based polymer (2 hrs fire resistance as per ASTM E119-12 and clause B, S1, do as per ENT13501-1sandwiched between 0.50 skins thick aluminium sheet making a total panel thickness of 4mm. The surfaces will be finished with PVDF based coating on topsides and service coating on reverse sides would be in polyester paint. The system shall be fixed using GI brackets, aluminium L cleats and stainless steel bolts and nuts complete with spring washer and cap nuts and all other necessary road etc. complete. For Straight Portion | 49.00 | Sqm | 3989.00 | 1,95,461.00 |
| 2 | Providing, erecting and removing of MS scaffolding set with cross bracings on the sides, for 30 days including cost of transportation, loading, unloading, labour, fitting etc all complete. | 16.00 | Set | 265.00 | 4,240.00 |
| Amount put to quotation (excluding GST) Rs. : | | | | | 1,99,701.00 |
| ADD: % (Above the estimate amount put to quotation. Rs. | | | | | |
| LESS: % (Below the estimate amount put to quotation Rs. | | | | | |
| Rupees : Total Amount Rs. | | | | | |

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR