

**नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY**  
**सिविल एंगिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING**  
**अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I**  
**कोटेशन / QUOTATION No.5/397/CIVIL/Mtc-I/2025-TS dated 05.05.2025**

निम्नलिखित कार्य के लिए प्रतिलिखित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुराबदा कोटेशन आमंत्रित किए जाते हैं:  
Sealed quotations are re-invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: एनएमपीए के बिजनेस डेवलपमेंट सेंटर की उत्तरी दीवार पर डक्ट ओपनिंग में एल्युमिनियम कम्पोजिट पैनल उपलब्ध कराना और लगाना
Name of work	: Providing and fixing aluminium composite panel to the duct openings on northern wall Business Development Centre, NMPA
अनुमानित लागत / Estimated Cost	: Rs.1,99,701.00
ईएमडी /EMD	: Rs.4,715.00
खुलने की तिथि /Date of opening	: 09.05.2025
समापन अवधि / Completion Period	: 30 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **09.05.2025** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.

The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

- NMPA Bank Details for remittance of Tender fee and EMD.
1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
  2. Bank A/C No. 10205649448
  3. IFSC Code: SBIN0002249
  4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),  
रखरखाव प्रभाग-I / Maintenance Division-I,



**नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY**  
**सिविल इंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING**  
**अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I**  
**कोटेशन/QUOTATION No.5/397/CIVIL/Mtc-I/2025-TS dated 05.05.2025**

**BILL OF QUANTITIES**

**कार्य का नाम:** एनएमपीए के बिजनेस डेवलपमेंट सेंटर की उत्तरी दीवार पर इकट ओपनिंग में एल्युमिनियम कम्पोजिट पैनाल उपलब्ध कराना और लगाना

**Name of work:** Providing and fixing aluminium composite panel to the duct openings on northern wall Business Development Centre, NMPA

SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Providing and fixing of Aluminium composite panel of approved make and colour for wall cladding for Brick/Rcc/stone walls & columns/beams with necessary aluminium frame works at required level made out of 50x25x4mm C section or equivalent. The panel should consist of 3mm thick non-halogenated FR grade mineral based polymer ( 2 hrs fire resistance as per ASTM E119-12 and clause B, S1, do as per ENT13501-1sandwiched between 0.50 skins thick aluminium sheet making a total panel thickness of 4mm. The surfaces will be finished with PVDF based coating on topsides and service coating on reverse sideswould be in polyester paint. The system shall be fixed using GI brackets, aluminium L cleats and stainless steel bolts and nuts complete with spring washer and cap nuts and all other necessarys road etc. complete. For Straight Portion	49.00	Sqm	3989.00	1,95,461.00
2	Providing, erecting and removing of MS scaffolding set with cross bracings on the sides, for 30 days including cost of transportaion, loading, unloading, labour, fitting etc all complete.	16.00	Set	265.00	4,240.00
Amount put to quotation (excluding GST) Rs. :					<b>1,99,701.00</b>
ADD: % ( ) Above the estimate amount put to quotation. Rs.					
LESS: % ( ) Below the estimate amount put to quotation Rs.					
Rupees :					Total Amount Rs.

Note: GST will be reimbursed as applicable

**SIGNATURE OF THE CONTRACTOR**