

# नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY

## सिविल एंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING

### अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.3/265/CIVIL/Mtc-I/2025-TS dated 06.06.2025

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहुरबंद कोटेशन आमंत्रित किए जाते हैं;

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work:

कार्य का नाम;	: एनएमपीए में घाट क्षेत्र के अंदर पुरानी कैटीन के पास क्षतिग्रस्त स्प्रिंकलर पंप हाउस की मरम्मत और उन्नयन
Name of work	: Repair and upgrading the damaged sprinkler pump house near wharf old canteen inside wharf area at NMPA
अनुमानित लागत / Estimated Cost	: Rs.64,000.00
ईएमडी / EMD	: Rs.1,515.00
खलने की तिथि / Date of opening	: 13.06.2025
समापन अवधि / Completion Period	: 45 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **13.06.2025** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.

The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),  
रखरखाव प्रभाग-I / Maintenance Division-I,

*Shashikanth*



**नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY**  
**सिविल इंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING**  
**अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I**  
**कोटेशन/QUOTATION No.3/265/CIVIL/Mtc-1/2025-TS dated 06.06.2025**

**BILL OF QUANTITIES**

**कार्य का नाम :** एनएमपीए में घाट क्षेत्र के अंदर पुरानी कैटीन के पास क्षतिग्रस्त स्प्रिंकलर पंप हाउस की मरम्मत और उन्नयन  
**Name of work:** Repair and upgrading the damaged sprinkler pump house near wharf old canteen inside wharf area at NMPPA

SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Upgradation of Sprinkler pumphouse by increasing the height of all four walls of pumphouse upto 1.5mtr. Fabrication, supplying and erecting M.S. tubular trusses of all spans as per approved drawing & design with pre-fabricated steel applications using quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, etc., complete as per specification. Providing and Installing of pre Painted galvalume iron Trapezoidal profiled and sheet of approved make 1060 mm width (1000mm cover width )28-30 mm crest height with crest distance of 200mmc/c with 2ribs at the centre for stiffening the total coated thickness (TCT) of the sheet will be 0.47mm+/- 0.02mm tolerance Zinc Alu Alloy coating Az 150 gsm asper ASTM 1397/A755-550 mpa steel grade,5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling /self tapping screws of 25mm length, to be fixed over the existing Purlins , rafters, channels and trusses etc.,. The said job also includes the supply and fixing of	1.00	Job	64000.00	64,000.00

door frame and fibre door with plastering of walls, cement concrete flooring, painting etc., as according to the directions of the Engineer-in-charge.				
Amount put to quotation (excluding GST) Rs. :				<b>64,000.00</b>
ADD: % ( ) Above the estimate amount put to quotation. Rs.				
LESS: % ( ) Below the estimate amount put to quotation Rs.				
Total Amount Rs.				
Rupees :				

Note: GST will be reimbursed as applicable

**SIGNATURE OF THE CONTRACTOR**