

नव मेंगलोर पोर्टन प्राधिकरण / NEW MANGALORE PORT AUTHORITY  
सिविल इंजीनरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING  
अनुरक्षण प्रभाग - I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/280/CIVIL/Mtc-I/2022-1S dated 24.11.2022

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहुरबंद कोटेशन आमंत्रित किए जाते हैं:

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: एनएमपीए में अस्पताल भवन में कनरा बैंक के सामने गाय पकड़ने वाले की मरम्मत
Name of work	: Repairing the cow catcher in front of Canara bank in Hospital building at NMPA
अनुमानित लागत / Estimated Cost	: Rs.65,120.00
ईएमडी / EMD	: Rs.1,540.00
खुलने की तिथि / Date of opening	: 30.11.2022
समापन अवधि / Completion Period	: 30 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **30.11.2022** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorised representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

  
कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),  
खरखाव प्रभाग - I / Maintenance Division I,

नव मेंगलोर पत्तन प्राधिकरण / **NEW MANGALORE PORT AUTHORITY**  
सिविल इंजीनरिंग विभाग / **DEPARTMENT OF CIVIL ENGINEERING**  
अनुरक्षण प्रभाग -I / **MAINTENANCE DIVISION-I**  
कोटेशन/QUOTATION No.5/280 /CIVIL/Mtc-I/2022-TS dated 24.11.2022

**BILL OF QUANTITIES**

**कार्य का नाम:** एनएमपीए में अस्पताल भवन में केनरा बैंक के सामने गाय पकड़ने वाले की मरम्मत  
**Name of work:** Repairing the cow catcher in front of Canara bank in Hospital building at NMPA.

SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Providing and fixing <b>Steel work</b> in built up <b>tubular</b> (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Kg	570.00	109.00	62,130.00
2	Painting with <b>synthetic enamel paint</b> of approved brand and manufacture of required colour to give an even shade :Two coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	23.00	130.00	2,990.00
Amount put to quotation (excluding GST) Rs. :					<b>65,120.00</b>
<b>ADD:</b>	% ( )				
Above the estimate amount put to quotation.				<b>Rs.</b>	
<b>LESS:</b>	% ( )				
Below the estimate amount put to quotation				<b>Rs.</b>	
<b>Total Amount Rs.</b>					
Rupees					

Note: GST will be reimbursed as applicable

**SIGNATURE OF THE CONTRACTOR**