



नव मंगलूर पत्तन प्राधिकरण
NEW MANGALORE PORT AUTHORITY
यांत्रिक अभियंता विभाग
Mechanical Engineering Department
इलेक्ट्रिकल इंजिनियरिंग डिविजन, पणवूर, मंगलूर
Electrical Engineering Division
Panambur, Mangalore - 575010

E-mail: ele-section@nmpt.gov.in
GSTIN: 29AAALN0057A2ZG

Phone: 0824 2887750/740/738
Fax: 0824 2408200/2408300

No.8/3/2023/Ele. Dvn/EQ/01/04

Date: 17.01.2023

To,

Sir,

Sub: -NMPA-EE (E) - "Shifting of HT overhead line and RCC poles leading from Thannirbhavi road (near IOCL) to MK Agro Terminal outside Wharf area of NMPA" - Quotation invited - Reg.

Quotation in sealed covers superscribed as "Shifting of HT overhead line and RCC poles leading from Thannirbhavi road (near IOCL) to MK Agro Terminal outside Wharf area of NMPA" invited in accordance with the instructions to the Tendered Terms & Conditions as detailed below, may please be submitted addressed to "**The Executive Engineer (Elec.), Electrical Division, Administration Building, New Mangalore Port Authority, Panambur, Mangalore- 575010**" not later than **3.00 PM on or before 24.01.2023**. Quotation will be opened on the same day at 3.30 PM in the presence of the tenderers who wish to be present.

Sl. No	Description of Work	Qty	Rate (Rs.)	Rate in words	Amount (Rs.)
A	Part -I: Material Cost				
1	Supply of PSC Pole - 9.0 M Long 200KG WL	3 No.			
2	Supply of 11KV, Horizontal Cross Arm with HT Single Top supports, clamps, bolts, nuts & Washers for PSCC Pole, 200KG WL -GI	3 Set			
3	Supply of 11KV Pin Insulators (Both Shell and GI Pin) - Polymeric	9 Nos.			


4	Supply of Guy set with 2 Nos. 15 strain insulator & Concreting materials as per Drwg No. BESCOM/GM/CP /7/ Dt; 24.10.07-GI	3 Set			
B	Part -II: Erection Charges				
5	Digging of Pits 1.8 mtr dept for erection of 9 to 10 mtr Long Steel/RCC/PSC supports as per approved Drawings- Ordinary Soil (For Sl. No. 1)	3 No.			
6	Erection of PSC poles 9 to 10 mtr long but in a pit of 1.8 mtr depth - Ordinary Soil. (For Sl. No. 1)	3 No.			
7	Fixing of V-Shape/Horizontal cross arm including single top support Braces and insulators fixing - Ordinary Soil. (For Sl. No. 2)	3 Set			
8	Digging of Pit for GUY SET - Ordinary Soil. (For Sl. No. 4)	3 Set			
9	Fixing of GUY Sets with break insulators making use of 7/3.15mm (7/10 SWG) galvanized steel wire with turn buckle and anchoring arrangement as per approved drawing. (Excluding excavation of PIT) - Ordinary Soil. (For Sl. No. 4)	3 Set			
10	Releasing and Refixing - RCC Pole - 9.0M Long 145kg WL - Ordinary Soil.	4 Nos.			
11	Releasing and Refixing - DP Sets - MS - Ordinary Soil	2 Set			
12	Releasing and Refixing - Rabbit ACSR Conductor - Ordinary Soil	1.86 km			
13	Releasing and Refixing - 11KV 200Amps Single Break GOS - Ordinary Soil	2 Set			
14	Releasing and Refixing - PSC Pole - 9.0M Long 200kg WL - Ordinary Soil	16 Nos.			
15	Locality Allowance	per job			
16	Employee Cost	per job			
	Total				
	Applicable GST				
	Grand Total				

TERMS & CONDITIONS:

1. The rate quoted for the items shall be firm and F.O.R destination basis. Please note that NMPA is not issuing any concessional C or D forms.

2. The Tenderer shall submit Valid Electrical Contractor License (Class-I) and GST Registration Certificate along with their offer, without which the offer will be rejected.
3. Applicable GST will be paid as extra as per actual.
4. The time allowed for “Shifting of HT overhead line and RCC poles leading from Thannirbhavi road (near IOCL) to MK Agro Terminal outside Wharf area of NMPA” is **45 days** from the date of issue of work order.
5. Please note that no advance payment will be made. But payment will be made within 15 days after satisfactory completion of Work.
6. The Tenderers should quote their rates in figures as well as in words the amount tendered by them. The amount per each item should be worked out and requisite total should be given. All rates shall be quoted in proper form in the tender schedule enclosed. The rates quoted should be valid for **90 days**.
7. The PSC Pole, 11KV Horizontal Cross Arm items, 11KV Pin Insulators, Guy set etc. to be supplied should conform to the Technical Specifications of MESCOM, standards of IS.
8. The complete work of “Shifting of HT overhead line and RCC poles leading from Thannirbhavi road (near IOCL) to MK Agro Terminal outside Wharf area of NMPA” shall have guarantee period of **one year** after successful completion of work.
9. The Tenderer shall be responsible for making good of all the damages done during the work and has to employ skilled & competent workers for carrying out the work.
10. The Tenderer shall be responsible for taking precautionary measures for the safety of the workman working under them and the responsibility arising due to any mishap during the execution of work, the payment of any compensation etc., lies entirely on the part of the Contractor.
11. No tools, plant, Labour, equipment, transport, etc., required for the work will be supplied departmentally and contractor has to make his own arrangements.
12. The evaluation shall be done on the basis of total lowest value (L1) quoted. The GST element if any will not be considered for evaluation.
13. The acceptance of the tender will rest with competent authority of NMPA who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all of the tenders received without assigning any reason.
14. LIQUIDATED DAMAGES:
 - i. In case of delay in completion of the contract, liquidated damages (L.D) may be levied at the rate of 0.5% of the contract price plus applicable GST per week of delay, or part thereof subject to a maximum of 10 per cent of the contract price.

15. Department standard operating procedure will be shared with the successful bidder before commencing the work and an undertaking will be obtained for complying with the same. In case if the Contractor does have a defined SOP for carrying out the work, the same shall be scrutinized and approved by the Executive Engineer (E)-I for its applicability.
16. If the Tenderer after award of work/contract fail to execute the work in the specified allotted period, then the Tenderer shall be debarred for a period of three (3) years from participating for tenders at New Mangalore Port Authority.


Executive Engineer (E)
Electrical Division, NMPA

Seal and sign of Tenderer