

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजीनरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग-I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/281/CIVIL/Mtc-I/2022-TS dated 21.12.2022

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;
Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: जेएनसी अतिथि कक्ष में सभी खिड़कियों की दहलीज पर ग्रेनाइट स्लैब प्रदान करना
Name of work	: Providing Granite slab to the sill of all windows at JNC guest Room
अनुमानित लागत / Estimated Cost	: Rs.53,871.36
ईएमडी / EMD	: Rs.1,275.00
खुलने की तिथि / Date of opening	: 28.12.2022
समापन अवधि / Completion Period	: 60 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **28.12.2022** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorised representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.

The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

- 1.Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
- 2.Bank A/C No. 10205649448
- 3.IFSC Code: SBIN0002249
- 4.MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

Sd/-

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
खरखाव प्रभाग-I / Maintenance Division-I,

Date: 29.12.2022

The above subject work will be extend upto 04.01.2023 and submission on or before 3.00P.M on **04.01.2023**

Sd/-

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
खरखाव प्रभाग-I / Maintenance Division-I,

Date: 05.01.2023

The above subject work will be extend upto **11.01.2023** and submission on or before 3.00P.M on **11.01.2023**

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
खरखाव प्रभाग-I / Maintenance Division-I,

नव मंगलोर पत्तन प्राधिकरण / **NEW MANGALORE PORT AUTHORITY**
सिविल इंजिनरिंग विभाग / **DEPARTMENT OF CIVIL ENGINEERING**
अनुरक्षण प्रभाग -I / **MAINTENANCE DIVISION-I**
कोटेशन/QUOTATION No.5/281/CIVIL/Mtc-I/2022-TS dated 21.12.2022

BILL OF QUANTITIES

कार्य का नाम: जेएनपी अतिथि कक्ष में सभी खिड़कियों की दहलीज पर ग्रेनाइट स्लैब प्रदान करना Name of work: Providing Granite slab to the sill of all windows at JNC guest Room					
SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. ** Polished Granite stone slab Black, Cherry Red, Brown, Cat Eye, River Pink or equivalent.	15.00	Sqmt	2881.00	43,215.00
2	Re fabricating the Aluminium Window by reducing the window height of 10cm, including dismantling and cutting the section and glass, re fabricating the whole window and fixing the same in position . Including cost and conveyance of all materials, labours, etc., complete.	11.00	Sqmt	968.76	10,656.36
Amount put to quotation (excluding GST) Rs. :					53,871.36
ADD: % () Above the estimate amount put to quotation.				Rs.	
LESS: % () Below the estimate amount put to quotation				Rs.	
Total Amount Rs.					
Rupees					

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR