

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY  
सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING  
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/284/CIVIL/Mtc-I/2022-TS dated 20.02.2023

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: एक्स रे रूम और एल्युमिनियम को फाल्स सीलिंग प्रदान करना एनएमपी अस्पताल में विभाजन
Name of work	: Providing false ceiling to the x ray room and aluminium partition at NMP hospital
अनुमानित लागत / Estimated Cost	: Rs.26,693.00
ईएमडी / EMD	: Rs.630.00
खुलने की तिथि / Date of opening	: 27.02.2023
समापन अवधि / Completion Period	: 45 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **27.02.2023** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorised representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

  
कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),  
खरखाव प्रभाग-I / Maintenance Division-I,

**नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY**  
**सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING**  
**अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I**  
**कोटेशन/QUOTATION No.5/284 /CIVIL/Mtc-I/2022-TS dated 20.02.2023**

**BILL OF QUANTITIES**

कार्य का नाम: एक्स रे रूम और एल्युमिनियम को फाल्स सीलिंग प्रदान करना एनएमपी अस्पताल में विभाजन					
Name of work: Providing false ceiling to the x ray room and aluminium partition at NMP hospital					
SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Providing and fixing new 9mm PVC laminated false ceiling suspended with the frame work and accessories completed from the roof slab, beams etc. by means of aluminum angles, J bolts, Tee runners and edge trim etc. , cutting the openings for fixing light fittings, including cost of materials, labours, lead and lift finishing etc. complete as per specification.	15.00	SqM	1362.75	20,441.25
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate sections and other sections of approved make conforming to IS: 733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :For Fixed Portion: Powder coated aluminium (minimum thickness of powder coating 50 micron) including cost of materials, labour, usage charges of machinery complete as per specifications.	12.00	kgs	388.00	4,656.00
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with	2.00	SqM	798.00	1,596.00

	EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4.0 mm thickness (weight not less than 10kg/ m <sup>2</sup> ) including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.				
Amount put to quotation (excluding GST) Rs. :					<b>26,693.00</b>
<b>ADD:</b>	%( )				<b>Rs.</b>
Above the estimate amount put to quotation.					
<b>LESS:</b>	%( )				<b>Rs.</b>
Below the estimate amount put to quotation					
<b>Total Amount Rs.</b>					
Rupees					

Note: GST will be reimbursed as applicable

**SIGNATURE OF THE CONTRACTOR**