

NEW MANGALORE PORT TRUST
DEPARTMENT OF CIVIL ENGINEERING
MAINTENANCE DIVISION-II
QUOTATION No.22/129/MTC-II/2023-TS dated 01.08.2023

Sealed quotations are invited with EMD on percentage rate basis from the contractors having ESI, PF and GST Registration for the following work.

| | |
|-------------------------|---|
| Name of work | : Supply and laying of Granite for Flag mast area near main entrance gate at NMPA |
| Amount put to quotation | : Rs.1,64,104.10 |
| EMD Rs. | : Rs.3,900.00 |
| Date of opening | : 04.08.2023 |
| Completion Period | : 03 days |

The quotation shall be dropped in the tender box placed in **A.O. building Annexure block ground floor (Next to PRO office)** on or before 3.00P.M on 04.08.2023 and will be opened at 3.30 P.M on the same day in the presence of the quotationer or their authorised representatives. The estimate, Plan, specification and other particulars to be furnished may be seen in this office on any day during working hours.


The Contractor shall quote the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, cost and conveyance of all materials, tool and plants etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The EMD shall be paid through RTGS/NEFT to the following bank details in favour of the FA&CAO, NMPA. The copy of receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Center (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details:

Name of the Bank: State Bank of India, Panambur, Mangalore - 575010
Bank A/c No.: 10205649448, IFSC Code: SBIN0002249,
MICR Code: 575002011

The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. In the event of contractor backing out before the expiry of 90 days from the date of opening the offer or fails to adhere to the conditions stipulated herein and in the contract for on which the offer is deemed to have been submitted the EMD of the said firm will be forfeited to the New Mangalore Port Authority. The successful quotationer shall execute an Undertaking in the prescribed form on a stamp paper of required value.


Shashikanth P. Kodi
Executive Engineer
Maintenance Division -II

NEW MANGALORE PORT TRUST
DEPARTMENT OF CIVIL ENGINEERING
MAINTENANCE DIVISION-II
QUOTATION No. 22/129/MTC-II/2023-TS dated 01.08.2023

BILL OF QUANTITIES

| Name of work: Supply and laying of Granite for Flag Mast area near Main entrance gate at NMPA | | | | | |
|--|--|-------|------|-----------------|----------------|
| SL No | Description of items | Qty | Unit | Rate in Figures | Amount Rs. Ps. |
| 1 | Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab Black, Cherry Red, Brown, Cat Eye, River Pink or equivalent. | 23.00 | Sqm | 2881.00 | 66263.00 |
| 2 | Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite, black granite, ruby red or as directed by Engineer in charge in CM 1:3 (1 cement: 3 coarse sand) proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including cost of all | 19.00 | Sqm | 3073.00 | 58387.00 |

| | | | | | |
|---|--|-------|-----|---------|--------------------|
| | materials, mortar, labour, curing etc., complete. | | | | |
| 3 | Providing full nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM etc., complete as per specification | 28.00 | Mtr | 270.00 | 7560.00 |
| 4 | Engraving the Letter on the granite slab of required size of letter/logo/border including labour charges handling cost etc complete and as directed by Engineer in charge. | 4.90 | Sqm | 6509.00 | 31894.10 |
| Estimated amount put to quotation (excluding GST) Rs. : | | | | | 1,64,104.10 |
| ADD: % () Above the estimate amount put to quotation. | | | | | Rs.: |
| DEDUCT: % () Below the estimate amount put to quotation. | | | | | Rs.: |
| Total Amount Rs. | | | | | |
| Rupees----- | | | | | |

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR