

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY

सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING

अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.3/243/CIVIL/Mtc-I/2024-TS dated 28.05.2024

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: 5 एचपी, 15 एचपी, 30 एचपी और 40 एचपी की मरम्मत के लिए तत्काल कार्य एसटीपी और घाट के पंपों का स्थान और निराकरण, स्थानांतरण, आरसीएचडब्ल्यू कॉलोनी में 10 एचपी पंप की स्थापना
Name of work	: Urgent work for Repair of the 5HP, 15HP, 30HP & 40HP pumps of STP & Wharf Locations & Dismantling, Shifting, Installing of 10HP pump to RCHW Colony
अनुमानित लागत / Estimated Cost	: Rs.1,44,546/-
ईएमडी /EMD	: Rs.3,415.00
खुलने की तिथि /Date of opening	: 04.06.2024
समापन अवधि /Completion Period	: 45 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **04.06.2024** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorised representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.

The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan .The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
खरखाव प्रभाग-I / Maintenance Division-I,

नव मेंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I
कोटेशन/QUOTATION No.3/243/CIVIL/Mtc-I/2024-TS dated 28.05.2024

BILL OF QUANTITIES

कार्य का नाम: : 5 एचपी, 15 एचपी, 30 एचपी और 40 एचपी की मरम्मत के लिए तत्काल कार्य एसटीपी और घाट के पंपों का स्थान और निराकरण, स्थानांतरण, आरसीएचडब्ल्यू कॉलोनी में 10 एचपी पंप की स्थापना Name of work: Urgent work for Repair of the 5HP, 15HP, 30HP & 40HP pumps of STP & Wharf Locations & Dismantling, Shifting, Installing of 10HP pump to RCHW Colony					
SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	5.00HP motor rewinding, dismantling, removing of rusted bolt nut, scraping exchange assembling & trail run including all transportation, loading unloading, HOM, All complete as per the instructions of NMPA Engineer in Charge.	1.00	Job	10200.00	10,200.00
2	15HP water pumpset repairing , replacing 35mm oil coolant mechanical seal & bush, 6306 SKF bearing, overheating & 20W40 oil change, pump dismantling, removing of rusted boltnuts, scraping, exchange assembling & trail run including all transportation, loading unloading, HOM, All complete as per the instructions of NMPA Engineer in Charge.	1.00	Job	16800.00	16,800.00
3	40HP Kirloskar pumpset repair work with replacing new spider coupling set, S S Bush, 6305 SKF bearing and pumpset overheating, removing rusted boltnut, scraping, exchange motor assembling, trail run including all transportation, loading unloading, HOM, All complete as per the instructions of NMPA Engineer in Charge.	1.00	Job	30660.00	30,660.00
4	30.00HP Monoblock pump motor rewinding, Bearing work, Replacing Impeller, cooling fan, gland bush, Back Cover, bolt nuts, gland roof, Lath work & pump motor dismantling, removing of rusted bolt nut scraping exchange assembling & trial run including fixing and removing of standby 7.5HP pump including electrical connections starter etc. ,all transportation, loading unloading, Motor Connecting & Electrical work, HOM, All complete as per the instructions of NMPA Engineer in Charge.	1.00	Job	48890.00	48,890.00

5	Shifting the 10HP Submersible Pumpset from 1.2MLD STP to RCHW colony Sewage pump house and installing the pump with necessary materials like 2dia Tata B class pipe 12 feet, 16mm thick steel chain, 16mm thick D-cycle, 2" GI clamp, 5-8dia GI nut bolt with washer ,3core 6sqmm round cable and deploying cesspool and emptying the available sewage in pump, checking & removing the existing pump & fixing in position & lowering the repaired submersible pumpset. Removed of residual sand in pumping well/sump. All complete as per the instructions of NMPA Engineer in Charge.	1.00	Job	37996.00	37,996.00
Amount put to quotation (excluding GST) Rs. :					1,44,546.00
ADD: % () Above the estimate amount put to quotation. Rs.					
LESS: % () Below the estimate amount put to quotation Rs.					
Total Amount Rs.					
Rupees					

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR