

नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/359/CIVIL/Mtc-I/2024-TS dated 26.07.2024

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;
Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

| | |
|---------------------------------|---|
| कार्य का नाम; Name of work | : क्वार्टर की तत्काल मरम्मत। एनएमपीए कॉलोनी में नंबर 8, 9वां एवेन्यू (पोर्ट हाउस) : Urgent repairs to the Qtr. No. 8, 9th Avenue (Port House) at NMPA colony |
| अनुमानित लागत / Estimated Cost | : Rs. 1,60,298.68 |
| ईएमडी / EMD | : Rs. 3,783.00 |
| खुलने की तिथि / Date of opening | : 31.07.2024 |
| समापन अवधि / Completion Period | : 15 days |

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **31.07.2024** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favor of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.


कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
खरखाव प्रभाग-I / Maintenance Division-I,

नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजिनरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I
कोटेशन/ QUOTATION No.5/359/CIVIL/Mtc-I/2024-TS dated 26.07.2024

BILL OF QUANTITIES

| कार्य का नाम : क्वार्टर की तत्काल मरम्मत। एनएमपीए कॉलोनी में नंबर 8, 9वां एवेन्यू (पोर्ट हाउस) | | | | | |
|--|--|------------|-------------|------------------------|-----------------------|
| Name of work: Urgent repairs to the Qtr. No. 8, 9th Avenue (Port House) at NMPA colony | | | | | |
| SI No | Description of items | Qty | Unit | Rate in Figures | Amount Rs. Ps. |
| 1 | Supply of unskilled labour with necessary tools for cleaning the floor with acid wash inside the building in neat and tidy conditions as required by the department all complete. | 1.00 | LS | 5467.10 | 5,467.10 |
| 2 | Providing and fixing aluminium frames of section 20mm x 8 mm fitted with stainless steel powder coated net for openings, doors and partitions with extruded built up standard tubular sections of approved make, fixing with screws, removable type frames, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including, all complete as per architectural drawings and the directions of Engineer-in-charge | 10.00 | Sqm | 1956.15 | 19,561.50 |
| 3 | Providing and fixing on wall face un plasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 100 mm diameter | 10.00 | M | 291.00 | 2,910.00 |
| 4 | Providing & fixing window blinds with approved quality fabric for the zebra blinds, selected colour, pattern and design including all the necessary fittings as directed by the Engineer -in-charge. | 2.00 | Sqm | 2313.27 | 4,620.53 |
| 5 | Providing and fixing Soap/Shampoo Holder including cost and conveyance of all material, fixing charges, tools & plants and all other incidental charges etc. complete. | 2.00 | No. | 510.00 | 1,020.00 |
| 6 | Providing and fixing Towel Holder (Folding rack 24"-steel 202) including cost and conveyance of all material, fixing charges, tools & plants and all other incidental charges etc. complete. | 2.00 | No. | 1440.00 | 2,880.00 |
| 7 | Providing and fixing cloth drying unit with lowering and raising arrangements for a length of 8 ft with 6 rows of aluminium pipes, nylon ropes with all necessary accerories , labour transportation etc. all complete. | 1.00 | No. | 6,300.00 | 6,300.00 |

| | | | | | |
|---|---|--------|-----|---------|-------------|
| 8 | Providing stitching & fixing curtains of selected fabric with ring, belt, frills, welcrow etc. to the doors, windows and partition walls as directed by the Engineer -in-charge. | 50.00 | Sqm | 555.39 | 27,769.50 |
| 9 | KSRB 15-19.2 : Providing and applying spray painting (excluding priming coat) over concrete / masonry /asbestos cement sheet / plastered surfaces, metal surface with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.KSRB 15-19.2: do- spray painting in two coat | 40.00 | Sqm | 89.25 | 3,570.00 |
| 10 | Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 g/L as per specifications and as per directions of Engineer in charge. | 375.00 | Sqm | 53.00 | 19,875.00 |
| 11 | Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two coat applied @ 1.67 l/ 10 m ²) on existing cement paint surface including preparing the surface after thoroughly cleaning the surface to remove all dirt, dust and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. | 375.00 | Sqm | 105.00 | 39,375.00 |
| 12 | Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per m ² including pointing in white cement mixed with pigment of matching shade complete. | 15.00 | Sqm | 1106.00 | 16,590.00 |
| 13 | Providing and fixing to the required line and slope roofing with semi-corrugated fibre roofing sheets white colour day light sheet, fixed with self tapping screws with washers, over the existing purlins, rafters and trusses including cost of materials, labour, complete as per specification. | 19.00 | Sqm | 544.95 | 10,354.05 |
| Amount put to quotation (excluding GST) Rs. : | | | | | 1,60,298.68 |
| ADD: % () Above the estimate amount put to quotation. | | | | | Rs. |
| LESS: % () Below the estimate amount put to quotation | | | | | Rs. |
| Total Amount Rs. | | | | | |
| Rupees | | | | | |

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR