

नव मेंगलोर पत्तन प्राधिकरण / **NEW MANGALORE PORT AUTHORITY**
सिविल इंजिनियरिंग विभाग / **DEPARTMENT OF CIVIL ENGINEERING**
अनुरक्षण प्रभाग -I / **MAINTENANCE DIVISION-I**

कोटेशन / **QUOTATION No.2/455/CIVIL/Mtc-I/2023-TS dated 26.09.2024**

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;
Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	: गायों के लिए अस्थायी आश्रय उपलब्ध कराना
Name of work .	: Providing Temporary shelter for Cows
अनुमानित लागत / Estimated Cost	: Rs.1,50,566.65
ईएमडी / EMD	: Rs.3,560.00
खुलने की तिथि / Date of opening	: 03.10.2024
समापन अवधि / Completion Period	: 45 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **03.10.2024** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan .The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.


कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
रखरखाव प्रभाग-I / Maintenance Division-I,

नव मेंगलोर पत्तन प्राधिकरण / **NEW MANGALORE PORT AUTHORITY**
सिविल इंजिनियरिंग विभाग / **DEPARTMENT OF CIVIL ENGINEERING**
अनुरक्षण प्रभाग -I / **MAINTENANCE DIVISION-I**
कोटेशन/QUOTATION No.2/455/CIVIL/Mtc-I/2024-TS dated 26.09.2024

BILL OF QUANTITIES

कार्य का नाम: गायों के लिए अस्थायी आश्रय उपलब्ध कराना					
Name of work: Providing Temporary shelter for Cows					
SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m ³ and minimum compressive strength of 4.00 N/mm ² conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	20.00	Sqm	1231.00	24,620.00
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	15.00	Cum	266.00	3,990.00
3	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid, in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 Using 20 mm nominal size graded crushed coarse aggregates-Including the Formwork Charges	0.14	Cum	6217.00	870.38
4	Providing and Fabricating of GI pipe "B" class dia pipe verticle support of 100mm pipe as per the Department drawing, cutting, welding, gusset plates, bolts & nuts, applying 2 coats of painting of metal enamel paint over a coat of primer & conveyance of all materials, transportation to work site, cost of all labours, all tools, lead & lift, bolts & nuts, plates & erection, fixing charges etc complete as per specification	22.00	Rm	1087.26	23,919.72
5	Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and	8.50	Kgs	136.00	1,156.00

