

नव मंगलोर पतन प्राधिकरण / NEW MANGALORE PORT AUTHORITY  
सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING  
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.2/472/CIVIL/Mtc-1/2024-TS dated 16.12.2024

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी उन्हेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं;

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	
Name of work	: : डाइनिंग रूम में बॉल टाइल क्लैडिंग और पेंटिंग उपलब्ध करवाना एओबी, प्लम्परी एवं कैटिन का कामरा।
अनुमानित लागत / Estimated Cost	: Providing Wall Tile Cladding & Painting to the Dining Room of Canteen at AOB, NMPA.
ईएमडी / EMD	: Rs.1,63,251.00
खुलने की तिथि / Date of opening	: Rs.3,855.00
समापन अवधि / Completion Period	: 23.12.2024
	: 45 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **23.12.2024** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.

The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN0002249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),  
रखरखान प्रभाग-I / Maintenance Division-I,

*Shashi Kant*



**नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY**  
**सिविल इंजिनीरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING**  
**अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I**  
**कोटेशन/QUOTATION No.2/472 /CIVIL/Mtc-I/2024-TS dated 16.12.2024**

**BILL OF QUANTITIES**

**कार्य का नाम :** डाइनिंग रूम में बॉल टाइल क्लैडिंग और पेंटिंग उपलब्ध कराना एओबी, एनएमपीए में कैंटीन का कमरा  
**Name of work:** Providing Wall Tile Cladding & Painting to the Dining Room of Canteen at AOB, NMPPA

SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg/m <sup>2</sup> , including pointing in white cement mixed with pigment of matching shade complete...	46.00	Sqm	1106.00	50,876.00
2	Providing and fixing of Aluminium composite panel of approved make and colour for wall cladding on both sides of the existing aluminium partition. The panel should consist of 3mm thick non-halogenated FR grade mineral based polymer ( 2 hrs fire resistance as per ASTM E119-12 and clause B, S1, do as per ENT 13501-1sandwiched between 0.50 skins thick aluminium sheet making a total panel thickness of 4mm. The surfaces will be finished with PVDF based coating on topsides and service coating on reverse sides would be in polyester paint. The system shall be fixed using GI brackets, aluminium L cleats and stainless steel bolts and nuts complete with spring washer and cap nuts and all other necessary accessories, sealing shall be done with necessary rods etc.,complete For Straight Portion..	19.00	Sqm	3988.02	75,772.42
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 g/L approved brand and manufacture, including applying additional coats	310.00	Sqm	110.00	34,100.00

	wherever required to achieve even shade and colour. Two coats as per specifications and as per directions of Engineer in charge..				
	Amount put to quotation (excluding GST) Rs. :				
<b>ADD:</b>	% ( )				<b>1,60,748.42</b>
Above the estimate amount put to quotation.					
<b>LESS:</b>	% ( )				<b>Rs.</b>
Below the estimate amount put to quotation					
<b>Total Amount Rs.</b>					
<b>Rupees :</b>					

Note: GST will be reimbursed as applicable

**SIGNATURE OF THE CONTRACTOR**