

नव मंगलोर पोर्टन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन /QUOTATION No.4/189/CIVIL/Mtc-1/2024-TS dated 26.12.2024

निम्नलिखित कार्य के लिए प्रतिष्ठित एवं अनुभवी ठेकेदारों या फर्म से प्रतिशत दर के आधार पर मुहरबंद कोटेशन आमंत्रित किए जाते हैं:

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम, Name of work	: एम्एमडी कार्यालय और ट्रक टर्मिनल के सामने प्रस्तावित उद्यान के लिए कटिदार तार की बाड़ लगाना और लाल मिट्टी की आपूर्ति - भाग-ए : Barbed wire fencing and supply of red earth for the proposed garden In front of MMD office and Truck Terminal -Part-A
अनुमानित लागत /Estimated Cost	: Rs.1,49,755.02
ईएमडी /EMD	: Rs.3,535.00
खुलने की तिथि /Date of opening	: 02.01.2025
समापन अवधि /Completion Period	: 45 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **02.01.2025** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.


The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

NMPA Bank Details for remittance of Tender fee and EMD.

1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
2. Bank A/C No. 10205649448
3. IFSC Code: SBIN00022249
4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),
रखरखान प्रभाग-I / Maintenance Division-I,


नव मंगलोर पोर्टन प्राधिकरण / NEW MANGALORE PORT AUTHORITY
सिविल एंजिनरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I
कोटेशन/QUOTATION No.4/189/CIVIL/Mtc-I/2024-TS dated 26.12.2024

BILL OF QUANTITIES

कार्य का नाम: एमएमडी कार्यालय और ट्रक टर्मिनल के सामने प्रस्तावित उद्यान के लिए कोटेशन तार की बाड़ लगाना
 और लाल मिट्टी की आपूर्ति - भाग-ए

Name of work: Barbed wire fencing and supply of red earth for the proposed garden in front of MMD office and Truck Terminal -Part-A

SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	G.I Barbed Wire Fencing 1.8 m High Providing and fixing 1.8 m high GI barbed wire fencing with 2.4 m angle iron posts 50 mm x 50 mm x 6 mm placed every 3 m center to center founded in M15 grade cement concrete, 0.6 metre below ground level, every 15th post, last but one end post and corner post shall be struttled on both sides and end post on one side only and provided with 12 horizontal lines and 2 diagonals interwoven with horizontal wires, fixed with GI staples, turn buckles etc complete as per clause 808.	70.00	M	543.00	38,010.00
2	Finishing with Epoxy paint (two coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On concrete work including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	9.00	Sq.m	172.00	1,548.00
3	Supplying and fixing M15 grade precast cement concrete Kerb stones for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finished in line as per direction of Engineer in charge, including the cost of PCC 300 x 100 mm size.	70.00	M	489.51	34,265.70
4	Supply of red earth of approved quality from the approved quarry including loading and unloading, cost of labour, T&P and all other incidental charges etc. complete as directed by the dept	110.00	Cum	690.28	75,931.32
Amount put to quotation (excluding GST) Rs. :					1,49,755.02
ADD: % () Above the estimate amount put to quotation. Rs.					
LESS: % () Below the estimate amount put to quotation Rs.					
Total Amount Rs.					
Rupees :					

Note: GST will be reimbursed as applicable

SIGNATURE OF THE CONTRACTOR