

नव मंगलोर पोर्टन प्राधिकरण / NEW MANGALORE PORT AUTHORITY  
सिविल इंजिनियरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING  
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I

कोटेशन / QUOTATION No.5/384/CIVIL/Mtc-I/2024-TS dated 13.01.2025

निम्नलिखित कार्य के लिए प्रतिलिखित एवं अनुभवशील ठेकेदारों या फर्म से प्रतिलिखित दर के आधार पर मुहूर्तबंद कोटेशन आमंत्रित किए जाते हैं:

Sealed quotations are invited on percentage rate basis from the reputed and experienced contractors for the following work;

कार्य का नाम;	
Name of work .	:एनएमपीए कॉलोनी में 9वें एवेन्यू दरवाजा नंबर 4 के फ्लॉटियों में एल्युमीनियम कम्पोजिट डैन्ल किचन कैबिनेट और डेक्सिकन लॉन उपलब्ध कराना
अनुमानित लागत /Estimated Cost	:Providing Aluminium composite panel kitchen Cabinates and mexican lawn in the quarters at 9th Avenue Door no.4 at NMPA Colony
ईएमडी /EMD	: Rs.77,261.46
खुलने की तिथि /Date of opening	: Rs.1,825.00
समापन अवधि /Completion Period	: 20 .01.2025
	: 45 days

The quotation shall be dropped in the tender box placed in A.O. building ground floor on or before 3.00 P.M. on **20.01.2025** and will be opened at 3.30P.M on the same day in the presence of the bidders or their authorized representatives. The BOQ, specification and other particulars are enclosed. The NMPA reserves the right to accept or reject quotation without assigning reasons thereof.

The Earnest Money Deposit shall be paid through NEFT/RTGS in favour of FA&CAO, NMPA and copy of the NEFT/RTGS receipt shall be enclosed along with the quotation. The benefit of exemption of EMD to all Micro and Small Enterprises (MSE) shall be allowed. The proof of being MSE registered with District Industries Centers (DIC) shall be enclosed. The quotation without copy of receipt of RTGS/NEFT/Certificate will not be entertained.

- NMPA Bank Details for remittance of Tender fee and EMD.
1. Name of the Bank: State Bank of India, Panambur, Mangalore - 575 010.
  2. Bank A/C No. 10205649448
  3. IFSC Code: SBIN0002249
  4. MICR Code: 575002011

The Contractor shall write the percentage rate in figures as well as in words clearly in the enclosed BOQ. The percentage rate quoted shall be inclusive of labour, tool and plants, transportation, machinery etc. complete. GST will be reimbursed as applicable. Payment will be made after satisfactory completion of work and applicable taxes will be recovered from the bill.

The Contractor shall submit the quotation accompanied with covering letter on bidder's letter head having GST/Pan. The offer submitted should be open for acceptance for a period of 90 days from the date of opening the same. The successful bidder shall execute an agreement/undertaking in the prescribed form on a stamp paper of required value and sign all the pages of the contract form including Plan(s) enclosed to the same.

कार्यकारी अभियंता (सिविल) / Executive Engineer (Civil),  
रखरखान प्रभाग-I / Maintenance Division-1,



नव मंगलोर पत्तन प्राधिकरण / NEW MANGALORE PORT AUTHORITY  
सिविल इंजिनरिंग विभाग / DEPARTMENT OF CIVIL ENGINEERING  
अनुरक्षण प्रभाग -I / MAINTENANCE DIVISION-I  
कोटेशन/QUOTATION No.5/384/CIVIL/Mtc-1/2024-TS dated 13.01.2025

**BILL OF QUANTITIES**

कार्य का नाम: एनएमपीए कॉलोनी में 9<sup>वें</sup> एवेन्यू दरवाजा नंबर 4 के क्वार्टरों में एल्युमीनियम कम्पोजिट धैनाल फिनिश  
कैबिनेट और मैक्सिकन लॉन उपलब्ध कराना

Name of work: Providing Aluminium composite panel kitchen Cabinets and Mexican  
lawn in the quarters at 9th Avenue Door no.4 at NMPA Colony

SI No	Description of items	Qty	Unit	Rate in Figures	Amount Rs. Ps.
1	Dismantling the old existing wooden door shutters of the kitchen cabinets and Providing, fabricating, assembling and fixing in position aluminium shutters to the door frame using 50mmx25mm with wall thickness 1.4mm; aluminium sections and cut to length joint metred and corners grinded, the bottom rail and top rail hinged or pivoted, opening arrangements including providing and fixing standard approved accessories, such as Stainless steel 1set of SS Thali drawers, 2 sets of SS pull outs (3 each), handles, pivots: hinges PVC. or rubber gasket, SS ventilators, Aluminium composite sheet (ACP) of wooden grains colour, 3mm thick, air vents to the shutters, aluminium sections treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non-adherance of mortars or any other sticky materials, including cost of materials, fixtures, labour and HOW complete as per specifications. - using aluminium section powdered coated to a minimum of 60-70 microns with exterior durable pure polyester grade powder of approved quality..	4.50	Sqm	12475.88	56,141.46
2	Providing and laying Mexican lawn grass to the desired gradient by losing the existing soil surface, providing manure mixing with the soil and sand to the desired quantity, spreading over the surface and planting the lawn at 5cms spacing on all sides, cost shall be inclusive of all the materials, labour, Transport, T&P etc. all complete.	120.00	Sqm	176.00	21,120.00

Amount put to quotation (excluding GST) Rs. :	77,261.46
ADD: % ( ) Above the estimate amount put to quotation. Rs.	
LESS: % ( ) Below the estimate amount put to quotation Rs.	
Total Amount Rs.	
Rupees :	

Note: GST will be reimbursed as applicable

**SIGNATURE OF THE CONTRACTOR**