नव मगंलुर पत्तन प्राधिकरण
NEW MANGALORE PORT AUTHORITY
यांत्रिक अभियंता विभाग
Mechanical Engineering Department
इलेक्ट्रिकल इंजिनियरिंग डिविजन, पणंबूर, मंगलूर
Electrical Engineering Division
Panambur, Mangalore – 575010

E-mail: ele-section@nmpt.gov.in
GSTIN: 29AAALN0057A2ZG
Phone: 0824 2887750/740/73
Fax: 0824 2408200/2408300

No. 8/3/2026/Ele. Dvn/ETS.II/08/01

Date: 07.08.2026

To,

Sir,

Sub: -NMPA–EE (E) – "Supply, Installation, Testing, and Commissioning of 1kVA Offline UPS Systems with 100Ah Batteries for Pump Houses along with associated Electrical Wiring Works at NMPA" - Quotation invited - Reg.

Quotation in sealed covers superscribed as "Supply, Installation, Testing, and Commissioning of 1kVA Offline UPS Systems with 100Ah Batteries for Pump Houses along with associated Electrical Wiring Works at NMPA" invited in accordance with the instructions to the Tendered Terms & Conditions as detailed below, may please be submitted addressed to "**The Executive Engineer (Elec.), Electrical Division, Administration Building, New Mangalore Port Authority, Panambur, Mangalore- 575010"** not later than **3.00 PM on or before 13.08.2026**. Quotation will be opened on the same day at 3.30 PM in the presence of the tenderers who wish to be present.

Sl. No.	Item Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Supply, erecting, testing & commissioning of 1 KVA OFF Line UPS system for operation on 230 volts, 50 Hz AC supply with all accessories complete excluding battery and wiring complete.	5	Nos.		
2	Supply, Installation, Testing & commissioning of 12 V DC, 100AH batteries and supplying and fixing of poly propylene container for Maintenance Free Battery complete.	5	Nos.		
3	Supplying and fixing 20mm PVC Casing on the wall or ceiling using necessary materials like bends, junction boxes, elbows screws at an interval of 30mm as required.	20	Mtrs.		

4	Wiring for lighting circuit using one of 1.5 sq. mm FRLS PVC insulated copper wire 1100 volts multi strand copper wire.	90	Mtrs.		
5	Supplying and fixing surface mounting un breakable PVC modular box suitable for mounting modular switch plates on wall including necessary rawl plugs, machine screws etc complete. **a) 3 way.**	5	Nos.		
6	Supplying and fixing superior quality modular switch mounting plates with necessary supporting back plates with required no of screws, nuts complete existing PVC box. **a) 3 module**	5	Nos.		
6	Supplying and fixing of modular switch 6 A modular switch on existing board.	5	Nos.		
7	Supplying and fixing of modular 6A 3 way socket on existing board.	5	Nos.		
8	Supplying and fixing of 6A 3 pin top on existing board.	5	Nos.		
	Total				
	Applicable GST @ 18%				
	Grand Total				

TERMS & CONDITIONS:

1. The rate quoted for the items shall be firm and F.O.R destination basis. Please note that NMPA is not issuing any concessional C or D forms.

2. The Tenderer shall submit Valid Electrical Contractor License and GST Registration Certificate along with their offer, without which the offer is liable for rejection.

3. Applicable GST will be paid as extra as per actual.

4. The time allowed for completion of work is **30 days** from the date of issue of work order.

5. The carried out work shall have one year Guarantee from the date of handing over after satisfactory completion of work.

6. Please note that no advance payment will be made. But payment will be made within 15 days after satisfactory completion of Work.

7. Offer shall be submitted in NMPA format only along with Terms & Conditions of Enquiry. Offer submitted in other format will not be considered for evaluation and liable for rejection.

8. The Tenderers should quote their rates in figures as well as in words the amount tendered by them. The amount per each item should be worked out and requisite total should be given. All rates shall be quoted in proper form in the tender schedule enclosed. The rates quoted should be valid for **90 days**.

9. The Tenderer shall be responsible for making good of all the damages done during the work and has to employ skilled & competent workers for carrying out the work.

10. The Tenderer shall be responsible for taking precautionary measures for the safety of the workman working under them and the responsibility arising due to any mishap during the execution of work, the payment of any compensation etc., lies entirely on the part of the Contractor.

11. No tools, plant, Labour, equipment, transport, etc., required for the work will be supplied departmentally and contractor has to make his own arrangements.

12. The evaluation shall be done on the basis of total lowest value (L1) quoted. The GST element if any will not be considered for evaluation.

13. The acceptance of the tender will rest with competent authority of NMPA who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all of the tenders received without assigning any reason.

14. LIQUIDATED DAMAGES:
    i. In case of delay in completion of the contract, liquidated damages (L.D) may be levied at the rate of 0.5% of the contract price plus applicable GST per week of delay, or part thereof subject to a maximum of 10 per cent of the contract price.

15. Department standard operating procedure will be shared with the successful bidder before commencing the work and an undertaking will be obtained for complying with the same. In case if the Contractor does have a defined SOP for carrying out the work, the same shall be scrutinized and approved by the Executive Engineer (E)-I for its applicability.

16. If the Tenderer after award of work/contract fail to execute the work in the specified allotted period, then the Tenderer shall be debarred for a period of two (2) years from participating for tenders at New Mangalore Port Authority.

Sd/-
Executive Engineer (E)
Electrical Division, NMPA

Seal and sign of Tenderer